PROJ. REFERENCE NO.	SHEET NO.
R-2915C	X-F

STATE OF NORTH CAROLINA
DIVISION OF HIGHWA

Note: Earthwork quantities are calculated by the Roadway Design Unit. These earthwork quantities are based in part on subsurface data provided by the Geotechnical Engineering Unit.

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station L_DET(RT1)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
271+00.00000	3	1
271+50.00000	6	4
272+00.00000	512	6
272+50.00000	988	6
273+00.00000	1043	4
273+50.00000	919	1
274+00.00000	398	0
274+50.00000	43	0
275+00.00000	0	0
275+50.00000	0	0
276+00.00000	0	0
276+50.00000	0	0
277+00.00000	0	0
277+50.00000	0	0
278+00.00000	0	0
278+50.00000	0	0
279+00.00000	0	0
279+50.00000	0	2
280+00.00000	0	2
280+50.00000	0	0
281+00.00000	0	0
281+50.00000	0	0
282+00.00000	1	1
282+50.00000	1	1
283+00.00000	0	0
283+50.00000	1	1
284+00.00000	3	3
284+50.00000	2	2

Station L_DET(RT2)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
284+50.00000	0	0
285+00.00000	0	0
285+50.00000	4	4
286+00.00000	15	15
286+50.00000	63	63
287+00.00000	54	54
287+50.00000	7	7
288+00.00000	11	11
288+50.00000	28	28
289+00.00000	53	53
289+50.00000	46	46
290+00.00000	16	16
290+50.00000	0	0
291+00.00000	0	0
291+50.00000	0	0
292+00.00000	0	0
292+50.00000	0	0
293+00.00000	0	0
293+50.00000	0	0
294+00.00000	0	0
294+50.00000	0	0

Station L_DET(RT2)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
295+00.00000	0	0
295+50.00000	0	0
296+00.00000	0	0
296+50.00000	0	0
297+00.00000	0	0
297+50.00000	0	0
298+00.00000	0	0
298+50.00000	0	0

Station L_XO1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+00.00000	0	0
11+50.00000	17	14
12+00.00000	33	23
12+50.00000	46	22
13+00.00000	46	27
13+50.00000	30	66
14+00.00000	10	377
14+50.00000	3	1160
15+00.00000	4	834
15+50.00000	20	1
16+00.00000	308	1
16+50.00000	1608	2
17+00.00000	3613	2
17+50.00000	5330	1
18+00.00000	5770	0
18+50.00000	4112	0
19+00.00000	1883	0
19+50.00000	1813	0
20+00.00000	3426	0
20+35.00000	3034	0

Station L_XO3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00000	0	0
10+50.00000	0	11
11+00.00000	1	7
11+50.00000	5	3
12+00.00000	12	1
12+50.00000	25	0
13+00.00000	54	0
13+50.00000	70	0
14+00.00000	69	0
14+50.00000	79	0
15+00.00000	90	0
15+50.00000	96	0
16+00.00000	96	0
16+45.77000	85	0

Station L_DET2(RT)	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
374+50.00000	0	0
375+00.00000	10	31
375+50.00000	20	84
376+00.00000	20	121
376+50.00000	20	143
377+00.00000	19	121
377+50.00000	19	72
378+00.00000	18	57
378+50.00000	18	44
379+00.00000	19	15
379+50.00000	19	9
380+00.00000	9	18