

NOTES

ASSUMED LIVE LOAD = HL-93 OR ALTERNATE LOADING.

THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS.

THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.

FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.

FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.

FOR FALSEWORK AND FORMWORK. SEE SPECIAL PROVISIONS.

FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.

FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.

THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH "HEC 18-EVALUATING SCOUR AT BRIDGES."

FOR PLACING LOAD ON STRUCTURE MEMBERS, SEE SPECIAL PROVISIONS.

IN AS MUCH AS THE PAINT SYSTEM ON THE EXISTING STRUCTURAL STEEL CONTAINS LEAD, THE CONTRACTOR'S ATTENTION IS DIRECTED TO ARTICLE 107-1 OF THE STANDARD SPECIFICATIONS. ANY COSTS RESULTING FROM COMPLIANCE WITH APPLICABLE STATE OR FEDERAL REGULATIONS PERTAINING TO HANDLING OF MATERIALS CONTAINING LEAD BASED PAINT SHALL BE INCLUDED IN THE BID PRICE FOR "REMOVAL OF EXISTING STRUCTURE AT STATION 68+25.60 -L-".

PRESTRESSED CONCRETE DECK PANELS MAY BE USED IN LIEU OF METAL STAY-IN-PLACE FORMS IN ACCORDANCE WITH ARTICLE 420-3 OF THE STANDARD SPECIFICATIONS.

REMOVABLE FORMS MAY BE USED IN LIEU OF METAL STAY-IN-PLACE FORMS IN ACCORDANCE WITH ARTICLE 420-3 OF THE STANDARD SPECIFICATIONS.

NEEDLE BEAMS WILL NOT BE ALLOWED UNLESS OTHERWISE CALLED FOR ON THE PLANS OR APPROVED BY THE ENGINEER.

THE CLASS AA CONCRETE IN THE BRIDGE DECK SHALL CONTAIN FLY ASH OR GROUND GRANULATED BLAST FURNACE SLAG AT THE SUBSTITUTION RATE SPECIFIED IN ARTICLE 1024-1 AND IN ACCORDANCE WITH ARTICLES 1024-5 AND 1024-6 OF THE STANDARD SPECIFICATIONS. NO PAYMENT WILL BE MADE FOR THIS SUBSTITUTION AS IT IS CONSIDERED INCIDENTAL TO THE COST OF THE REINFORCED CONCRETE DECK SLAB.

THE MATERIAL SHOWN IN THE CROSS-HATCHED AREA ON SHEET S-1 SHALL BE EXCAVATED FOR A DISTANCE OF 63 FT.RIGHT AND 11.75 FT.LEFT OF RIGHT LANE CONTROL LINE AT END BENT 1 AND A DISTANCE OF 35 FT.RIGHT AND 23.5 FT. LEFT OF RIGHT LANE CONTROL LINE AT END BENT 2 AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR UNCLASSIFIED STRUCTURE EXCAVATION. SEE SECTION 412 OF THE STANDARD SPECIFICATION. EXCAVATION AREA SHOULD BE SLOPED 2% TOWARDS CREEK.

THE EXISTING STRUCTURE CONSISTING OF 3 SIMPLE SPANS @ 40'EACH WITH A CLEAR ROADWAY WIDTH OF 26'-0" AND CONCRETE DECK ON I-BEAMS; SUBSTRUCTURE: END BENTS CONSISTING OF CONCRETE CAP ON STEEL PILES; INTERIOR BENTS CONSISTING OF CONCRETE CAP, COLUMNS AND FOOTINGS LOCATED AT THE PROPOSED SITE SHALL BE REMOVED. THE EXISITNG BRIDGE IS PRESENTLY NOT POSTED FOR LOAD LIMIT. SHOULD THE STRUCTURAL INTEGRITY OF THE BRIDGE DETERIORATE DURING CONSTRUCTION OF THE PROPOSED BRIDGE, A LOAD LIMIT MAY BE POSTED AND MAY BE REDUCED AS FOUND NECESSARY DURING THE LIFE OF THE PROJECT.

THE SUBSTRUCTURE OF THE EXISTING BRIDGE INDICATED ON THE PLANS IS FROM THE BEST INFORMATION AVAILABLE. SINCE THIS INFORMATION IS SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT OF TRANSPORTATION FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN THE EXISTING BRIDGE SUBSTRUCTURE SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

REMOVAL OF THE EXISTING BRIDGE SHALL BE PERFORMED IN A MANNER THAT PREVENTS DEBRIS FROM FALLING INTO THE WATER. THE CONTRACTOR SHALL SUBMIT DEMOLITION PLANS FOR REVIEW AND REMOVE THE BRIDGE IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS.

FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.

AT THE CONTRACTOR'S OPTION, AND UPON REMOVAL OF THE CAUSEWAYS, THE CLASS II RIP RAP USED IN THE CAUSEWAYS MAY BE PLACED AS RIP RAP SLOPE PROTECTION. SEE SPECIAL PROVISIONS FOR CONSTRUCTION, MAINTENANCE AND REMOVAL OF TEMPORARY ACCESS AT STATION 68+25.60 -L-.

THE LOCATION OF THE CONSTRUCTION JOINT IN THE DRILLED PIERS IS BASED ON AN APPROXIMATE GROUND LINE ELEVATION. IF THE CONSTRUCTION JOINT IS ABOVE THE ACTUAL GROUND ELEVATION, THE CONTRACTOR SHALL PLACE THE CONSTRUCTION JOINT 1 FT. BELOW THE GROUND LINE.

FOR ASBESTOS ASSESSMENT FOR BRIDGE DEMOLITION AND RENOVATION ACTIVITIES, SEE SPECIAL PROVISIONS.

HYDRAULIC DATA

DESIGN DISCHARGE FREQUENCY OF DESIGN FLOOD

OOD = 50 YRS. ATION = 665.4

DESIGN HIGH WATER ELEVATION
DRAINAGE AREA
BASE DISCHARGE (Q100)
BASE HIGH WATER ELEVATION

= 16.4 SQ.MI. = 5,200 C.F.S. = 665.86

= 4,700 C.F.S.

= 13,200 C.F.S. = 500+ YRS.

= 670.5

OVERTOPPING FLOOD DATA

OVERTOPPING DISCHARGE FREQUENCY OF OVERTOPPING FLOOD OVERTOPPING FLOOD ELEVATION

——— TOTAL BILL OF MATERIAL ———														
	CONSTRUCTION, MAINTENANCE AND REMOVAL OF TEMPORARY ACCESS	REMOVAL OF EXISTING STRUCTURE	3'-6"DIA. DRILLED PIERS IN SOIL	3'-6"DIA. DRILLED PIERS NOT IN SOIL	PERMANENT STEEL CASING FOR 3'-6"DIA. DRILLED PIER	SID INSPECTIONS	SPT TESTING	l CSL I	UNCLASSIFIED STRUCTURE EXCAVATION	REINFORCED CONCRETE DECK SLAB	GROOVING BRIDGE FLOORS	CLASS A CONCRETE	BRIDGE APPROACH SLABS	REINFORCING STEEL
	LUMP SUM	LUMP SUM	LIN.FT.	LIN.FT.	LIN.FT.	EACH	EACH	EACH	LUMP SUM	SQ.FT.	SQ.FT.	CU. YDS.	LUMP SUM	LBS.
SUPERSTRUCTURE										5,124	4,930		LUMP SUM	
END BENT 1												40.0		5,003
BENT 1			4.0	49.0	23.2	2	4					31.7		8,624
BENT 2			46.0	27.0		2	4					30.9		9,578
END BENT 2												40.5		4,949
TOTAL	LUMP SUM	LUMP SUM	50.0	76.0	23.2	4	8	2	LUMP SUM	5,124	4,930	143.1	LUMP SUM	28,154

TOTAL BILL OF MATERIAL — RIP RAP GEOTEXTILE PRESTRESSE COLUMN HP 12X53 THREE BAR CONCRETE ELASTOMERI **ASBESTOS** CLASS II FOR STEEL PILES METAL RAIL BARRIER RAIL ASSESSMENT REINFORCING CONCRETE BEARINGS (2'-0" THICK) DRAINAGE **GIRDERS** STEEL NO. LIN. FT. NO. LIN. FT. LIN.FT. LUMP SUM LIN.FT. TONS SQ. YDS. LUMP SUM 12 502.667 **SUPERSTRUCTURE** LUMP SUM 120.32 128.22 LUMP SUM END BENT 1 160 180 BENT 1 1.401 BENT 2 1,769 END BENT 2 165 145 160 3,170 12 | 502.667 255 305 340 LUMP SUM LUMP SUM TOTAL 120.32 128.22

PROJECT NO. U-3440

CABARRUS COUNTY

STATION: 68+25.60 -L-

SHEET 3 OF 3

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

GENERAL DRAWING

FOR BRIDGE OVER IRISH BUFFALO CREEK ON NC 3 BETWEEN SR 1639 AND SR 1643

SHEET NO

S2-3

TOTAL SHEETS

(RIGHT LANE)

REVISIONS

NT NOT CONSIDERED

NO. BY: DATE: NO. BY: DATE:

SEAL 031480 SEAL 031480 Poward R. Smith, Jr EDC877061748490....

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

H. B. DESAI

R. P. PATEL

DESIGN ENGINEER OF RECORD: T.R. PETERSON DATE: 6/20/16

DRAWN BY :

CHECKED BY : _

DATE : 4/7/16

_ DATE : 4/26/16