



BAGGED STONE AND PIPE SHALL BE PLACED IMMEDIATELY AFTER COMPLETION OF END BENT EXCAVATION. PIPE MAY BE EITHER CONCRETE, CORRUGATED STEEL, CORRUGATED ALUMINUM ALLOY, OR CORRUGATED PLASTIC. PERFORATED PIPE WILL NOT BE ALLOWED.


BAGGED STONE SHALL REMAIN IN PLACE UNTIL THE ENGINEER DIRECTS THAT IT BE REMOVED. THE CONTRACTOR SHALL REMOVE AND DISPOSE OF SILT ACCUMULATIONS AT BAGGED STONE WHEN SO DIRECTED BY THE ENGINEER. BAGS SHALL BE REMOVED AND REPLACED WHENEVER THE ENGINEER DETER-MINES THAT THEY HAVE DETERIORATED AND LOST THEIR EFFECTIVENESS.

NO SEPARATE PAYMENT WILL BE MADE FOR THIS WORK AND THE ENTIRE COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR THE SEVERAL PAY ITEMS.

TEMPORARY DRAINAGE AT END BENT








HP 12 X 53 STEEL PILES

No. 6

90 LIN.FT



PROJECT NO. U-3440 CABARRUS STATION: 68+25.60 -L-

SHEET 3 OF 3

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

SUBSTRUCTURE

END BENT 1

(RIGHT LANE)

SHEET NO **REVISIONS** S1-27 DATE: DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED BY:

CONST. JT.—	-#4 U1	#4 V1 NO (NIW)	
4-#4 B3			
4-#10 B1		4-#4 B2 @ 4" CTS.	<u> </u>
#4 B2 (EA.FACE)		OVER PILES	ا ا
#4 B2 (EA.FACE)	T #4 B8 >		
#4 B2 (EA.FACE)		<u> </u>	
#4 B2 (EA.FACE)		9 ~	0,7 4'-0" (MIN.)
#4 B2 (EA.FACE)		#4 S1	2'-0"
2-#10 B1 <u>2"CL.(TYP.)</u>		<u> </u>	
FILL FACE 2'-0"Ø CONC. COLLAR (TYP.) Physical Picture of the control of the con	1'-2" 1'-10\(\frac{1}{2}\)" 3'-9"	2-#10 B1	

SECTION A-A

_ DATE : 4/2016 _ DATE : 4/2016 J.D. HAWK CHECKED BY : K.D. LAYNE DESIGN ENGINEER OF RECORD: T.R. PETERSON DATE: 6/2016

17-AUG-2016 08:51
R:\Structures\Plans\Str02\U-3340_SD_E*_02.dgn
jpadams

STR. #2

Donald K. Smith, Ir