

**STATE OF NORTH CAROLINA
 DIVISION OF HIGHWAYS**

**PAVEMENT REMOVAL SUMMARY
 IN SQUARE YARDS**

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	ASPHALT REMOVAL	ASPHALT BREAKUP	CONCRETE REMOVAL	CONCRETE BREAKUP
-L-	16+50.00	25+48.04	LT	707.80			
-L-	38+92.99	41+91.29	LT	50.55			
-L-	46+01.46	46+20.00	LT	3.13			
-L-	46+54.93	48+43.64	LT	48.10			
-L-	49+79.00	51+06.03	LT	52.90			
-L-	51+36.33	64+61.09	LT	1914.24			
-L-	69+86.90	79+82.00	LT	1293.17			
-L-	90+17.98	93+50.00	LT	462.05			
-L-	128+86.78	136+39.38	LT	489.14			
-L-	144+99.76	151+08.61	LT	292.14			
-L-	151+25.12	154+35.04	LT	105.88			
-L-	154+72.16	156+34.94	LT	18.09			
-L-	203+28.41	206+16.12	LT	109.06			
-L-	96+33.23	128+71.51	CL	7123.25			
-L-	168+35.87	173+14.31	CL	713.14			
-L-	33+52.38	37+47.74	RT	207.38			
-L-	45+83.29	48+43.91	RT	80.68			
-L-	49+79.32	50+84.51	RT	59.26			
-L-	85+20.52	90+01.46	RT	1549.55			
-L-	44+62.22	(Y1REV)	LT	294.29			
-L-	45+70.00	(Y1REV)	LT	161.18			
-DRV3-	10+20.00	10+30.00	CL	22.09			
DET 2	10+00.00	11+70.36		135.97			
DET 2	11+70.36	20+02.16		1848.44			
DET 2	20+02.16	21+65.34		138.50			
TEMP DRIVE CONNECT DET 2				58.94			
L	24+69.00	25+50.00	LT	20.44			
L	78+70.00	80+00.00	LT	58.78			
L	94+20.00	98+01.00	LT	151.67			
L	128+88.00	129+54.00	LT	16.44			
L	139+20.00	146+66.00	RT	1165.00			
L	98+08.00	103+89.00	RT	191.11			
L	141+64.00	146+20.00	LT	36.67			
TOTAL:				19579.03			
SAY:				19700.00			

SHOULDER BERM GUTTER SUMMARY

LINE	Station	Station	LENGTH
-L- RT	16+50.00	32+00.00	1550
-L- RT	34+26.00	37+91.00	365
-L- RT	62+10.00	66+50.00	440
-L- RT	69+50.00	84+00.00	1450
-L- RT	92+10.00	95+75.00	365
-L- RT	128+35.00	138+00.00	965
-L- RT	148+25.00	153+05.00	480
-L- LT	151+75.00	153+50.00	175
-L- RT	163+15.00	165+00.00	185
-L- RT	170+30.00	172+30.00	200
TOTAL:			6175
SAY:			6200

RETAINING WALL SUMMARY

LINE	Station	Station	LENGTH	AREA (SF)
-L- RT	18+00.00	23+00.00	500.00	10700.00
-L- RT	26+61.00	31+75.00	514.00	7800.00
-L- RT	54+77.16	57+05.00	227.84	3700.00
-L- RT	58+00.00	62+10.00	410.00	11300.00
-L- RT	71+70.00	81+80.00	1010.00	31000.00
-L- RT	92+10.00	95+75.00	365.00	8000.00
-L- RT	128+35.00	133+35.00	500.00	13000.00
-L- RT	148+25.00	149+50.00	125.00	1500.00
-L- RT	150+50.00	153+05.00	255.00	3500
TOTAL:				90500.00
SAY:				90500.00

EXPRESSWAY GUTTER SUMMARY

LINE	Station	Station	LENGTH
-L- LT	30+50.00	44+60.00	1410.00
-L- LT	55+00.00	61+00.00	600.00
-L- LT	65+00.00	69+55.00	455.00
-L- LT	81+00.00	84+10.00	340.70
-L- LT	84+45.00	98+03.00	1336.69
-L- LT	122+00.00	132+21.81	1021.81
-L- LT	138+00.00	141+30.00	330.00
-L- LT	165+30.00	167+80.00	250.00
-L- LT	181+43.00	184+78.90	335.90
-L- LT	192+92.00	199+68.00	676.00
-L- LT	203+45.00	207+68.00	423.00
TOTAL:			7179.1
SAY:			7200