DocuSign Envelope ID: 7AD0FD6A-ABB0-4491-A5D2-C295637C38DC

8/17/99

PROJECT REFERENCE NO.	SHEET NO.
R–4753	PMP–2

NORTH CAROLINA PROFESSIONAL SEAL 24416 ENGINEER SCOTT CLARK

Scott Clark
D22FB20CCE9F457...
11/18/2016

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PAVEMENT MARKING SCHEDULE

PAVEMENT MARKING LINES

---------- POLYUREA (4")

VA - WHITE EDGELINE
VD - 3 ft. - 9 ft./SP WHITE MINISKIP
VE - WHITE SOLID LANE LINE
VI - YELLOW DOUBLE CENTER
V8 - 2 ft. - 6 ft./SP WHITE MINISKIP

---------- THERMOPLASTIC (8", 90 MIL)

TP - YELLOW DIAGONAL

---------- THERMOPLASTIC (24", 120 MIL)

T2 - WHITE STOP BAR

PAVEMENT MARKING SYMBOLS

---------- THERMOPLASTIC SYMBOLS (90 MIL)

UA - LEFT TURN ARROW

UB - RIGHT TURN ARROW

UJ - BICYCLE SYMBOL, HEATED-IN-PLACE

UK - BICYCLE STRAIGHT ARROW, HEATED-IN-PLACE

---------- COLD APPLIED PLASTIC SYMBOLS

DA- LEFT TURN ARROW

9/15/2016
G:\2016\160923_NCDOT_R4753JacksonCo\RDESIGN\03_CADD\PLANS\PM\160923_09_PM_02.dgn
RAVENBURT/sclark