



DRAWN BY :	E.C.PHE	LPS/VXN	DATE : <u>8-5-16</u>
CHECKED BY :	н.т.	BARBOUR	DATE : <u>8-8-16</u>
DESIGN ENGINEER	OF RECORD:	A.M.LEE	DATE : <u>9-16</u>

+

+

SCHEDULE				BAR SCHEDULE					
STAGE I			STAGE II						
SIZE	TYPE	LENGTH	WEIGHT	BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
#4	1	6'-6″	664	A1	67	#4	1	6′-6″	291
# 5	1	6'-3"	997	A2	67	# 5	1	6′-3″	437
# 6	STR	10'-11"	1230	A150	32	# 6	STR	10'-11"	525
# 6	STR	8'-6"	13	A151	1	# 6	STR	9'-0"	14
# 6	STR	5′-2″	8	A152	1	#6	STR	5′-8″	9
# 6	STR	1'-11"	3	A153	1	# 6	STR	2'-4"	4
# 7	STR	10'-11"	1674	A250	32	#7	STR	10'-11"	714
# 7	STR	8'-6"	17	A251	1	#7	STR	9'-0"	18
# 7	STR	5′-2″	11	A252	1	#7	STR	5′-8″	12
# 7	STR	1'-11"	4	A253	1	#7	STR	2'-4"	5
# 4	STR	6'-11"	416	B1	40	#4	STR	6'-11"	185
#4	STR	5'-4"	545	B2	67	#4	STR	5′-4″	239
#4	STR	24'-10"	1261	C2	76	#4	STR	11'-2"	567
# 6	STR	1'-10"	33	D1	ტ	# 6	STR	1'-10"	17
# 6	STR	1'-4"	16	D2	4	# 6	STR	1'-4"	8
# 4	STR	11'-2"	15	G1	2	#4	STR	11'-2"	15
# 8	STR	11'-2"	179	S2	6	# 8	STR	11'-2"	179
STEEL = 7,086 LBS REINFORCING STEEL = 3,239 LBS					LBS				

-	STAGE II
NTITIES	STRUCTURE QUANTITIES
40.9 C.Y. 8.2 C.Y. 1.9 C.Y. 51.0 C.Y.	CLASS A CONCRETE BARREL @0.913CY/FT18.0 C.Y. WINGS ETC8.2 C.Y. SILLS/BAFFLES1.0 C.Y. TOTAL27.2 C.Y.
7,086 LBS. 466 LBS. 7,552 LBS.	REINFORCING STEEL BARREL
LUMP SUM	CULVERT EXCAVATION LUMP SUM
TERIAL 48 TONS	FOUNDATION CONDITIONING MATERIAL 21 TONS

PROJECT NO. <u>R-4753</u> <u>JACKSON</u> COUNTY STATION: 168+42.00 -L- SHEET 5 OF 7							
STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION RALEIGH SEAL 17230 MONETER S. ARHING S. ARHING DOCUSIGNED by: Wall Graft							
4139C12A32AB406 10/18/2016	REVISIONS SHEET NO.						
DOCUMENT NOT CONSIDERED	NO. BY:	DATE:	NO. BY:	DATE:	C-12		
FINAL UNLESS ALL SIGNATURES COMPLETED	1 2		3 4		TOTAL SHEETS 14		
	CULVERT	*2					