


BENCHMARK #1 : RR SPIKE SET IN 12" Ø GUM TREE 46.77' RT. OF STA. 11+14.96 -L-, EL. 104.80



FOR UTILITY INFORMATION, SEE UTILITY PLANS & SPECIAL PROVISIONS.

**LOCATION SKETCH**

**NOTES:**


- ASSUMED LIVE LOAD = HL 93 OR ALTERNATE LOADING.
- THIS BRIDGE HAS BEEN DESIGNED IN ACCORDANCE WITH THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS.
- FOR OTHER DESIGN DATA AND GENERAL NOTES, SEE SHEET SN.
- FOR EROSION CONTROL MEASURES, SEE EROSION CONTROL PLANS.
- THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH "HEC 18-EVALUATING SCOUR AT BRIDGES".
- THE EXISTING STRUCTURE CONSISTING OF 3 SPANS (1 @ 17'-9", 1 @ 17'-2" (1 @ 17'-8") WITH A CLEAR ROADWAY WIDTH OF 24'+0" AND A REINFORCED CONCRETE DECK ON 19 LINES OF 6' X 13 1/2" TIMBER JOISTS AND END BENTS AND BENTS CONSIST OF TIMBER CAPS AND TIMBER PILES. THE EXISTING STRUCTURE, LOCATED AT THE SITE OF THE PROPOSED BRIDGE SHALL BE REMOVED. THE EXISTING BRIDGE IS PRESENTLY POSTED FOR LOAD LIMIT. SHOULD THE STRUCTURAL INTEGRITY OF THE BRIDGE DETERIORATE DURING CONSTRUCTION OF THE PROPOSED BRIDGE, A LOAD LIMIT MAY BE POSTED AND MAY BE REDUCED AS FOUND NECESSARY DURING THE LIFE OF THE PROJECT.
- THE CONTRACTOR SHALL PROVIDE INDEPENDENT ASSURANCE SAMPLES OF REINFORCING STEEL AS FOLLOWS: FOR PROJECTS REQUIRING UP TO 400 TONS OF REINFORCING STEEL, ONE 30 INCH SAMPLE OF EACH SIZE BAR USED, AND FOR PROJECTS REQUIRING OVER 400 TONS OF REINFORCING STEEL, TWO 30 INCH SAMPLES OF EACH SIZE BAR USED. THE BARS FROM WHICH THE SAMPLES ARE TAKEN MUST THEN BE SPLICED WITH REPLACEMENT BARS OF THE SIZE AND LENGTH OF THE SAMPLE, PLUS A MINIMUM LAP SPLICE OF THIRTY BAR DIAMETERS. PAYMENT FOR THE SAMPLES OF REINFORCING STEEL SHALL BE CONSIDERED INCIDENTAL TO VARIOUS PAY ITEMS.
- THE MATERIAL SHOWN IN THE CROSS-HATCHED AREA SHALL BE EXCAVATED FOR A DISTANCE OF 30 FT. RIGHT OF THE CENTERLINE ROADWAY AT END BENT No. 1 AND FOR A DISTANCE OF 30 FT. EACH SIDE OF THE CENTERLINE ROADWAY AT END BENT No. 2 AS DIRECTED BY THE ENGINEER. THIS WORK WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FOR UNCLASSIFIED STRUCTURE EXCAVATION. SEE SECTION 412 OF THE STANDARD SPECIFICATIONS.
- THE SUBSTRUCTURE OF THE EXISTING BRIDGE INDICATED ON THE PLANS IS FROM THE BEST INFORMATION AVAILABLE. SINCE THIS INFORMATION IS SHOWN FOR THE CONVENIENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL HAVE NO CLAIM WHATSOEVER AGAINST THE DEPARTMENT OF TRANSPORTATION FOR ANY DELAYS OR ADDITIONAL COST INCURRED BASED ON DIFFERENCES BETWEEN THE EXISTING BRIDGE SUBSTRUCTURE SHOWN ON THE PLANS AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.
- REMOVAL OF THE EXISTING BRIDGE SHALL BE PERFORMED IN A MANNER THAT PREVENTS DEBRIS FROM FALLING INTO THE WATER. THE CONTRACTOR SHALL REMOVE THE BRIDGE AND SUBMIT PLANS FOR DEMOLITION IN ACCORDANCE WITH ARTICLE 402-2 OF THE STANDARD SPECIFICATIONS.
- THIS BRIDGE IS LOCATED IN SEISMIC ZONE 1.
- FOR SUBMITTAL OF WORKING DRAWINGS, SEE SPECIAL PROVISIONS.
- FOR FALSEWORK AND FORMWORK, SEE SPECIAL PROVISIONS.
- FOR CRANE SAFETY, SEE SPECIAL PROVISIONS.
- FOR GROUT FOR STRUCTURES, SEE SPECIAL PROVISIONS.
- ASPHALT WEARING SURFACE IS INCLUDED IN ROADWAY QUANTITY ON ROADWAY PLANS.
- FOR ASBESTOS ASSESSMENT FOR BRIDGE DEMOLITION AND RENOVATION ACTIVITIES, SEE SPECIAL PROVISIONS.

HYDRAULIC DATA	
DESIGN DISCHARGE	= 3300 C.F.S.
FREQUENCY OF DESIGN FLOOD	= 25 YRS.
DESIGN HIGH WATER ELEVATION	= 106.70
DRAINAGE AREA	= 72.8 SQ. MI.
BASE DISCHARGE (Q100)	= 4900 C.F.S.
BASE HIGH WATER ELEVATION	= 107.73
OVERTOPPING DATA	
OVERTOPPING DISCHARGE	= 6000 C.F.S.
FREQUENCY OF OVERTOPPING FLOOD	= 200+ YRS.
OVERTOPPING FLOOD ELEVATION	= 108.60

TOTAL BILL OF MATERIAL														
	REMOVAL OF EXISTING STRUCTURE	PDA TESTING	UNCLASSIFIED STRUCTURE EXCAVATION	CLASS A CONCRETE	BRIDGE APPROACH SLABS	REINFORCING STEEL	HP 12 x 53 STEEL PILES	PILE REDRIVES	VERTICAL CONCRETE BARRIER RAIL	RIP RAP CLASS II	GEOTEXTILE FOR DRAINAGE	ELASTOMERIC BEARINGS	3'-0" x 2'-9" PRESTRESSED CONCRETE BOX BEAMS	ASBESTOS ASSESSMENT
	LUMP SUM	EACH	LUMP SUM	CU. YDS.	LUMP SUM	LBS.	NO.	LIN. FT.	EACH	LIN. FT.	TONS	SO.YDS.	LUMP SUM	LUMP SUM
SUPERSTRUCTURE					LUMP SUM								10	800.00
END BENT No. 1			LUMP SUM	23.7		3342	5	350	3		115	128		
END BENT No. 2			LUMP SUM	23.7		3342	5	350	3		132	147		
TOTAL	LUMP SUM	1	LUMP SUM	47.4	LUMP SUM	6684	10	700	6	160.00	247	275	LUMP SUM	10 800.00 LUMP SUM

DRAWN BY : B. N. BARODAWALA/MP DATE : 7-8-15  
 CHECKED BY : T.L.CLELLAND DATE : 01-2016

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



10/7/2016

PROJECT NO. B-4814  
 SAMPSON COUNTY  
 STATION: 17+71.00 -L-

SHEET 3 OF 3

STATE OF NORTH CAROLINA  
 DEPARTMENT OF TRANSPORTATION  
 GENERAL DRAWING  
 FOR BRIDGE OVER  
 LITTLE COHARIE CREEK  
 ON SR 1233  
 BETWEEN SR 1406 & SR 1412

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S2-3
1			3			TOTAL SHEETS
2			4			46

STR. #2