PROJ. REFERENCE NO.	SHEET NO.
B-5548	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, Borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+00.00	0	0	36+00.00	153	0
11+50.00	115	6	36+50.00	127	0
12+00.00	282	17	37+00.00	109	6
12+50.00	332	21	37+50.00	128	6
13+00.00	285	26	38+00.00	144	0
13+50.00	209	30	38+50.00	176	0
14+00.00	87	34	39+00.00	290	0
14+50.00	26	56	39+50.00	448	0
15+00.00	38	101	40+00.00	732	0
15+50.00	44	186	40+50.00	1024	0
16+00.00	53	369	41+00.00	1230	0
16+50.00	70	602	41+50.00	1343	0
17+00.00	92	757	42+00.00	1280	1
17+50.00	122	831	42+50.00	1055	4
18+00.00	150	854	43+00.00	735	6
18+50.00	95	819	43+50.00	555	5
19+00.00	21	639	44+00.00	496	11
19+50.00	32	276	44+50.00	432	28
20+00.00	229	30	45+00.00	411	34
20+50.00	531	0	45+50.00	431	21
21+00.00	671	0	46+00.00	487	15
21+50.00	505	0	46+50.00	535	14
22+00.00	187	177	47+00.00	464	10
22+50.00	26	696	47+50.00	191	4
23+00.00	19	1433			
23+50.00	19	2006			
24+00.00	0	2117			
24+50.00	0	2022			
25+00.00	0	1960			
25+50.00	0	1919			
26+00.00	7	1746			
26+50.00	27	1594			
27+00.00	62	1646			
27+50.00	56	1606			
28+00.00	47	1500			
28+50.00	80	1366			
28+64.21	27	359			

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+12.00	0	0
10+50.00	2	8
11+00.00	29	22
11+50.00	40	20
12+00.00	31	4

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
30+45.79	0	0
30+50.00	0	138
31+00.00	0	1628
31+50.00	0	1604
32+00.00	0	1594
32+50.00	0	1623
33+00.00	0	1668
33+50.00	0	1627
34+00.00	0	1475
34+50.00	0	1003
35+00.00	0	370
35+50.00	89	58

INDEX OF SHEETS

LINE	STATIONS	SHEETS
-L-	STA 11+00.00 TO STA 47+50.00	X-1 THRU X-14
-Y1-	STA 10+12.00 TO STA 12+00.00	X-15