

PROJECT NO.	SHEET NO.
2017CPT.01.11.10581.1, ETC	5

REVISED: 01/11/17 SPF

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	MOBILIZATION LS	1½" MILLING SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	ASP FOR PLANT MIX TONS	POLYM MOD ASP BNDR FOR PLT MIX GAL	OGAFC, TYPE FC-2 MOD TONS	WORK ZONE ADV/GEN WARN SIGN SF	TEMPORARY TRAFFIC CONTROL LS
2017CPT.01.11.10581.1	Martin	1	US 13 WBL (US 64)	FROM NC 903 TO EDGECOMBE CO.	1	2	MD	NO	NO	5.417	26	1	*91540		*7650	452	250	4,100	303	1
2017CPT.01.11.10581.2	Martin	2	US 13 EBL (US 64)	FROM EDGECOMBE CO. TO NC 903	1	2	MD	NO	NO	5.417	26	*	*91540		*7650	452	250	4,100	303	*
2017CPT.01.11.10581.5	Martin	3	US 17	FROM END OF 4 LANE TO BEAUFORT CL	2	2	2WU	NO	NO	6.117	24	*	89,500	7,900		474			126	*
2017CPT.01.11.10581.6	Martin	4	US 13 WBL (US 64)	FROM SR 1138 OVERPASS TO NC 903	1	2	MD	NO	NO	5.066	26	*	*108000		*9000	531	281	4,600	303	*
2017CPT.01.11.10581.7	Martin	5	US 13 EBL (US 64)	FROM NC 903 TO SR 1138 OVERPASS	1	2	MD	NO	NO	5.066	26	*	*115000		*9540	563	281	4,600	303	*
GRAND TOTAL										27.083		1	*495,580	7,900	*33,840	2,472	1,062	17,400	1,338	1

* INCLUDES RAMPS AND GORE AREAS. SEE NOTES FOR TYPICAL SHEET 3

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	LENGTH	WIDTH	4" X 90 M WHITE THERMO LF	4" X 120 M YELLOW THERMO LF	6" X 90 M WHITE THERMO LF	6" X 90 M YELLOW THERMO LF	6" X 120 M WHITE THERMO LF	THERMO PVT MKG LINES 8"90 MILS (WHITE) LF	12" X 90 M WHITE THERMO LF	THERM PVT SYM 90MIL (MERGE ARROW) EA	4" WHITE PAINT LF	4" YELLOW PAINT LF	PAINT PVT MKG SYM (MERGE ARROW) EA	PERM RAISE PVT MKRS (CRYSTAL & RED) EA	PERM RAISE PVT MKRS (YELLOW) EA
2017CPT.01.11.10581.1	Martin	1	US 13 WBL (US 64)	FROM NC 903 TO EDGECOMBE CO.	1	2	MD	5.417	29			29,000	29,000	7,150		1,100	3	37,300	29,000	3	400	
										58,000						66,300				400		
2017CPT.01.11.10581.2	Martin	2	US 13 EBL (US 64)	FROM EDGECOMBE CO. TO NC 903	1	2	MD	5.417	29			29,000	29,000	7,150	37	1,100		37,300	29,000		400	
										58,000						66,300				400		
2017CPT.01.11.10581.5	Martin	3	US 17	FROM END OF 4 LANE TO BEAUFORT CL	2	2	2WU	6.117	24	66,000	40,372							66,000	40,372			405
										106,372						405						
2017CPT.01.11.10581.6	Martin	4	US 13 WBL (US 64)	FROM SR 1138 OVERPASS TO NC 903	1	2	MD	5.066	25			26,800	26,800	6,700	111	4,000	6	37,620	26,800	6	475	
										53,600						64,420				475		
2017CPT.01.11.10581.7	Martin	5	US 13 EBL (US 64)	FROM NC 903 TO SR 1138 OVERPASS	1	2	MD	5.066	25			26,800	26,800	6,700	74	4,000	9	37,620	26,800	9	475	
										53,600						64,420				475		
GRAND TOTAL								27.083		66,000	40,372	111,600	111,600	27,700	222	10,200	18	215,840	151,972	18	1,750	405
										223,200						367,812				2,155		