


EDI MODEL 2018EClip-NC CONFLICT MONITOR

PROGRAMMING DETAIL

(remove jumpers and set switches as shown)



REMOVE JUMPERS AS SHOWN

NOTES:

1. Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
2. Ensure jumpers SEL2-SEL5 and SEL9 are present on the monitor board.
3. Ensure that Red Enable is active at all times during normal operation.
4. Integrate monitor with Ethernet network in cabinet.

■ = DENOTES POSITION OF SWITCH

NOTES

1. To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
2. Enable Simultaneous Gap-Out for all phases.
3. Program phases 2 and 6 for volume density operation.
4. Program controller to start up in phase 2 Green and 6 Green.
5. The cabinet and controller are part of the Fayetteville Signal System.

LOAD SWITCH NO.	S1	S2	S3	S4	S5	S6	S7	S8	S9	S10	S11	S12
CMU CHANNEL NO.	1	2	13	3	4	14	5	6	15	7	8	16
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED
SIGNAL HEAD NO.	11,12	42	21,22	NU	NU	41,42	NU	51	61,62	NU	NU	NU
RED		128			101			134				
YELLOW		129			102			135				
GREEN		130			103			136				
RED ARROW	125							131				
YELLOW ARROW	126	126						132				
GREEN ARROW	127	127						133				


NU = Not Used

EQUIPMENT INFORMATION

CONTROLLER.....2070E
 CABINET.....332
 SOFTWARE.....ECONOLITE ASC/3-2070
 CABINET MOUNT.....BASE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S1,S2,S5,S7,S8
 PHASES USED.....1,2,4,5,6
 OVERLAPS.....NONE

INPUT FILE POSITION LAYOUT

(front view)




EX.: 1A, 2A, ETC. = LOOP NO.'S

FS = FLASH SENSE
 ST = STOP TIME

INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND TIME	DELAY TIME	DETECTOR TYPE
1A	TB2-1,2	I1U	56	1	1	YES			S
1B	TB2-3,4	I1L	56	1	1	YES			S
1C	TB2-5,6	I2U	39	2	1	YES		15	S
2A	TB2-7,8	I2L	43	12	2	YES			N
2B	TB2-9,10	I3U	63	32	2	YES			N
2C	TB2-11,12	I3L	76	42	2	YES			N
4A	TB4-9,10	I6U	41	4	4	YES			S
5A	TB3-1,2	J1U	55	5	5	YES			S
6A	TB3-5,6	J2U	40	6	6	YES			N
6B	TB3-7,8	J2L	44	16	6	YES			N
6C	TB3-9,10	J3U	64	36	6	YES			N

INPUT FILE POSITION LEGEND: J2L




THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 06-0032
 DESIGNED: September 2015
 SEALED: 3/14/2016
 REVISED: N/A

Electrical Detail

ELECTRICAL AND PROGRAMMING DETAILS FOR:


NC 24-87 (Bragg Boulevard) at Elm Street



750 N. Greenfield Pkwy, Garner, NC 27529

Division 6 Cumberland County Fayetteville
 PLAN DATE: March 2016 REVIEWED BY: T. Joyce
 PREPARED BY: S. Armstrong REVIEWED BY:

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED



DocuSigned by: Keith M. Mims 3/17/2016
 SIG. INVENTORY NO. 06-0032