
PHASING DIAGRAM



PHASTNG	DTAGRAM	DETECTION	I FGFND
IIII	D I / (OI I/ (III	DETECTION	LLGLIID

DETECTED MOVEMENT

UNDETECTED MOVEMENT (OVERLAP)

UNSIGNALIZED MOVEMENT ← − − > PEDESTRIAN MOVEMENT

TABLE OF OPERATION SIGNAL FACE I.D. All Heads L.E.D. PHASE

FACE

21,22

41,42

61,62

81,82

P41**,**P42

F	
Y	12"



21,22	
41,42	
61,62	
81,82	


OASIS 2070 LOOP & DETECTOR INSTALLATION CHART												
INDUCTIVE LOOPS			DETECTOR PROGRAMMING									
LOOP	SIZE (FT)	DISTANCE FROM STOPBAR (FT)	TURNS	NEW LOOP	PHASE	CALLING	EXTENSION	FULL TIME DELAY	STRETCH TIME	DELAY TIME	SYSTEM LOOP	NEW CARD
2A	6X6	300	5	-	2	Υ	Υ	-	_	-	-	Υ
2B	6X6	300	5	-	2	Υ	Υ	-	-	1	-	Υ
2C	6X40	+5	2-4-2	-	2	Υ	Υ	Υ	-	3	-	Υ
4A	6X40	+5	EXIST	-	4	Υ	Υ	-	-	5	-	Υ
4B	6X40	+5	EXIST	-	4	Υ	Υ	-	-	15	-	Υ
6A	6X6	300	5	-	6	Υ	Υ	-	-	-	-	Υ
6B	6X6	300	5	-	6	Υ	Υ	-	-	1	-	Υ
6C	6X40	+5	2-4-2	_	6	Υ	Υ	Υ	-	3	-	Υ
88	6X40	+5	2-4-2	-	8	Υ	Υ	-	-	-	-	Υ
8B	6X6	0	EXIST	_	8	Υ	Υ	-	_	10	-	Υ

2 Phase

Fully Actuated Asheville Signal System

NOTES

- 1. Refer to "Roadway Standard Drawings NCDOT" dated January 2012 and "Standard Specifications for Roads and Structures" dated January 2012.
- 2. Do not program signal for late night flashing operation unless otherwise directed by
- the Engineer. 3. Set all detector units to presence mode.
- 4. Locate new cabinet so as not to obstruct sight distance of vehicles turning right on red.
- 5. Omit "WALK" and flashing "DON'T WALK" with no pedestrian calls.
- 6. Program pedestrian heads to countdown the flashing "Don't Walk" time only.
- 7. Pavement markings are existing.
- 8. Maximum times shown in timing chart are for free-run operation only. Coordinated signal system timing values supersede these values.



OASIS	2070	TIMING	G CHART	Γ	
	PHASE				
FEATURE	2	4	6	8	
Min Green 1 *	12	7	12	7	
Extension 1 *	6.0	2.0	6.0	1.0	
Max Green 1 *	100	20	100	20	
Yellow Clearance	4.8	3.9	4.8	3.9	
Red Clearance	1.8	2.5	1.8	2.5	
Red Revert	2.0	2.0	2.0	2.0	
Walk 1 *	-	7	-	-	
Don't Walk 1	-	18	-	-	
Seconds Per Actuation *	1.5	-	1.5	-	
Max Variable Initial *	35	-	35	-	
Time Before Reduction *	15	-	15	-	
Time To Reduce *	45	-	45	-	
Minimum Gap	3.0	_	3.0	-	
Recall Mode	MIN RECALL	-	MIN RECALL	-	
Vehicle Call Memory	YELLOW	-	YELLOW	-	
Dual Entry	-	ON	-	ON	
Simultaneous Gap	ON	ON	ON	ON	

* These values may be field adjusted. Do not adjust Min Green and Extension times for phases 2 and 6 lower than what is shown. Min Green for all other phases should not

be lower than 4 seconds.

PROPOSED		EXISTING
\bigcirc	Traffic Signal Head	
O	Modified Signal Head	N/A
\dashv	Sign	\dashv
\downarrow	Pedestrian Signal Head With Push Button & Sign	#
<u> </u>	Signal Pole with Guy	•
	Signal Pole with Sidewalk Guy	y • • • • • • • • • • • • • • • • • • •
	Inductive Loop Detector	$\subset = = \supset$
	Controller & Cabinet	~
	Junction Box	
	- 2-in Underground Conduit	
N/A	Right of Way	
\longrightarrow	Directional Arrow	\longrightarrow
\bigcirc	Type II Signal Pedestal	•

LEGEND



NC 63 (Leicester Highway) SR 1318 (Eliada Home Road)

Division 13 Buncombe County Leicester REVIEWED BY: T. J. Williams PLAN DATE: June 2016 750 N.Greenfield Pkwy.Garner.NC 27529 PREPARED BY: C. Pierce REVIEWED BY:

24393 SIG. INVENTORY NO. 13-0057

DOCUMENT NOT CONSIDERED

FINAL UNLESS ALL SIGNATURES COMPLETED