

RAILROAD PREEMPTION PROGRAMMING DETAIL

(program controller as shown below)


From Main Menu press 'A' (Preemption), then '1' (Standard Preemptions).

PREEMPTION #1	SETTINGS (NEXT:1-10)
INTERVAL/TIMING	CLEAR/DWELL PHASES
GRN YEL RED	12345678910111213141516
1 10 3.2 2.7	X
2 255 0.0 0.0	X X
3 0 0.0 0.0	
4 0 0.0 0.0	
5 1 0.0 0.0	X X

EXIT CALLS	OPTIONS
PRIORITY (Y/N TO SELECT)HIGH
DELAY TIMER (0-255 SEC)0
MIN GREEN BEFORE PRE (0= DEFAULT)1
PED CLEAR BEFORE PRE (0= DEFAULT)0
YELLOW CLEAR BEFORE PRE (0= DEFAULT)5.2
RED CLEAR BEFORE PRE (0= DEFAULT)1.1
DWELL MIN TIMER (0-255 SEC)12
DWELL MAX TIMER (0-OFF,1-255MIN)0
DWELL HOLD-OVER TIMER (0-255)0
LATCH CALL?N
LINK TO NEXT PREEMPT?N
ENABLE BACKUP PROTECTION?N
HOLD CLEAR 1 PHASES DURING DELAY?N
FAST GREEN FLASH DWELL PHASES?N
PED CLEARANCE THROUGH YELLOW?N
INHIBIT OVERLAP GREEN EXTENSION?N
SERVICE DURING SOFTWARE FLASH?N
REST IN RED DURING DWELL INTERVAL?N
FLASH DWELL INTERVAL?N
ALLOW PEDS IN DWELL INTERVAL?N
RE-TIME DWELL INTERVAL?N
OVERLAPS:	ABCDEFGHIJKLMNPO
DWELL INT FLASH YELLOW:	
OMIT OVERLAPS:	X X

RAILROAD PREEMPTION WIRING DETAIL


(wire as shown below)



NOTES


- Relay K1 is shown in the energized (Preempt not active) normal operation state.
- Relay K1 is a DPDT with 120VAC coil with octal base.
- Relay SSR1 is a SPST (normally open) Solid State Relay with AC input and AC (25 amp) output.
- AC Isolator Card shall activate preemption upon removal of AC+ from the input (as shown above). To accomplish this set invert dip switch on AC Isolator Card.
- IMPORTANT!!** A jumper must be added between input file terminals J14-E and J14-K if not already present. Also, terminal TB9-12 (on input panel) shall be connected to AC neutral (jumper may have to be added).

FRONT VIEW



PREEMPT 1 AC ISOLATOR (MODEL 252) OUTPUT PROGRAMMING DETAIL

(set DIP switches as shown below)



NOTE: IF ANOTHER MANUFACTURER TYPE OF AC ISOLATOR IS USED, OUTPUT PROGRAMMING IS LIKELY NOT TO EQUATE TO THAT SHOWN ABOVE.

THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 13-0816
 DESIGNED: March 2016
 SEALED: 11/2/2016
 REVISED:

Electrical Detail Sheet 3 of 3

ELECTRICAL AND PROGRAMMING DETAILS FOR: Prepared In the Offices of: 	US 19-23 (Smokey Park Hwy.) at SR 3613 (Enka Quarry Rd.)/ SR 1233 (Rutherford Rd.)		SEAL
	Division 13 PLAN DATE: September 2016 PREPARED BY: Z.M. Little	Buncombe County Enka REVIEWED BY: K.M. Mims REVIEWED BY:	

09-0004-2016_09-16
 S:\MITS\SU\TS\Sig\work\hgr\output\sig\Map\1111e13-0816\130816_sm.e1e.2016mdd.dgn
 zmlittle