## LOGICAL I/O PROCESSOR PROGRAMMING DETAIL

TO PRODUCE SPECIAL FYA-PPLT SIGNAL SEQUENCE

(program controller as shown below)

1. FROM MAIN MENU PRESS '2' (PHASE CONTROL), THEN '1' (PHASE CONTROL FUNCTIONS). SCROLL TO THE BOTTOM OF THE MENU AND ENABLE ACT LOGIC COMMANDS 1, 2 AND 3.

2. FROM MAIN MENU PRESS '6' (OUTPUTS), THEN '3' (LOGICAL I/O PROCESSOR).

```
LOGICAL I/O COMMAND #1   (+/-COMMAND#)
IF   ACTIVE PHASE        #1   IS ON
AND RED CLEAR ON PHASE   #1   IS ON



              SCROLL DOWN

THEN:
SET OUTPUT   ASSIGNMENT #50 ON
SET OUTPUT   ASSIGNMENT #51 OFF
```
NOTE: LOGIC FOR PHASE 1 RED CLEAR WHEN TRANSITIONING FROM PHASE 1 TO PHASE 2 (HEAD 11).

PRESS '+'

```
LOGICAL I/O COMMAND #2   (+/-COMMAND#)
IF   ACTIVE PHASE        #1   IS ON



              SCROLL DOWN

THEN:
SET OUTPUT   ASSIGNMENT #52 OFF
```
NOTE: LOGIC FOR SWITCHING FLASHING YELLOW ARROW "OFF" DURING PHASE 1 (HEAD 11).

PRESS '+'

```
LOGICAL I/O COMMAND #3   (+/-COMMAND#)
IF   YELLOW ON PHASE     #1   IS ON



              SCROLL DOWN

THEN:
SET OUTPUT   ASSIGNMENT #51 ON
```
NOTE: LOGIC FOR YELLOW ARROW CLEARANCE FROM PHASE 1 (HEAD 11).

LOGIC I/O PROCESSOR PROGRAMMING COMPLETE

```
OUTPUT REFERENCE SCHEDULE

   OUTPUT 50 = Overlap A Red
   OUTPUT 51 = Overlap A Yellow
   OUTPUT 52 = Overlap A Green
```

OVERLAP PROGRAMMING DETAIL

(program controller as shown below)

FROM MAIN MENU PRESS '8' (OVERLAPS), THEN '1' (VEHICLE OVERLAP SETTINGS).

```
PAGE 1: VEHICLE OVERLAP 'A' SETTINGS
 PHASE:          |1234567891011213141516
VEH OVL PARENTS:|XX
VEH OVL NOT VEH:|
VEH OVL NOT PED:|
VEH OVL GRN EXT:|
STARTUP COLOR: _ RED  _ YELLOW  _ GREEN
FLASH COLORS:  _ RED  _ YELLOW  X GREEN
SELECT VEHICLE OVERLAP OPTIONS:   (Y/N)
FLASH YELLOW IN CONTROLLER FLASH?...Y
GREEN EXTENSION (0-255 SEC).........0
YELLOW CLEAR (0=PARENT,3-25.5 SEC)..0.0
RED CLEAR (0=PARENT,0.1-25.5 SEC)...0.0
OUTPUT AS PHASE # (0=NONE, 1-16)....0
```
← NOTICE GREEN FLASH

OVERLAP PROGRAMMING COMPLETE

THIS ELECTRICAL DETAIL IS FOR
THE SIGNAL DESIGN: 13-1226
DESIGNED: July 2016
SEALED: 9/8/2016
REVISED:

Electrical Detail - Sheet 2 of 2

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

ELECTRICAL AND PROGRAMMING DETAILS FOR:

Prepared in the Offices of:

Transportation Mobility and Safety Division

Signals Management Section

750 N.Greenfield Pkwy,Garner,NC 27529

SR 1368 (Lees Creek Road)
at
W. Buncombe Elementary School

Division 13	Buncombe County	Asheville
PLAN DATE: September 2016	REVIEWED BY:	T. Joyce
PREPARED BY: C. Strickland	REVIEWED BY:	

SEAL

NORTH CAROLINA
PROFESSIONAL
SEAL
030530
ENGINEER
ZACHARY M. LITTLE

REVISIONS	INIT.	DATE

DocuSigned by:
Zachary M. Little   9/13/2016
DATE

SIG. INVENTORY NO. 13-1226