



SUMMARY OF WORK BY CABLE ROUTING PLANS

CABLE ROUTING SHEET NUMBER	MESSANGER CABLE (1/4")	BOND MESSANGER CABLE	TRACER WIRE	UNDERGROUND CONDUIT (1 CONDUIT, 1 INCH)	UNDERGROUND CONDUIT (1 CONDUIT, 2 INCH)	UNDERGROUND CONDUIT (2 CONDUIT, 2 INCH)	DIRECTIONAL DRILL (2 CONDUIT, 2 INCH)	DIRECTIONAL DRILL (1 CONDUIT, 2 INCH)	JUNCTION BOX (OVER-SIZED)	JUNCTION BOX (SPECIAL SIZED)	REMOVE EXISTING JUNCTION BOX	DELINEATOR MARKER	STANDARD GUY ASSEMBLY	AERIAL GUY ASSEMBLY	SIDEWALK GUY ASSEMBLY	1" RISER WITH WEATHERHEAD FOR CCTV ELEC SERVICE	1" RISER WITH WEATHERHEAD FOR CAT 5E OR COMPOSITE	1" RISER WITH HEAT SHRINK TUBING	1.25" RISER WITH HEAT SHRINK TUBING	2" RISER WITH HEAT SHRINK TUBING	HEAT SHRINK TUBING RETROFIT KIT	DRILL/ CORE DRILL EXIST FOUNDATION
	LF	EA	LF	LF	LF	LF	LF	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
CRP-6.207	-	1	190	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-
CRP-6.208	-	2	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.209	-	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.210	-	3	380	-	10	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	2	-
CRP-6.211	-	1	110	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-
CRP-6.212	30	5	1,080	-	-	340	-	-	-	1	1	-	-	-	-	-	-	-	-	-	5	-
CRP-6.213	1,600	1	-	-	-	-	-	-	-	-	-	-	6	1	-	-	-	-	-	-	-	-
CRP-6.214	1,540	1	-	-	-	-	-	-	-	-	-	-	2	-	-	-	-	-	-	-	-	-
CRP-6.215	1,420	1	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
CRP-6.216	640	4	400	-	-	-	-	-	-	1	1	-	-	-	-	-	-	-	-	-	4	-
CRP-6.217	360	4	400	-	-	-	-	-	-	1	1	-	1	-	-	-	-	-	-	-	4	-
CRP-6.218	-	2	1,540	-	-	220	300	-	1	2	1	-	-	-	-	-	-	-	-	-	2	1
CRP-6.219	1,150	1	-	-	-	-	-	-	-	-	-	-	1	-	-	-	-	-	-	-	1	-
CRP-6.220	1,310	3	310	-	-	-	310	-	4	-	-	-	3	-	-	-	-	-	-	3	-	-
CRP-6.221	-	-	1,320	-	-	850	470	-	4	-	-	2	-	-	-	-	-	-	-	-	-	-
CRP-6.222	-	-	1,660	-	-	510	1,330	220	3	1	-	3	-	-	-	-	-	-	-	-	-	-
CRP-6.223	-	-	1,430	-	-	-	1,430	-	3	-	-	2	-	-	-	-	-	-	-	-	-	-
CRP-6.224	220	1	1,210	-	-	170	1,040	-	2	1	-	-	1	-	-	-	-	-	-	1	-	1
CRP-6.225	1,740	1	-	-	-	-	-	-	-	-	-	-	3	-	-	-	-	-	-	-	-	-
CRP-6.226	1,470	1	-	-	-	-	-	-	-	-	-	-	4	-	-	-	-	-	-	-	-	-
CRP-6.227	1,470	2	10	-	10	-	-	-	-	-	-	-	2	-	-	-	-	-	-	1	-	-
CRP-6.228	1,640	1	-	-	-	-	-	-	-	-	-	-	-	-	1	-	-	-	-	1	-	1
CRP-6.229	160	1	60	-	-	60	-	-	-	1	-	-	1	-	-	-	-	-	-	1	-	-
CRP-6.230	1,230	2	-	-	-	-	-	-	-	-	-	-	-	-	2	-	-	-	1	-	-	-
CRP-6.231	1,470	2	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1	-	-	-
CRP-6.232	1,070	1	-	-	-	-	-	-	-	-	-	-	1	-	-	-	-	-	-	-	-	-
CRP-6.233	1,930	3	20	-	-	20	-	-	1	-	-	-	2	2	-	-	1	-	-	2	-	-
CRP-6.234	1,190	2	250	-	-	250	-	-	2	-	-	-	2	-	-	-	-	-	-	2	-	-
CRP-6.235	-	-	1,410	-	-	1,080	330	-	5	1	-	2	-	-	-	-	-	-	-	-	-	1
CRP-6.236	-	-	1,430	-	-	680	750	-	3	-	-	1	-	-	-	-	-	-	-	-	-	-
CRP-6.237	550	2	790	-	-	520	270	-	3	-	-	1	2	-	-	-	-	-	-	2	-	-
CRP-6.238	-	-	1,440	-	-	1,130	310	-	3	2	-	3	-	-	-	-	-	-	-	-	-	-
CRP-6.239	-	-	570	-	-	200	370	-	2	1	-	1	-	-	-	-	-	-	-	-	-	-
CRP-6.240	1,170	2	220	-	-	-	220	-	2	-	-	-	5	-	1	-	-	-	-	2	-	-
CRP-6.241	590	2	700	-	-	120	580	-	4	-	-	1	4	-	-	-	-	-	-	2	-	-

21-DEC-2016 14:21
 G:\Projects\2016\14\21\01\Traffic\Signal\Traffic\CRP-1.018.dgn
 W:\LE2014 AT_DUS300019

- Work shown on this sheet is a summary of work for the installation of the fiber-optic cable and CCTV installations that are shown on the cable routing plans (i.e. CRP sheets). Work to be done for traffic signals is shown separately on the signal designs and the "Summary of Work by Intersection" sheets in Volume III of III.
- The items listed above are for informational purposes only and represent work that is necessary to complete the project and are not necessarily pay items. See Summary of Quantites and the Project Special Provisions for defined Pay Items for this contract.

ATKINS 1616 EAST MILLBROOK ROAD, SUITE 310
 RALEIGH, NORTH CAROLINA 27609
 (919) 876-8888 NCBEEES #F-0326

Prepared for the Offices of:  Transportation 750 Greenfield Parkway, Garner, NC 27529		Asheville Signal System Summary of Work by Cable Routing Plans (sheet 19 of 30) Division 13 Buncombe County Asheville		SEAL  MELISSA B. TOTH ENGINEER SEAL 025892	
PLAN DATE: December 2016 PREPARED BY: J A Wiles		REVIEWED BY: M B Toth		REVIEWED BY:	
REVISIONS		INIT.		DATE	
NTS		12/21/2016		DATE	
CADD File name: CRP-1.018.dgn					

DOCUMENT NOT CONSIDERED FINAL
 UNLESS ALL SIGNATURES COMPLETED