DocuSign Envelope ID: 1D5794B7-818B-4CF1-886E-601A67BB1F4C

SHEET REFERENCE	CCTV CAMERA NUMBER	LOCATION	POWER SERVICE				CABINET TYPE	COMM. TYPE	HORIZ. DIST. TO POWER SOURCE	DIST. TO SIGNAL CABINET	CABINETS ON SAME CORNER	AVAIL. 120 POWER
			TYPE	SOURCE	VOLTAGE	STATUS						
CRP - 6.001	CCTV-1	I-26 Exit 44 @ US 25 Hendersonville Road	UNDERGROUND	CABINET 14-0901	28V	EXIST.	TRAFFIC SIGNAL	ETHERNET	200	200	No	No
CRP - 6.082	CCTV-2	I-26 Exit 40 @ NC 280 Airport Road	UNDERGROUND	METER SERVICE	120V	NEW	TYPE 336 CCTV	SMFO	400	400	No	No
CRP - 6.018	CCTV-3	US 25 Hendersonville Rd @ NC 280 Airport Road	OVERHEAD	CABINET 13-0285	28V	EXIST.	TRAFFIC SIGNAL	ETHERNET	170	170	No	No
CRP - 6.103	CCTV-4	I-26 Exit 37 @ Long Shoals Road (existing)	UNDERGROUND	METER SERVICE	120V	EXIST.	TYPE 336 CCTV	SMFO	Exist.	N/A	N/A	Yes
CRP - 6.109	CCTV-5	US 25 Hendersonville Rd @ NC 146 Long Shoals Road	UNDERGROUND	METER SERVICE	120V	NEW	TYPE 336 CCTV	SMFO	350	350	No	No
CRP - 6.029	CCTV-6	US 25 Hendersonville @ Gerber Village	OVERHEAD	CABINET 13-1217	28V	EXIST.	TRAFFIC SIGNAL	ETHERNET	105	105	No	Yes
CRP - 6.325	CCTV-7	I-26 Eastbound MM 34 @ Ferry Road	OVERHEAD	METER SERVICE	120V	EXIST.	TYPE 336 CCTV	CELLULAR	50	N/A	N/A	Yes
CRP - 6.123	CCTV-8	I-26 Exit 33 NC 191 Brevard Road	UNDERGROUND	METER SERVICE	120V	NEW	TYPE 336 CCTV	SMFO	100	470	No	Yes
CRP - 6.326	CCTV-9	I-26 MM 32 Pond Road (existing)	OVERHEAD	METER SERVICE	120V	EXIST.	TYPE 336 CCTV	SMFO	N/A	N/A	N/A	Yes
CRP - 6.272	CCTV-10	I-240 MM 1 @ NC 191 Brevard Road (existing)	UNDERGROUND	METER SERVICE	120V	EXIST.	TYPE 336 CCTV	SMFO	140	140	No	Yes
CRP - 6.167	CCTV-11	I-240 Exit 2 @ Haywood Road	OVERHEAD	CABINET 13-0218	28V	EXIST.	TRAFFIC SIGNAL	ETHERNET	55	55	Yes	Yes
CRP - 6.161	CCTV-12	I-240/I-26 @ Patton Ave	UNDERGROUND	DETECT CABINET	120V	EXIST.	TYPE 336 CCTV	SMFO	10	10	Yes	Yes
CRP - 6.275	CCTV-13	I-240 @I-26	UNDERGROUND	METER SERVICE	120V	NEW	TYPE 336 CCTV	SMFO	N/A	N/A	N/A	Yes
CRP - 6.278	CCTV-14	I-240 Exit 4C @ Montford Ave / Haywood Street	OVERHEAD	METER SERVICE	120V	NEW	TYPE 336 CCTV	ETHERNET	150	150	No	Yes
CRP - 6.287	CCTV-15	I-240 Exit 5B @ Charlotte St	OVERHEAD	CABINET 13-0255	28V	EXIST.	TRAFFIC SIGNAL	ETHERNET	120	110	No	Yes
CRP - 6.191	CCTV-16	I-240 Exit 7 @Tri-level Bridges/US 70	OVERHEAD	CABINET 13-0033	28V	EXIST.	TRAFFIC SIGNAL	ETHERNET	150	150	No	No
CRP - 6.068	CCTV-17	I-26 Exit 25 @ Broadway	UNDERGROUND	METER SERVICE	120V	NEW	TYPE 336 CCTV	SMFO	> 400'	> 400'	No	No
CRP - 6.314	CCTV-18	I-40 Exit 53 @ I-240	N/A	SOLAR	28V	NEW	TYPE 336 CCTV	SMFO	> 400'	> 400'	No	No
CRP - 6.044	CCTV-19	I-40 Exit 50 @ US 25 Hendersonville Road	OVERHEAD	METER SERVICE	120V	NEW	TYPE 336 CCTV	SMFO	280	N/A	No	Yes
CRP - 6.328	CCTV-20	I-40 West MM 46 (existing)	OVERHEAD	METER SERVICE	120V	EXIST.	TYPE 336 CCTV	RADIO	N/A	N/A	N/A	Yes
CRP - 6.329	CCTV-21	I-40 West MM 44.5 (existing)	OVERHEAD	METER SERVICE	120V	EXIST.	TYPE 336 CCTV	RADIO	N/A	N/A	N/A	Yes
CRP - 6.146	CCTV-22	I-40 Exit 44 @ Smokey Park Hwy	OVERHEAD	CABINET 13-0468	28V	EXIST.	TRAFFIC SIGNAL	ETHERNET	170	200	Yes	Yes
CRP - 6.233	CCTV-23	US 19-23, Smokey Park Hwy @ NC 112 Sand Hill Road	OVERHEAD	CABINET 13-0282	28V	EXIST.	TRAFFIC SIGNAL	ETHERNET	160	200	No	Yes
CRP - 6.174	CCTV-24	Asheland Ave @ Hilliard Ave	OVERHEAD	CABINET COA-304	28V	EXIST.	TRAFFIC SIGNAL	ETHERNET	25	25	Yes	Yes
CRP - 6.276	CCTV-25	Patton Ave @ I-240/I-26 Ramps	OVERHEAD	CABINET 13-1029	28V	EXIST.	TRAFFIC SIGNAL	ETHERNET	40	40	Yes	Yes
CRP - 6.206	CCTV-26	I-40 Exit 55 at Porters Cove Road	OVERHEAD	CABINET 13-1225	28V	EXIST.	TRAFFIC SIGNAL	ETHERNET	180	180	No	Yes
CRP - 6.330	CCTV-27	I-26 @ US 19 Business	N/A	SOLAR	28V	NEW	TYPE 336 CCTV	SMFO	>400'	>400'	No	Yes
CRP - 6.047	CCTV-28	Biltmore Avenue at Meadow Rd./NC 81 (Bryson St.)	OVERHEAD	CABINET 13-0243	28V	EXIST.	TRAFFIC SIGNAL	ETHERNET	180	190	No	Yes
CRP - 6.046	CCTV-29	US 25 (McDowell St.) at Lodge St.	OVERHEAD	CABINET 13-0389	28V	EXIST.	TRAFFIC SIGNAL	ETHERNET	275	220	No	Yes

ATKINS
1616 EAST MILLBROOK ROAD, SUITE 310
RALEIGH, NORTH CAROLINA 27609
(919) 876-6888 NCBEES #F-0326

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared for the Offices of:

NC Transportation

750 Greenfield Parkway, Garner, NC 27529

NTS

Asheville Signal System
CCTV Installation Summary
(2 of 2)

Division 13 Buncombe County Asheville

PLAN DATE: October 2016 REVIEWED BY: HA Badgett

PREPARED BY: JO Oerter REVIEWED BY: JT Brooks

REVISIONS	INIT.	DATE

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 019962 ENGINEER HENRY ALFRED BADGETT III

DocuSigned by: Henry Alfred Badgett III 12/21/2016

6D2FA2B5EF8C43F... DATE

CADD Filename: 270_091_U-4715B_CRP-2.

21-DEC-2016 14:17
O:\Transportation\Traffic\Curr\1000486\32 U-4715B Asheville Sig Sys\Task 11_Typ_SD\Final Microstation Files Renamed\Volume 1 - Part 1\270_091_U-4715B_CRP-2.001.dgn
ALI07303 AT LD55195