



SPLICE ENCLOSURE NO. S6-6

DEVICE ID	CRP SHEET	CABLE X			CABLE Y		
		CABLE NUMBER	ALONG ROUTE	TO	CABLE NUMBER	ALONG ROUTE	TO
13-0059	CRP-6.023	6A	US 25 (HENDERSONVILLE RD)	NC 146 (LONG SHOALS RD)	6A	US 25 (HENDERSONVILLE RD)	HEYWOOD RD
13-0439	CRP-6.022	6A	US 25 (HENDERSONVILLE RD)	LINAMAR ENTRANCE	6A	US 25 (HENDERSONVILLE RD)	GLEN BRIDGE RD
13-0046	CRP-6.020	6A	US 25 (HENDERSONVILLE RD)	HEYWOOD RD	6A	US 25 (HENDERSONVILLE RD)	BUCK SHOALS RD

17-JAN-2017 16:12  
 D:\projects\asheville\signal\proj\asheville\sig\sys\task 11 Comm\in\microstation\files (Renamed - Merged)\u-4715b\fs-4.23.dgn  
 AT LUS355195

#### LEGEND

(1) BLUE	(7) RED	X = FUSION SPlice INDIVIDUAL FIBER
(2) ORANGE	(8) BLACK	C = CAP AND SEAL
(3) GREEN	(9) YELLOW	EXPRESS = EXPRESS ENTIRE BUFFER TUBE / FIBERS THROUGH WITHOUT CUTTING
(4) BROWN	(10) VIOLET	BUFFER SPlice = SPlice ALL FIBERS IN BUFFER TUBE COLOR TO COLOR
(5) SLATE	(11) ROSE	
(6) WHITE	(12) AQUA	

- #### NOTES
- UNUSED FIBERS LEFT COILED AND STORED IN SPlice TRAY
  - UNUSED BUFFER TUBES LEFT COILED AND STORED IN SPlice ENCLOSURE
  - EDGE SWITCH CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.

1616 EAST MILLBROOK ROAD, SUITE 310  
RALEIGH, NORTH CAROLINA 27609  
(919) 876-6888 NCBEEES #F-0326

**DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED**

Prepared for the Offices of:

750 Greenfield Parkway, Garner, NC 27529

### Asheville Signal System Fiber-Optic Splicing Details

Division 13 Buncombe County Asheville

PLAN DATE: December 2016 REVIEWED BY: HA Badgett

PREPARED BY: AM Quigley REVIEWED BY: JT Brooks

REVISIONS	INIT.	DATE

SCALE: NTS

SEAL

1/17/2017  
DATE

CADD File name: 271\_065\_U-4715B\_FS-4.23.dgn