



SPLICE ENCLOSURE NO. S2-1							
DEVICE ID	CRP SHEET	CABLE X			CABLE Y		
		CABLE NUMBER	ALONG ROUTE	TO	CABLE NUMBER	ALONG ROUTE	TO
14-0678	CRP-6.001C	8B	US 25 (ASHEVILLE HWY)	NAPLES RD	8B	US 25 (ASHEVILLE HWY)	RUGBY DR
14-1050	CRP-6.001D	8B	US 25 (ASHEVILLE HWY)	I-26 EB RAMP	8B	US 25 (ASHEVILLE HWY)	S NAPLES RD
14-0742	CRP-6.003	8A	US 25 (HENDERSONVILLE RD)	FLEA MARKET	8A	US 25 (HENDERSONVILLE RD)	I-26 WB RAMP
14-1145	CRP-6.004	8A	US 25 (HENDERSONVILLE RD)	OLD BRICKYARD RD	8A	US 25 (HENDERSONVILLE RD)	BUTTER BRIDGE RD
14-1259	CRP-6.005	8A	US 25 (HENDERSONVILLE RD)	ROCKWELL DR	8A	US 25 (HENDERSONVILLE RD)	FLEA MARKET
14-0772	CRP-6.006	8A	US 25 (HENDERSONVILLE RD)	HOWARD GAP RD	8A	US 25 (HENDERSONVILLE RD)	OLD BRICKYARD RD
14-0595	CRP-6.009	8A	US 25 (HENDERSONVILLE RD)	FANNING BRIDGE RD	8A	US 25 (HENDERSONVILLE RD)	ROCKWELL DR
14-0740	CRP-6.010	8A	US 25 (HENDERSONVILLE RD)	CANE CREEK RD	8A	US 25 (HENDERSONVILLE RD)	HOWARD GAP RD
14-0585	CRP-6.011	8A	US 25 (HENDERSONVILLE RD)	ST JOHN RD	8A	US 25 (HENDERSONVILLE RD)	FANNING BRIDGE RD
14-1039	CRP-6.013	8A	US 25 (HENDERSONVILLE RD)	OLD AIRPORT RD	8A	US 25 (HENDERSONVILLE RD)	CANE CREEK RD
14-0048	CRP-6.013	8A	US 25 (HENDERSONVILLE RD)	ALLIANCE PAGE RD	8A	US 25 (HENDERSONVILLE RD)	ST JOHN RD
14-1278	CRP-6.014	8A	US 25 (HENDERSONVILLE RD)	WATSON RD	8A	US 25 (HENDERSONVILLE RD)	OLD AIRPORT RD

COLOR CODE		LEGEND	
(1) BLUE	(7) RED	EXPRESS	EXPRESS ENTIRE BUFFER TUBE / FIBERS THROUGH WITHOUT CUTTING
(2) ORANGE	(8) BLACK	BUFFER SPlice	SPlice ALL FIBERS IN BUFFER TUBE COLOR TO COLOR
(3) GREEN	(9) YELLOW		
(4) BROWN	(10) VIOLET		
(5) SLATE	(11) ROSE		
(6) WHITE	(12) AQUA		

- NOTES**
- UNUSED FIBERS LEFT COILED AND STORED IN SPLICE TRAY
  - UNUSED BUFFER TUBES LEFT COILED AND STORED IN SPLICE ENCLOSURE
  - EDGE SWITCH CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.

1616 EAST MILLBROOK ROAD, SUITE 310  
RALEIGH, NORTH CAROLINA 27609  
(919) 876-6888 NCBEEES #F-0326

DOCUMENT NOT CONSIDERED FINAL  
UNLESS ALL SIGNATURES COMPLETED

	<b>Asheville Signal System Fiber-Optic Splicing Details</b>	
	Division 13    Buncombe County    Asheville	PLAN DATE: December 2016    REVIEWED BY: HA Badgett
PREPARED BY: AM Quigley    REVIEWED BY: JT Brooks	REVISIONS    INIT.    DATE	
SCALE: NTS	CADD File name: 271_071_U-4715B_FS-4.29.dgn	

17-JAN-2017 15:03 D:\projects\atkins\proj\offices\cur\100048632\_U-4715B\_Ashville\11e\_Sig\_System\Task 11\_Comms\Inol\_Microstation\_Files (Renamed\_Merged)\vol\ume 2\271\_071\_U-4715B\_FS-4.29.dgn