



SPLICE ENCLOSURE NO. S11-1

DEVICE ID	CRP SHEET	CABLE X			CABLE Y		
		CABLE NUMBER	ALONG ROUTE	TO	CABLE NUMBER	ALONG ROUTE	TO
13-0049	CRP-6.169	11C	HAYWOOD RD	I-264-240	11C	HAYWOOD RD	CRAVEN ST
13-0218 / CCTV 11	CRP-6.167	11D	HAYWOOD RD	STATE ST	11C	HAYWOOD RD	RIDGELAWN RD/BEVERLY RD W.
CCTV 13	CRP-6.275	11B	PATTON AVE	HAYWOOD RD	11B	PATTON AVE	I-26
13-0216	CRP-6.165	11E	HAYWOOD RD	BREVARD RD	11E	HAYWOOD RD	STATE ST
COA-5	CRP-6.274	11C	RIVERSIDE DR	I-264-240	11C	CRAVEN ST	EMMA RD

LEGEND

X = FUSION SPlice INDIVIDUAL FIBER
C = CAP AND SEAL
EXPRESS = EXPRESS ENTIRE BUFFER TUBE / FIBERS THROUGH WITHOUT CUTTING
BUFFER SPlice = SPlice ALL FIBERS IN BUFFER TUBE COLOR TO COLOR

- NOTES**
- UNUSED FIBERS LEFT COILED AND STORED IN SPlice TRAY
 - UNUSED BUFFER TUBES LEFT COILED AND STORED IN SPlice ENCLOSURE
 - EDGE SWITCH CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.

17-Jan-2017 15:04
 D:\projects\transportation\trf\c\curr\100048632_U-4715B_Ashveville_Sig_System\Task 11_Comms\Inoal_Microstation_Files (Renamed_Merged)\vol\ume 2\271_079_U-4715B_FS-4_37.dgn
 00107303 AT LUS355195

1616 EAST MILLBROOK ROAD, SUITE 310
 RALEIGH, NORTH CAROLINA 27609
 (919) 876-6888 NCBEEES #F-0326

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Prepared for the Offices of:

750 Greenfield Parkway, Garner, NC 27529

**Asheville Signal System
Fiber-Optic Splicing Details**

Division 13 Buncombe County Asheville

PLAN DATE: December 2016	REVIEWED BY: HA Badgett
PREPARED BY: AM Quigley	REVIEWED BY: JT Brooks

SCALE: NTS

SEAL

1/17/2017