



17-JAN-2017 15:05
 D:\projects\offices\curr\100048632_U-4715B_Ashville\110_Sig_Sys\Task 11_Comms\Inol_Microstation_Files (Renamed_Merged)\vol\Ums 2\271_100_U-4715B_FS-4.58.dgn
 AT LUS355195

COLOR CODE	
TIA/EIA	598-B
(1) BLUE	(7) RED
(2) ORANGE	(8) BLACK
(3) GREEN	(9) YELLOW
(4) BROWN	(10) VIOLET
(5) SLATE	(11) ROSE
(6) WHITE	(12) AQUA

X	= FUSION SPlice INDIVIDUAL FIBER
C	= CAP AND SEAL
EXPRESS	= EXPRESS ENTIRE BUFFER TUBE / FIBERS THROUGH WITHOUT CUTTING
BUFFER SPlice	= SPlice ALL FIBERS IN BUFFER TUBE COLOR TO COLOR

- ### NOTES
- UNUSED FIBERS LEFT COILED AND STORED IN SPlice TRAY
 - UNUSED BUFFER TUBES LEFT COILED AND STORED IN SPlice ENCLOSURE
 - EDGE SWITCH CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING/ENSURING THE PROPER TERMINATIONS.

ATKINS

1616 EAST MILLBROOK ROAD, SUITE 310
 RALEIGH, NORTH CAROLINA 27609
 (919) 876-6888 NCBEEES #F-0326

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

 Transportation <small>750 Greenfield Parkway, Garner, NC 27529</small>	Asheville Signal System Fiber-Optic Splicing Details		SEAL
	Division 13 Buncombe County Asheville	PLAN DATE: December 2016 REVIEWED BY: HA Badgett	PREPARED BY: AM Quigley REVIEWED BY: JT Brooks
SCALE	REVISIONS	INIT.	DATE
NTS			

CADD File name: 271_100_U-4715B_FS-4.58.dgn