

- 1 INSTALL 3-WIRE COPPER SERVICE ENTRANCE CONDUCTORS
- 2 INSTALL 4-WIRE COPPER FEEDER CONDUCTORS
- 3 INSTALL 3-WIRE COPPER FEEDER CONDUCTORS
- 4 INSTALL SMFO CABLE
- 5 INSTALL CAT 5e ETHERNET CABLE
- 6 INSTALL FIBER OPTIC DROP CABLE
- 7 INSTALL TRACER WIRE
- 8 TRENCH
- 9 INSTALL PVC CONDUIT
- 10 INSTALL RIGID, GALVANIZED STEEL CONDUIT
- 11 INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD
- 12 INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC CABLE SEAL
- 13 INSTALL POLYETHYLENE CONDUIT IN EXISTING OUTERDUCT
- 14 INSTALL POLYETHYLENE CONDUIT
- 15 DIRECTIONAL DRILL CONDUIT
- 16 BORE AND JACK CONDUIT
- 17 INSTALL CABLE(S) IN EXISTING CONDUIT
- 18 INSTALL CABLE(S) IN NEW CONDUIT
- 19 INSTALL CABLE(S) IN EXISTING RISER
- 20 INSTALL CABLE(S) IN NEW RISER
- 21 INSTALL CABLE(S) IN EXISTING CONDUIT STUBOUTS
- 22 INSTALL NEW CONDUIT INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
- 23 INSTALL NEW RISER INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE)
- 24 INSTALL NEW CONDUIT INTO EXISTING POLE MOUNTED CABINET
- 25 INSTALL NEW RISER INTO EXISTING POLE MOUNTED CABINET
- 26 TERMINATE FIBER-OPTIC CABLE ON EXISTING INTERCONNECT CENTER IN CCTV EQUIPMENT CABINET
- 27 INSTALL NEW TELEMETRY INTERFACE PANEL IN TRAFFIC SIGNAL CONTROLLER CABINET
- 28 INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS, AND FUSION SPLICE CABLE IN CABINET
- 29 INSTALL UNDERGROUND SPLICE ENCLOSURE
- 30 INSTALL AERIAL SPLICE ENCLOSURE
- 31 INSTALL UNDERGROUND SPLICE ENCLOSURE
- 32 MODIFY EXISTING SPLICE ENCLOSURE
- 33 REMOVE EXISTING SPLICE CABINET

- 34 INSTALL CABINET FOUNDATION
- 35 REMOVE EXISTING CABINET FOUNDATION
- 36 INSTALL CCTV CAMERA ASSEMBLY
- 37 INSTALL CCTV CAMERA WOOD POLE
- 38 INSTALL CCTV CAMERA METAL POLE AND FOUNDATION
- 39 INSTALL STANDARD (ELECTRICAL) JUNCTION BOX
- 40 INSTALL OVERSIZED JUNCTION BOX
- 41 INSTALL SPECIAL OVERSIZED JUNCTION BOX
- 42 INSTALL WOOD POLE
- 43 REMOVE EXISTING WOOD POLE
- 44 INSTALL AERIAL GUY ASSEMBLY
- 45 INSTALL STANDARD GUY ASSEMBLY
- 46 INSTALL SIDEWALK GUY ASSEMBLY
- 47 INSTALL MESSENGER CABLE
- 48 REMOVE EXISTING COMMUNICATIONS CABLE AND MESSENGER CABLE
- 49 REMOVE EXISTING COMMUNICATIONS CABLE
- 50 INSTALL TELEPHONE SERVICE
- 51 INSTALL CABLE STORAGE RACKS (SNOW SHOES) AND STORE 100 FEET OF CABLE
- 52 INSTALL DELINEATOR MARKER
- 53 STORE 30 FEET OF COMMUNICATIONS CABLE (EACH CABLE), EXCEPT AS NOTED ON PLANS
- 54 LASH CABLE(S) TO EXISTING MESSENGER CABLE
- 55 LASH CABLE(S) TO EXISTING SIGNAL /COMMUNICATION CABLE
- 56 LASH CABLE(S) TO NEW MESSENGER CABLE
- 57 MODIFY EXISTING ELECTRICAL SERVICE
- 58 INSTALL NEW ELECTRICAL SERVICE
- 59 INSTALL NEW POLE MOUNTED CABINET
- 60 INSTALL LOOP LEAD-IN CABLE

LEGEND

	NEW FIBER OPTIC COMMUNICATIONS CABLE
	EXISTING COMMUNICATIONS CABLE
	EXISTING COMMUNICATIONS CABLE TO BE REMOVED
	NEW CONDUIT
	EXISTING CONDUIT
	NEW DIRECTIONAL DRILLED CONDUIT
	NEW GUARDRAIL
	NEW CHAIN LINK FENCE
	EXISTING GUARDRAIL
	EXISTING GUIDERAIL
	EXISTING CONCRETE BARRIER
	EXISTING RIGHT OF WAY
	NEW JUNCTION BOX
	EXISTING JUNCTION BOX
	NEW SPECIAL OVERSIZED JUNCTION BOX WITH SPLICE ENCLOSURE
	EXISTING SPECIAL OVERSIZED JUNCTION BOX WITH NEW SPLICE ENCLOSURE
	EXISTING SPECIAL OVERSIZED JUNCTION BOX WITHOUT SPLICE ENCLOSURE
	NEW WOOD POLE
	EXISTING WOOD POLE
	NEW SPLICE ENCLOSURE
	EXISTING SPLICE ENCLOSURE
	NEW METAL POLE
	EXISTING METAL POLE
	NEW CCTV CAMERA ASSEMBLY
	EXISTING CCTV CAMERA ASSEMBLY
	NEW STANDARD GUY ASSEMBLY
	EXISTING STANDARD GUY ASSEMBLY
	NEW SIDEWALK GUY ASSEMBLY
	NEW SIGNAL CABINET
	EXISTING SIGNAL CABINET
	NEW FIELD EQUIPMENT CABINET
	EXISTING FIELD EQUIPMENT CABINET
	NEW YAGI ANTENNA (SINGLE)
	2.4 GHZ BROADBAND ETHERNET RADIO
	NEW ELECTRICAL SERVICE
	EXISTING ELECTRICAL SERVICE
	SIGNAL POLE
	EXISTING ITS DEVICE NUMBER
	SIGNAL INVENTORY NUMBER

CONSTRUCTION NOTE SYMBOLOGY KEY

NUMBER OF CABLE(S), LOOPS, ETC.		NUMBER OF FIBERS / TWISTED PAIRS PER CABLE, ETC.
NUMBER OF RISER(S) / CONDUIT(S)		DIAMETER OF RISER(S) / CONDUIT(S) (INCH)
NUMBER OF DEVICES		NUMBER OF FIBERS

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

HNTB HNTB NORTH CAROLINA, P.C.
343 E. Six Forks Road, Suite 200
Raleigh, North Carolina 27609
NC License No: C-1554
(919) 546-8997

Plans Prepared for: 250 N. Greenfield Place, Garner, NC 27529	CONSTRUCTION NOTES AND LEGEND Division 12 Gaston Co. Gastonia PLAN DATE: September 2016 REVIEWED BY: H.L. Winstead PREPARED BY: J.A. Wagner REVIEWED BY: N.R. Simmons	SEAL NATASHA R. SIMMONS ENGINEER								
SCALE NONE	REVISIONS <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>NO.</th> <th>REVISIONS</th> <th>INIT.</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	NO.	REVISIONS	INIT.	DATE					DocuSigned by: 11/8/2016 SIGNATURE DATE CADD File name: I-5000 SCP-01.dgn
NO.	REVISIONS	INIT.	DATE							