



REMOVE WIRELESS ASSEMBLIES, CABINET, ELECTRICAL SERVICE, AND FIBER AFTER WORK ZONE TRAFFIC CONTROL TMP FINAL PLAN. DELIVER WIRELESS ASSEMBLIES AND CABINET/EQUIPMENT TO DIVISION 12 TRAFFIC SERVICES. CUT EXISTING FIBER AT POLE #BS5 AND REMOVE EXISTING FIBER AND MESSENGER CABLE. RELOCATE BOTH FIBER-OPTIC VIDEO TRANSCIEVERS TO CCTV CABINETS #5 (SCP. 2) AND #7 (SCP. 4).

NOTES:

1. ATTACH MESSENGER CABLE 40" BELOW POWER AND ON THE FRONT SIDE OF THE POLE UNLESS OTHERWISE NOTED.
2. BOND MESSENGER CABLE AND RISER TO POLE GROUND.
- 3A. BOND TRACER WIRE TO EQUIPMENT GROUND BUS.
- 3B. DO NOT BOND TRACER WIRE TO EQUIPMENT GROUND BUS.
4. INTERCEPT EXISTING CONDUITS INSTALLED BY OTHERS FOR USE BY SIGNAL SYSTEM FIBER.
5. INSTALL FIBER IN SPARE CONDUIT.
6. RELOCATE EXISTING WIRELESS ASSEMBLY TO NEW CABINET DURING WORK ZONE TRAFFIC CONTROL TMP PHASE 1, STEP 1.
7. AFTER WORK ZONE TRAFFIC CONTROL TMP FINAL PHASE AND FIBER-OPTIC CABLE CONSTRUCTION IS COMPLETE, REMOVE EXISTING WIRELESS ASSEMBLY AND DELIVER TO DIVISION 12 TRAFFIC SERVICES.

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

**HNTB**  
HNTB NORTH CAROLINA, P.C.  
343 E. Six Forks Road, Suite 200  
Raleigh, North Carolina 27609  
NC License No: C-1554  
(919) 546-8997

<p>Plans Prepared for:</p> <p>750 N. Greenfield Pkwy., Garner, NC 27529</p>	<p><b>CABLE ROUTING PLAN</b></p>		<p>SEAL</p> <p>SEAL 031464 NATASHA R. SIMMONS ENGINEER</p>					
	<p>Division 12 Gaston Co. Gastonia</p> <p>PLAN DATE: September 2016 REVIEWED BY: H.L. Winstead</p> <p>PREPARED BY: J.A. Wagner REVIEWED BY: N.R. Simmons</p>	<table border="1"> <thead> <tr> <th>REVISIONS</th> <th>INIT.</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>		REVISIONS	INIT.	DATE		
REVISIONS	INIT.	DATE						