Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

PROJ. REFERENCE NO.	SHEET NO.
I-5000	X-1C

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

Station Rpd	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut (cu. yd.)
13+00.00	44	81	270
13+50.00	37	191	190
14+00.00	25	369	60
14+50.00	12	500	7
15+00.00	0	606	0
15+50.00	0	648	0
16+00.00	0	547	0
16+50.00	0	452	5
17+00.00	0	339	27
17+50.00	0	394	22
18+00.00	0	765	0
18+50.00	0	1448	0
19+00.00	0	1483	0
19+50.00	0	970	0
20+00.00	28	900	0
20+50.00	61	729	6
21+00.00	46	343	87
21+50.00	19	138	187
22+00.00	15	82	231
22+50.00	9	80	221
23+00.00	0	106	185
23+50.00	0	128	168
24+00.00	18	157	175
24+50.00	139	296	139
25+00.00	284	491	0
25+50.00	312	478	0
26+00.00	346	333	0
26+50.00	399	250	0
27+00.00	423	203	0
27+50.00	430	181	0
28+00.00	394	213	0
28+50.00	225	294	0
29+00.00	65	419	0
29+50.00	96	503	0
30+00.00	148	1594	0
30+50.00	133	2999	0
31+00.00	61	3697	0
31+50.00	6	3999	0
32+00.00	0	3665	0
32+50.00	0	3394	0
33+00.00	0	3282	0
33+50.00	0	2931	0
34+00.00	59	1976	0
34+50.00	71	972	0
35+00.00	25	480	0

Station Trail	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
15+00.00	0	0
15+50.00	27	0
16+00.00	18	2
16+50.00	5	19

Station Trail	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
17+00.00	5	47
17+33.46	3	112

Station Trail	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
29+01.26	0	0
29+50.00	0	2557
29+93.97	0	2228

Station Trail	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
31+58.64	0	0
32+00.00	0	228
32+50.00	0	231
33+00.00	0	158
33+50.00	0	84
34+00.00	0	31
34+50.00	0	20
35+00.00	0	22
35+50.00	0	36
36+00.00	0	44
36+50.00	0	52
37+00.00	0	64
37+50.00	0	59
38+00.00	0	58
38+50.00	0	65
39+00.00	0	56
39+50.00	0	39
40+00.00	0	27
40+50.00	0	21
41+00.00	0	15
41+50.00	4	5
42+00.00	6	1
42+50.00	5	2
43+00.00	4	2
43+50.00	2	1
44+00.00	1	12
44+50.00	19	13
45+00.00	47	5
45+50.00	29	9
46+00.00	0	29
46+50.00	60	27
47+00.00	93	6
47+50.00	32	4
48+00.00	26	4

Station Rpd/Trial	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
20+00.00	0	0
20+50.00	0	450
21+00.00	0	509
21+50.00	13	288
22+00.00	13	197
22+50.00	0	230
23+00.00	0	228
23+50.00	0	213
24+00.00	0	190
24+50.00	15	88
25+00.00	48	8
25+50.00	50	0
26+00.00	24	0
26+50.00	21	0
27+00.00	32	0
27+50.00	56	0
28+00.00	149	0
28+50.00	311	0
29+00.00	643	0
29+50.00	1127	0
30+00.00	1631	0
30+50.00	2185	0
31+00.00	2603	0

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
56+00.00	0	0
56+50.00	14	0
57+00.00	27	1
57+50.00	25	5
58+00.00	28	6
58+50.00	35	5
59+00.00	37	6
59+50.00	33	13
60+00.00	35	16
60+50.00	41	13
61+00.00	44	11
61+50.00	39	11
62+00.00	34	6
62+50.00	30	2
63+00.00	23	3
63+50.00	22	3
64+00.00	26	4
64+50.00	35	3
65+00.00	40	2
65+50.00	75	1
66+00.00	74	8
66+50.00	35	9
67+00.00	36	1
67+50.00	33	0
68+00.00	31	0
68+50.00	18	0

Station Lpb	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+00.00	0	0
12+50.00	63	0
13+00.00	72	0
13+50.00	76	0
14+00.00	74	0
14+50.00	68	0
15+00.00	63	0
15+50.00	32	1
16+00.00	9	11
16+50.00	11	21
17+00.00	10	19