Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDES BACKFILL FOR UNDERCUT

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
W-5520	X-1B

CROSS-SECTION SUMMARY

Station L1 LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
115+00.00	0	0	0
115+50.00	91	15	0
120+50.00	0	0	0
121+00.00	50	0	0
121+50.00	103	0	0
122+00.00	107	0	0
122+50.00	63	0	0
123+00.00	55	0	0
123+50.00	76	27	0
124+00.00	33	102	0
124+50.00	5	119	10
125+00.00	52	44	52
125+50.00	61	91	51
126+00.00	14	229	19
126+50.00	10	191	10
127+00.00	5	54	0

Station L1 RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
106+10.00	0	0	0
106+50.00	6	28	12
107+00.00	12	62	61
107+50.00	10	69	72
108+00.00	11	60	52
108+50.00	12	29	47
109+00.00	14	18	20
109+50.00	21	19	0
114+00.00	0	0	0
114+50.00	7	5	0
115+00.00	15	16	0
115+50.00	16	49	0
116+00.00	8	38	0
116+50.00	5	3	0
117+00.00	16	32	0
117+50.00	17	33	0
118+00.00	9	47	0
118+50.00	3	43	0

Station L1 CL	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
106+10.00	0	0	0
106+50.00	30	0	0
107+00.00	78	0	0
107+50.00	75	0	0
108+00.00	76	0	0
108+50.00	85	0	0
109+00.00	85	0	0
109+50.00	85	0	0
110+00.00	90	0	0
110+50.00	113	0	0
111+00.00	103	0	0
111+50.00	75	0	0
112+00.00	73	0	0
112+50.00	69	0	0
113+00.00	69	0	0
113+50.00	70	0	0
114+00.00	72	0	0
114+50.00	74	0	0
115+00.00	75	0	0
115+50.00	82	0	0
116+00.00	0	0	0
116+50.00	53	0	0
117+00.00	103	0	0
117+50.00	89	0	0
118+00.00	75	0	0
118+50.00	75	0	0
119+00.00	83	0	0
119+50.00	77	0	0
120+00.00	65	0	0
120+50.00	68	0	0
121+00.00	77	0	0
121+50.00	81	0	0
122+00.00	79	0	0
122+50.00	72	0	0
123+00.00	65	0	0
123+50.00	62	0	0
124+00.00	57	2	0
124+50.00	47	9	0
125+00.00	46	9	0
125+50.00	51	4	0
126+00.00	51	4	0
126+50.00	83	2	0
127+00.00	58	0	0

Station L2 LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
214+50.00	0	0	0
215+00.00	11	0	0
215+50.00	18	5	0
216+00.00	14	15	0
216+50.00	16	30	0
217+00.00	22	63	0
217+50.00	75	44	0
218+00.00	73	0	0
218+50.00	14	50	0
219+00.00	27	50	0
219+50.00	70	0	0
220+00.00	71	0	0
220+50.00	62	0	0
221+00.00	75	0	0
221+50.00	66	0	0
222+00.00	56	0	0
222+50.00	48	1	0
223+00.00	27	60	0
223+50.00	11	135	0
224+00.00	7	110	15
224+50.00	71	34	54
225+00.00	167	0	89
225+50.00	223	0	112
226+00.00	168	0	71
226+15.00	0	0	3

Station L2 RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
205+00.00	0	0	0
205+50.00	25	73	47
206+00.00	21	43	85
206+50.00	12	44	64
207+00.00	14	40	41
207+50.00	10	44	27
208+00.00	6	56	12
208+50.00	2	32	0
221+00.00	0	0	0
221+50.00	6	1	0
222+00.00	11	3	0
222+50.00	8	4	0
223+00.00	10	2	0
223+50.00	8	8	0
224+00.00	4	17	0
224+50.00	6	16	0
225+00.00	8	11	0
225+50.00	11	6	0
226+00.00	15	3	0
226+15.00	0	0	0

Station L2 CL	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
205+00.00	0	0	0
205+50.00	30	0	0
206+00.00	47	3	0
206+50.00	38	8	0
207+00.00	46	6	0
207+50.00	57	0	0
208+00.00	68	0	0
208+50.00	73	0	0
209+00.00	77	0	0
209+50.00	87	0	0
210+00.00	96	0	0
210+50.00	98	0	0
211+00.00	98	0	0
211+50.00	98	0	0
212+00.00	97	0	0
212+50.00	96	0	0
213+50.00	0	0	0
214+00.00	69	0	0
214+50.00	39	0	0
215+00.00	36	0	0
215+50.00	33	0	0
216+00.00	31	0	0
216+50.00	31	0	0
217+00.00	35	0	0
217+50.00	39	0	0
218+00.00	41	0	0
218+50.00	43	0	0
219+00.00	46	0	0
219+50.00	44	0	0
220+00.00	44	0	0
220+50.00	45	0	0
221+00.00	45	0	0
221+50.00	41	1	0
222+00.00	37	3	0
222+50.00	36	6	0
223+00.00	29	20	0
223+50.00	22	29	0
224+00.00	23	18	0
224+50.00	28	7	0
225+00.00	31	4	0
225+50.00	33	2	0
226+00.00	36	3	0
226+15.00	0	0	0

Station L3 LT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
324+00.00	9	4	0
324+50.00	16	29	17
325+00.00	13	9	34
325+50.00	11	177	29
326+00.00	7	247	22
326+50.00	8	169	10

Station L3 RT	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
303+20.00	0	0	0
303+50.00	107	0	25
304+00.00	481	0	99
304+50.00	606	0	102
305+00.00	556	0	78
305+50.00	428	0	56
306+00.00	234	0	22
306+50.00	61	0	0

Station L3 CL	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)	Undercut Exc. (cu. yd.)
303+50.00	0	0	0
304+00.00	44	3	0
304+50.00	36	8	0
305+00.00	29	13	0
305+50.00	31	10	0
306+00.00	30	13	0
306+50.00	30	12	0
307+00.00	33	6	0
307+50.00	38	3	0
308+00.00	41	3	0
308+50.00	40	4	0
309+00.00	36	9	0
309+50.00	38	9	0
310+00.00	41	3	0