1 1 A 1 B 1C-1 THRU 1C-2 2A-1 THRU 2A-4 2B-1 THRU 2B-4 2C-1 2C-2 2C-3

SHEET NUMBER

2C-4 2C-5 20-6 2G-1 THRU 2G-4 3B-1 3D-1 THRU 3D-2 3G-1 3P-1 4 THRU 5 6 THRU 9 TMP-1 THRU TMP-14A PMP-1 THRU PMP-3 EC-1 THRU EC-12 RF – 1 SIGN-1 THRU SIGN-5 UO-1 THRU UO-2 X – 1 A X-1 THRU X-36 S01-1 THRU S01-28 S02-1 THRU S02-28

C−1 THRU C-6

CULVERT PLANS

INDEX OF SHEETS SHEET TITLE SHEET INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARD DRAWINGS CONVENTIONAL SYMBOLS SURVEY CONTROL DATA SHEETS PAVEMENT SCHEDULE, TYPICAL SECTIONS, AND WEDGING DETAILS DETOUR PLAN SHEETS GUARDRAIL EXTRA LENGTH POST DETAIL TEMPORARY B-77 DETAIL NG 25 DETAIL SLOTTED DRAIN DETAIL TEMPORARY STEEL COVER DETAIL GUIDE FOR PAVING SHOULDERS UNDER BRIDGES DETAIL TEMPORARY SHORING DETAILS ROADWAY SUMMARIES DRAINAGE SUMMARY GEOTECHNICAL SUMMARY PARCEL INDEX SHEET PLAN SHEETS PROFILE SHEETS TRAFFIC MANAGEMENT PLANS PAVEMENT MARKING PLANS EROSION CONTROL PLANS REFORESTATION PLAN SIGNING PLANS UTILITY BY OTHERS PLANS CROSS-SECTION SUMMARY SHEET CROSS-SECTIONS STRUCTURE PLANS (-LWBL-) STRUCTURE PLANS (-LEBL-)


STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARD DRAWINGS

EFF. 01-17-2012 REV. 02-29-2016	
2012 ROADWAY ENGLISH STANDARD DRAWINGS	GENERAL 1
The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch – N. C. Department of Transportation – Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:	
STD.NO. TITLE	GRADE LIN GRADING /
DIVISION 2 - EARTHWORK 200.02 Method of Clearing - Method II 225.01 Guide for Grading Subgrade - Interstate and Freeway 225.02 Guide for Grading Subgrade - Secondary and Local 225.04 Method of Obtaining Superelevation - Two Lane Pavement 225.05 Method of Obtaining Superelevation - Divided Highways	
DIVISION 3 - PIPE CULVERTS 300.01 Method of Pipe Installation	CLEARING
DIVISION 4 - MAJOR STRUCTURES 422.10 Reinforced Bridge Approach Fills	
DIVISION 5 - SUBGRADE, BASES AND SHOULDERS 560.01 Method of Shoulder Construction - High Side of Superelevated Curve - Method I 560.02 Method of Shoulder Construction - High Side of Superelevated Curve - Method II	SUPERELE
DIVISION 6 - ASPHALT BASES AND PAVEMENTS 654.01 Pavement Repairs 665.01 Asphalt Shoulders - Milled Rumble Strips	
DIVISION 8 - INCIDENTALS 815.02 Subsurface Drain 838.01 Concrete Endwall for Single and Double Pipe Culverts - 15" thru 48" Pipe 90 Skew 838.11 Brick Endwall for Single and Double Pipe Culverts - 15" thru 48" Pipe 90 Skew 840.00 Concrete Base Pad for Drainage Structures 840.04 Concrete Open Throat Catch Basin - 12" thru 48" Pipe 840.05 Brick Open Throat Catch Basin - 12" thru 48" Pipe 840.18 Concrete Grated Drop Inlet Type 'B' - 12" thru 36" Pipe 840.20 Frames and Wide Slot Flat Grates 840.22 Frames and Wide Slot Sag Grates	SHOULDER
 Anchorage for Frames - Brick or Concrete or Precast Brick Grated Drop Inlet Type 'B' - 12" thru 36" Pipe Frames and Narrow Slot Flat Grates Concrete Junction Box - 12" thru 66" Pipe Brick Junction Box - 12" thru 66" Pipe Brick Junction Box - 12" thru 66" Pipe Traffic Bearing Grated Drop Inlet - for Cast Iron Double Frames and Grates Precast Drainage Structure 	SUBSURFAC
 840.46 Traffic Bearing Precast Drainage Structure 840.54 Manhole Frame and Cover 840.66 Drainage Structure Steps 840.72 Pipe Collar 846.01 Concrete Curb, Gutter and Curb & Gutter 846.04 Drop Inlet Installation in Shoulder Berm Gutter 862.01 Guardrail Placement 	GUARDRAII
62.02 Guardrail Installation 862.03 Structure Anchor Units 862.04 Anchoring End of Guardrail - B-77 and B-83 Anchor Units 866.02 Woven Wire Fence - with Wood Post 876.02 Woven Wire Fence - with Wood Post 876.02 Guide for Rip Rap at Pipe Outlets	TEMPORAR

END BENTS:

UTILITIES:



NOTES:

INE:

AND SURFACING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

NG:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

EVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 & STD. NO. 225.05 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS, SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

ER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01 & STD. NO. 560.02.

FACE DRAINS:

SUBSURFACE DRAINS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 815.02 AT LOCATIONS DIRECTED BY THE ENGINEER.

AIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

ARY SHORING:

SHORING REQUIRED FOR THE MAINTENANCE OF TRAFFIC NOT SHOWN ON THE PLANS WILL BE PAID FOR AT THE CONTRACT PRICE FOR "TEMPORARY SHORING".

THE ENGINEER SHALL CHECK THE STRUCTURE END BENT PLANS, DETAILS, AND CROSS-SECTION PRIOR TO SETTING OF THE SLOPE STAKES FOR THE EMBANKMENT OR EXCAVATION APPROACHING A BRIDGE.

UTILITY OWNERS ON THIS PROJECT ARE

Duke Energy Icard Township Water

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS.