PROJECT REFERENCE NO.	SHEET NO.
B-4447	EC-3A
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
20-2	-DET-	19+00	21+50	RT	205
20-2	-DET-	21+50	22+50	RT	95
20-2, -3	-DET-	27+75	31+50	RT	250
20-3	-DET-	31+75	32+50	RT	150
4	-L-	18+50	22+25	RT	665
4	-L-	19+25	22+50	LT	550
				SUBTOTAL	1915
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					10275
				TOTAL	12190
				SAY	12200

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
20-2	-DET-	18+50	19+00	RT	55
				SUBTOTAL	55
		ADDITIONAL PSRM TO BE INSTALLED			1245
				TOTAL	1300
				SAY	1300