

PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	
T1	WHITE LINE, RR X	<u>THERMOPLASTIC (16", 120 MILS)</u>
T2	WHITE STOPBAR	<u>THERMOPLASTIC (24", 120 MILS)</u>
T3	WHITE CROSSWALK LINE	
T6	WHITE EDGELINE	<u>THERMOPLASTIC (6", 90 MILS)</u>
T7	YELLOW EDGELINE	
T8	2 FT. - 6 FT./SP WHITE MINISKIP	<u>THERMOPLASTIC (4", 120 MILS)</u>
T9	2 FT. - 6 FT./SP YELLOW MINISKIP	
TC	10 FT. WHITE SKIP	
TD	3 FT. - 9 FT./SP WHITE MINISKIP	
TE	WHITE SOLID LANE LINE	
TI	YELLOW DOUBLE CENTER	
T11	2 FT. - 6 FT./SP WHITE MINISKIP	<u>THERMOPLASTIC (6", 120 MILS)</u>
T12	2 FT. - 6 FT./SP YELLOW MINISKIP	
TJ	10 FT. WHITE SKIP	
TK	3 FT. - 9 FT./SP WHITE MINISKIP	
TL	WHITE SOLID LANE LINE	
T13	3 FT. - 9 FT./SP WHITE MINISKIP	<u>THERMOPLASTIC (8", 120 MILS)</u>
TQ	WHITE CROSSWALK LINE	
TR	WHITE SOLID LANE LINE	
T14	3 FT. - 9 FT./SP WHITE MINISKIP	<u>THERMOPLASTIC (12", 120 MILS)</u>
TT	WHITE SOLID LANE LINE	
TA	WHITE EDGELINE	<u>THERMOPLASTIC (4", 90 MILS)</u>
TB	YELLOW EDGELINE	
TN	WHITE GORELINE	<u>THERMOPLASTIC (8", 90 MILS)</u>
TP	YELLOW DIAGONAL	
TS	WHITE GORELINE	<u>THERMOPLASTIC (12", 90 MILS)</u>
TU	WHITE DIAGONAL	
UA	LEFT TURN ARROW	<u>THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS)</u>
UB	RIGHT TURN ARROW	
UC	STRAIGHT ARROW	
UE	COMBO RIGHT/STRAIGHT ARROW	
UG	COMBO LEFT/RIGHT/STRAIGHT ARROW	
UP	MERGE ARROW	
UT	U-TURN ARROW	
UI	ALPHANUMERIC CHARACTERS	<u>THERMOPLASTIC PAVEMENT MARKING SYMBOLS (120 MILS)</u>
VA	WHITE EDGELINE	<u>POLYUREA (4") Highly Reflective Elements</u>
VB	YELLOW EDGELINE	
VC	10 FT. WHITE SKIP	

LEGEND

GENERAL	PAVEMENT MARKINGS
DIRECTION OF TRAFFIC FLOW	PAVEMENT MARKING SYMBOLS
NORTH ARROW	
PROPOSED PVMT.	
EXIST. PVMT.	

GENERAL NOTES

- THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.
- A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
US HWY 70	THERMOPLASTIC	SNOWPLOWABLE
SLOCUM RD	THERMOPLASTIC	SNOWPLOWABLE
SR 1771	THERMOPLASTIC	NONE
SR 1772	THERMOPLASTIC	NONE
BRIDGE	POLYUREA	PERMANENT RAISED
 - B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.
 - E) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.
 - F) PASSING ZONES WILL BE DETERMINED IN THE FIELD AND MUST BE APPROVED BY THE ENGINEER.
 - G) STOP BAR LOCATION AT NON-SIGNALIZED INTERSECTIONS MAY BE ADJUSTED AS DIRECTED BY THE ENGINEER.
 - H) REMOVE ALL RESIDUE AND SURFACE LAITANCE BY ACCEPTABLE METHODS ON CONCRETE BRIDGE DECKS PRIOR TO PLACING POLYUREA PAVEMENT MARKING MATERIAL.
 - I) UNLESS OTHERWISE SPECIFIED, HEATED-IN-PLACE THERMOPLASTIC MAY BE USED IN LIEU OF EXTRUDED THERMOPLASTIC FOR STOP BARS, SYMBOLS, CHARACTERS AND DIAGONALS. IF HEATED-IN-PLACE IS USED, IT SHALL BE PAID FOR USING THE EXTRUDED THERMOPLASTIC PAY ITEM.

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO-LANE AND MULTILANE ROADWAYS
1205.03	PAVEMENT MARKINGS - EXIT AND ENTRANCE RAMP
1205.04	PAVEMENT MARKINGS - INTERSECTIONS
1205.05	PAVEMENT MARKINGS - TURN LANES
1205.06	PAVEMENT MARKINGS - LANE DROPS
1205.08	PAVEMENT MARKINGS - SYMBOLS AND WORD MESSAGES
1205.09	PAVEMENT MARKINGS - PAINTED ISLANDS
1205.10	PAVEMENT MARKINGS - SCHOOL AREAS
1205.11	PAVEMENT MARKINGS - RAILROAD CROSSINGS
1205.12	PAVEMENT MARKINGS - BRIDGES
1205.13	PAVEMENT MARKINGS - LANE REDUCTIONS
1250.01	RAISED PAVEMENT MARKERS - INSTALLATION SPACING
1251.01	RAISED PAVEMENT MARKERS - PERMANENT AND TEMPORARY
1253.01	RAISED PAVEMENT MARKERS - SNOWPLOWABLE
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION
1267.01	FLEXIBLE DELINEATORS - INSTALLATION
1267.02	FLEXIBLE DELINEATORS - SPACING TABLES
1267.03	FLEXIBLE DELINEATORS - INTERCHANGE PLACEMENT

TIP NO. R-5516	SHEET NO. PMP-2
Documented by: APPROVED: _____ <small>SCDGEAEF80A4FA</small>	
DATE: 3/15/2017	
SEAL 	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

3/14/2017 11:58:41 AM element_Markings_PMP-2.dgn

SEPI
ENGINEERING & CONSTRUCTION
1025 Wade Avenue
Raleigh, NC 27605
Tel: 919-789-9977
Fax: 919-789-9591
License: C-2197

**PAVEMENT MARKING SCHEDULE
GENERAL NOTES AND ROADWAY
STANDARD DRAWING SCHEDULE**