

- ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL COMMUNICATION CIRCUITS ARE FUNCTIONING PROPERLY. ALL WORK IS NOT COMPLETE UNTIL THE SIGNAL SYSTEM IS BACK UP AND OPERATIONAL.
- 2. MODIFY RADIO INSTALLATION (RELOCATE EXISTING RADIO, MOUNTING HARDWARE, AND ANTENNA TO NEW SIGNAL CABINET/SIGNAL POLE LOCATION).
- 3. INSTALL NEW COAXIAL CABLE THROUGH A NEW 2" RISER AND WEATHERHEAD. INSTALL COAXIAL CABLE SHIELD GROUNDING AND WEATHERPROOFING KIT.

TMP PHASE 2



DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED (MAINTAIN WIRELESS SYSTEM)



Prepared in the Offices of:

WIRELESS COMMUNICATIONS PLANS

DIVISION 2 CRAVEN CO. ______Docusigned by HAVELOCK PLAN DATE: FEBRUARY 2017 REVIEWED BY: 1. N. WELLY 50 N. Greenfield Pkwy., Garner, NC 27529 PREPARED BY: H. T. BERGGREN REVIEWED BY:

Gregory d. Fuller 2/15/2017

SEAL

SEAL

023919

PROJECT REFERENCE NO.

R-5516

SCP 3

REVISIONS