

## REFORESTATION

□ TREE REFORESTATION SHALL 3E PLANTED 6 FT. TO 10 FT. ON CENTER, RANDOM SPACING, AVERAGING 8 FT. ON CENTER, APPROXIMATELY 680 PLANTS PER ACRE.

REFORESTATION MIXTURE, TYPE, SIZE, AND FURNISH SHALL CONFORM TO THE FOLLOWING: 34% LIRIODENDRON TULIPIFERA

33% PLATANUS OCCIDENTALIS

33% SALIX NIGRA

PROJECT REFERENCE NO.		SHEET NO.
B-5/59		RF-I
R/W SHEET NO.		
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER
	B-5/59 rw sheet no roadway design	B-5/59 rw sheet no. roadway design

YELLOW POPLAR	12 in – 18 in BR
SYCAMORE	12 in – 18 in BR
BLACK WILLOW	12 in – 18 in BR

## **REFORESTATION DETAIL SHEET**

N.C.D.O.T. - ROADSIDE ENVIRONMENTAL UNIT