PROJECT REFERENCE NO.	SHEET NO.
U-5796	EC-3
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL (SLOPES)

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
6	RP. A	7+60	12+40	RT.	2,915
5 & 6	RP. B	10+20	13+70	LT.	1,941
5 & 6	RP. C	10+50	15+80	RT.	3,379
6	RP. D	9+50	12+60	LT.	1,501
			SUBTOTAL		9,736

MATTING FOR EROSION CONTROL (DITCHES)

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4 & 5	-L-	180+50	182+00	LT.	190
5	-L-	190+00	191+50	LT.	70
8	-Y8-	17+65	18+00	LT.	25
8	-Y8-	21+50	22+00	LT.	35
8	-Y8-	19+36	20+00	RT.	45
8	-Y8-	21+50	22+00	RT.	35
9	-Y8-	35+50	35+93	RT.	30
9	-Y8-	36+47	37+00	LT.	40
			SUBTOTAL		470
				TOTAL	10,206
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					6,779
				TOTAL	16,985
				SAY	16,985