

PROJECT REFERENCE NO.	SHEET NO.
I-5812	5

Drainage Structure Repair Summary

PROJECT #	MAP #	STATION	Location	Remove & Replace Concrete Apron	Frame wirh Grate, STD. 840.22	Flowable Fill Excavatable	Repair of Drop Inlet	Comments
			LT, RT or Median	EA	EA	CY	EA	
I-5812	1	14+27	RT				1	Repair block wall
I-5812	1	38+29	RT				1	Repair block wall
I-5812	1	39+95	Median			1		
I-5812	1	86+80	Median			1		
I-5812	1	92+00	Median			1		
I-5812	1	107+50	Median	1				
I-5812	1	116+10	RT	1				
I-5812	1	123+12	RT				1	Repair block wall
I-5812	1	126+30	Median			1		
I-5812	1	328+70	RT	1				
I-5812	1	355+70	RT			2		
I-5812	1	360+05	RT	1	1			
I-5812	1	367+00	RT			2		
MAP 1 TOTALS				4	1	8	3	
I-5812	3	17+25	RT			1		
MAP 3 TOTALS						1		
I-5812	5	41+10	RT	1				
MAP 5 TOTALS				1				
I-5812	9	35+00	RT	1				
I-5812	9	119+60	RT			2		
I-5812	9	122+20	RT	1				
I-5812	9	178+90	RT	1				
I-5812	9	189+15	RT	1				
I-5812	9	303+40	RT	1				
I-5812	9	342+70	RT	1				
I-5812	9	345+30	RT			1		
I-5812	9	382+10	RT	1				
MAP 9 TOTALS				7		3		
I-5812	15	14+10	RT				1	Remove brick invert & pour invert with concrete
MAP 15 TOTALS							1	
PROJECT GRAND TOTALS				12	1	12	4	