

PROJECT NO.	SHEET NO.	TOTAL NO.
I-5852B	12	

SUMMARY OF QUANTITIES

PROJECT NO.	COUNTY	MAP NO.	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	SEALING EXIST PAVEMENT CRACKS & JOINTS LB	DIAMOND GRINDING PCC SY	SHOULDER DRAIN LF	4" SHOULDER DRAIN PIPE LF	4" OUTLET PIPE FOR SHOULDER DRAINS LF	REMOVE & REPLACE CONCRETE APRON EA	REM & REPL CONC. EXPRESSWAY GUTTER LF	REMOVE & REPLACE CURB RAMP STD. 848.06 AND DETAIL EA	SEALING EX. PVT CRACKS (POLYMER PATCH) LB	ADJ. OF MANHOLES EA	REMOVE & RESET EXISTING GUARDRAIL LF	PORTABLE LIGHTING LS	TEMPORARY SILT FENCE LF	MATTING FOR EROSION CONTROL SY	WATTLE LF	SEEDING & MULCHING AC	INDUCTIVE LOOP SAW CUT LF		
53056.3.3	Guilford	1	I-73 NB	FROM SOUTH OF I-40 TO OLD CONCRETE JOINT SOUTH OF SR 2085 (BRYAN BLVD.)	1,2	4	MD	NO	NO	3.856	48	897.00	116,795.0					100				100.00	1.00	750		375				
TOTAL FOR MAP NO. 1										3.856		897.00	116,795.0					100				100.00	1.00	750		375				
53056.3.3	Guilford	2	RAMP TO I-40 EB	RAMP FROM I-73 NB TO I-40 EB	3	1		NO	NO	0.408	16																			
TOTAL FOR MAP NO. 2										0.408																				
53056.3.3	Guilford	3	RAMP TO I-40 WB	RAMP FROM I-73 NB TO I-40 WB	1	3	MD	NO	NO	0.378	36	519.00	8,000.0																	
TOTAL FOR MAP NO. 3										0.378		519.00	8,000.0																	
53056.3.3	Guilford	4	LOOP TO I-73 NB	FROM I-40 EB TO I-73 NB	4	1		NO	NO	0.205	20																			
		"	"	CONCRETE SECTION	5	1		NO	NO	0.022	20		260.0																	
TOTAL FOR MAP NO. 4										0.227			260.0																	
53056.3.3	Guilford	5	RAMP TO I-73 NB	RAMP FROM I-40 WB TO I-73 NB	3	1		NO	NO	0.264	16																			
		"	"	CONCRETE SECTION	6	1		NO	NO	0.012	16		116.0																	
TOTAL FOR MAP NO. 5										0.276			116.0																	
53056.3.3	Guilford	6	RAMP TO FRIENDLY AVE.	RAMP FROM I-73 NB TO FRIENDLY AVE.	7,8,9,10	3		NO	NO	0.201	36								1		1							825		
TOTAL FOR MAP NO. 6										0.201									1		1								825	
53056.3.3	Guilford	7	RAMP FROM FRIENDLY AVE.	RAMP FROM FRIENDLY AVE. TO I-73 NB	7,9,10,11	2		NO	NO	0.215	22								1		1									
TOTAL FOR MAP NO. 7										0.215									1		1									
53056.3.3	Guilford	8	RAMP TO BRYAN BLVD. WB	RAMP FROM I-73 NB TO BRYAN BLVD. WB	12	2		NO	NO	0.644	24																			
TOTAL FOR MAP NO. 8										0.644																				
53056.3.3	Guilford	9	RAMP TO BRYAN BLVD. EB	RAMP FROM I-73 NB TO BRYAN BLVD. EB	12	1		NO	NO	0.339	16																			
TOTAL FOR MAP NO. 9										0.339																				
53056.3.3	Guilford	10	I-73 SB	FROM OLD CONCRETE JOINT SOUTH OF SR 2085 (BRYAN BLVD.) TO SOUTH OF SOUTH OF I-40	1,2	3	MD	NO	NO	3.9	36	854.00	92,077.0	300	300	20	1			72					90	10	0.10			
TOTAL FOR MAP NO. 10										3.9		854.00	92,077.0	300	300	20	1		72					90	10	0.10				
53056.3.3	Guilford	11	RAMP TO FRIENDLY AVE.	RAMP FROM I-73 SB TO FRIENDLY AVE.	7,8,9,10	4		NO	NO	0.516	48								1									825		
TOTAL FOR MAP NO. 11										0.516									1									825		
53056.3.3	Guilford	12	RAMP FROM FRIENDLY AVE	ON-RAMP FROM FRIENDLY AVE. TO I-73 SB	7,9,10,11	2		NO	NO	0.534	24								1											
TOTAL FOR MAP NO. 12										0.534									1											
53056.3.3	Guilford	13	RAMP TO I-40 EB	RAMP FROM I-73 SB TO I-40 EB (CONCRETE SECTION)	2	2		NO	NO	0.058	24		811.0																	
		"	"	ASPHALT SECTION	12	2		NO	NO	1.01	24																			
TOTAL FOR MAP NO. 13										1.068			811.0																	
53056.3.3	Guilford	14	RAMP TO I-40 WB	RAMP FROM I-73 SB TO I-40 WB	12	1		NO	NO	0.402	16																			
		"	"	CONCRETE SECTION	1	1		NO	NO	0.015	16		137.0																	
TOTAL FOR MAP NO. 14										0.417			137.0																	
53056.3.3	Guilford	15	LOOP TO I-73 SB	LOOP FROM I-40 WB TO I-73 SB	4	1		NO	NO	0.185	19																			
		"	"	CONCRETE SECTION	5	1		NO	NO	0.019	19		211.0																	
TOTAL FOR MAP NO. 15										0.204			211.0																	
53056.3.3	Guilford	16	RAMP TO I-73 SB	RAMP FROM I-40 EB TO I-73 SB	1	3	MD	NO	NO	0.837	36	1,149.00	17,680.0																	
TOTAL FOR MAP NO. 16										0.837		1,149.00	17,680.0																	
TOTAL FOR PROJ NO. 53056.3.3										14.02		3,419.00	236,087.0	300	300	20	1	100	4	72	2	100.00	1.00	750	90	385	0.10	1,650		
GRAND TOTAL										14.02		3,419.00	236,087.0	300	300	20	1	100	4	72	2	100.00	1.00	750	90	385	0.10	1,650		