

PROJECT NO.	SHEET NO.	TOTAL NO.
2018CPT.08.02.10191	8	
2018CPT.08.02.20191		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	AGGREGATE SHOULDER BORROW TON	SHOULDER RECONSTRUCTION SMI	1.5" MILLING SY	0" TO 1.5" MILLING SY	INCIDENTAL MILLING SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	SURFACE COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE SY	ASPHALT SURFACE TREATMENT, MATCOAT, #78M STONE SY	EMULSION FOR ASPHALT SURFACE TREATMENT GAL	VACUUM TRUCK WK	
2018CPT.08.02.10191	Chatham	1	US 64	FROM W JOINT RR BRIDGE #11 (0.43MI W OF SR 1317 GREENSBORO AVE) TO BEGIN DIVIDED SECTION 0.36MI W OF SR 1106 (ELLINGTON RD)	1-5	2	2WU	NO	NO	1.824	32-71	894	3.65	1,820	5,600	986		6,930		409	200	75,000		30,000	0.5	
		2	US 64 EB	FROM RANDOLPH CO TO END DIVIDED SECTION 0.36MI W OF SR 1106 (ELLINGTON RD)	1, 2, 3	2	MD	NO	NO	2.334	33-37	1,144	4.67		320	1,283		4,840		286	200	46,000		18,400	0.3	
		3	US 64 WB	FROM BEGIN DIVIDED SECTION 0.36MI W OF SR 1106 (ELLINGTON RD) TO RANDOLPH CO	1, 2, 3	2	MD	NO	NO	2.331	33-37	1,142	4.66	1,800	400	917		4,560		269	200	46,000		18,400	0.3	
		4	US 64	FROM E JT BRIDGE #34 (700FT E OF PROGRESS BLVD) TO BEGIN MED DIV SECTION 1250FT E OF SR 1003 (SILK HOPE RD)	6	2	MU	NO	NO	0.756	68	370	1.51	6,850			600		3,550		209	600				
		5	US 64 EB	FROM BEGIN MED DIV SECTION 1250FT E OF SR 1003 (SILK HOPE RD) TO PVT. JT N OF SR 2170 REIVES CHAPEL RD	7	2	MD	NO	NO	3.047	30	1,493	6.09	660		917		5,900		348	300		54,000	18,900	0.4	
		6	US 64 WB	FROM PVT. JT N OF SR 2170 REIVES CHAPEL RD TO END MED DIV SECTION 1250FT E OF SR 1003 (SILK HOPE RD)	8	2	MD	NO	NO	3.169	30	1,553	6.34	1,680		583		5,725		338	500					
TOTAL FOR PROJ NO. 2018CPT.08.02.10191										13.461		6,596	26.92	12,810	6,320	5,286		31,505		1,859	2,000	167,000	54,000	85,700	1.5	
2018CPT.08.02.20191	Chatham	7	SR 1346 (SILK HOPE GUM SPRINGS/LIBERTY RD)	FROM SR 1332 (JESSE BRIDGES RD) TO NC 87	9	2	2WU	NO	NO	10.07	22	4,934	20.14			856	12,080			725	3,200	124,950		50,000	1.0	
		8	SR 1003 (SILK HOPE RD)	FROM PVT. JT. N OF US 64 TO SR 1334 (WADE HARRIS RD)	10	2	2WU	NO	NO	6.338	20	3,106	12.68			778		5,655	379	2,000		75,000	26,250		0.5	
TOTAL FOR PROJ NO. 2018CPT.08.02.20191										16.408		8,040	32.82			1,634	12,080		5,655	1,104	5,200	124,950	75,000	76,250	1.5	
GRAND TOTAL										29.869		14,636	59.74	12,810	6,320	6,920	12,080	31,505	5,655	2,963	7,200	291,950	129,000	161,950	3	