PROJECT NO.	SHEET NO.	TOTAL NO.
2018CPT.08.02.10191 2018CPT.08.02.20191	9	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/ GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4510000000-N LAW ENFORCE-MENT HR	4685000000-E 4" X 90 M WHITE THERMO LF	4685000000-E 4" X 90 M YELLOW THERMO LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4700000000-E 12" x 90M YELLOW THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG SCHOOL 120 M EA	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO STR ARROW 90 M EA	4725000000-E THERMO STR & LT ARROW 90 M EA	4725000000-E THERMO STR & RT ARROW 90 M EA	4725000000-E THERMO LT STR RT ARROW 90 M EA	4810000000-E 4" WHITE PAINT LF	4900000000-N YELLOW & YELLOW MARKERS EA	4905000000-N SNOW PLOWABLE MARKERS Y & Y MARKERS EA	4905000000-N SNOW PLOWABLE MARKERS C & R MARKERS EA
2018CPT.08.02.10191	Chatham	1	US 64	FROM W JOINT RR BRIDGE #11 (0.43MI W OF SR 1317 GREENSBORO AVE) TO BEGIN DIVIDED SECTION 0.36MI W OF SR 1106 (ELLINGTON RD)	1-5	2	2WU	1.824	32-71	400		10	19,626		23,144	7,530	150	255		67	13	20				5,000		300	470
		2	US 64 EB	FROM RANDOLPH CO TO END DIVIDED SECTION 0.36MI W OF SR 1106 (ELLINGTON RD)	1, 2, 3	2	MD	2.334	33-37	400		20	12,500	12,500		6,500		135		12	10	20							350
		3	US 64 WB	FROM BEGIN DIVIDED SECTION 0.36MI W OF SR 1106 (ELLINGTON RD) TO RANDOLPH CO	1, 2, 3	2	MD	2.331	33-37	400		20	12,500	12,500		6,000		65		10	4	20							300
		4	US 64	FROM E JT BRIDGE #34 (700FT E OF PROGRESS BLVD) TO BEGIN MED DIV SECTION 1250FT E OF SR 1003 (SILK HOPE RD)	6	2	MU	0.756	68	300		10	8,233	8,233	10,960	3,200		95		26	8	8	2			5,050		115	200
		5	US 64 EB	FROM BEGIN MED DIV SECTION 1250FT E OF SR 1003 (SILK HOPE RD) TO PVT. JT N OF SR 2170 REIVES CHAPEL RD	7	2	MD	3.047	30	500		20	16,100	16,100		7,300		100		21	7	28	1						460
		6	US 64 WB	FROM PVT. JT N OF SR 2170 REIVES CHAPEL RD TO END MED DIV SECTION 1250FT E OF SR 1003 (SILK HOPE RD)	8	2	MD	3.169	30	500	*	20	16,900	16,900		7400		90		18	9	24		1	1				470
TOTAL FOR PROJ NO. 2018CPT.08.02.10191								**13.461**		**2,500**	**1**	**100**	**85,859**	**66,233**	**34,104**	**37,930**	**150**	**740**		**154**	**51**	**120**	**3**	**1**	**1**	**10,050**		**415**	**2,250**
													152,092		**72,034**					**330**								**2,665**	
2018CPT.08.02.20191	Chatham	7	SR 1346 (SILK HOPE GUM SPRINGS/LIBERTY RD)	FROM SR 1332 (JESSE BRIDGES RD) TO NC 87	9	2	2WU	10.07	22	1,150			108,353		108,353	600		100	12								890		
		8	SR 1003 (SILK HOPE RD)	FROM PVT. JT. N OF US 64 TO SR 1334 (WADE HARRIS RD)	10	2	2WU	6.338	20	800	*		68,197		68,197	700												
TOTAL FOR PROJ NO. 2018CPT.08.02.20191								**16.408**		**1,950**	**1**		**176,550**		**176,550**	**1,300**		**100**	**12**								**890**		
													176,550		**177,850**														
GRAND TOTAL								**29.869**		**4,450**	**1**	**100**	**262,409**	**66,233**	**210,654**	**39,230**	**150**	**840**	**12**	**154**	**51**	**120**	**3**	**1**	**1**	**10,050**	**890**	**415**	**2,250**
													328,642		**249,884**					**330**								**2,665**	