

PROJECT NO.	SHEET NO.
2018CPT.03.01.10311, ETC.	14

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW EXC. CY	INC. STONE BASE TONS	SHOULDER RECONST. SMI	1 1/2" MILLING SY	INC. MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	LEVELING COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TON	PATCHING EXISTING PAVEMENT (MILL) TON	2'-6" CONCRETE CURB & GUTTER LF	4" CONCRETE SIDEWALK SY	CONCRETE CURB RAMP EA	REMOVE AND REPLACE 4" CONCRETE SIDEWALK SY	REMOVE AND REPLACE 5" MONOLITHIC CONCRETE ISLANDS SY	REMOVE & REPLACE 2'-6" CURB & GUTTER LF					
2018CPT.03.01.10311	Duplin	1	US 117 ALT	FROM US 117 TO WAYNE COUNTY (MP .100 - MP 2.230)	1	2	2WU	NO	NO	2.13	20	64	50	1.30	25,790	50		2,182	25	133												
TOTAL FOR MAP NO. 1										2.13		64	50	1.30	25,790	50		2,182	25	133												
2018CPT.03.01.10311	Duplin	2	NC 11	FROM NC 24 (S. KENANSVILLE BYPASS) TO BEGINNING OF 2'6" C&G/PVMT. SEAM (MP 16.194 - MP 17.839)	1	2-3	2WU	NO	NO	1.645	22-34	48	10	1.00	32,858			2,810		169												
TOTAL FOR MAP NO. 2										1.645		48	10	1.00	32,858			2,810		169												
2018CPT.03.01.10311	Duplin	3	NC 11	FROM END OF C&G/PVMT SEAM TO PVMT SEAM AT NC 903 (MP 19.000 - MP 20.32)	1 & 2	2	2WU	NO	NO	1.32	22	40	30	0.80	17,250			1,459		88												
TOTAL FOR MAP NO. 3										1.32		40	30	0.80	17,250			1,459		88												
2018CPT.03.01.10311	Duplin	4	NC 24 BUS. (ROUTLEDGE RD.)	FROM NC 11 TO NC 903 (N. KENANSVILLE BYPASS) (MP 10.836 - MP 11.821)	3	2-5	2WU	NO	NO	0.985	40-60		10		28,205			2,373		142		30		2	20		30					
TOTAL FOR MAP NO. 4										0.985			10		28,205			2,373		142		30		2	20					30		
2018CPT.03.01.10311	Duplin	5	NC 24 BUS./NC 50	FROM NC 11 TO PVMT SEAM AT SR 1300 (MP 23.633 - MP 30.680)	1,2 & 3	2	2WU	NO	NO	6.955	22	208	100	4.00	111,400			9,375		563		16	15				20					
TOTAL FOR MAP NO. 5										6.955		208	100	4.00	111,400			9,375		563		16	15						20			
TOTAL FOR PROJ NO. 2018CPT.03.01.10311										13.035		360	200	7.10	215,503		50	18,199	25	1,095		46	15	2	20						50	
2018CPT.03.01.20311	Duplin	6	SR 1100 (OLD CAMP RD.)	FROM NC 41 TO SAMPSON COUNTY LINE (NO WORK DUPLIN BRIDGE # 51) (MP 0.000 - MP 7.226)	4	2	2WU	NO	NO	7.226	20		175			338		7,161		430	213											
TOTAL FOR MAP NO. 6										7.226			175			338		7,161		430	213											
2018CPT.03.01.20311	Duplin	7	SR 1827 (LIGHTWOOD BRIDGE RD./BEAR POND RD.)	FROM ONSLOW CO. LINE TO THE INTERSECTION OF NC 50 (MP 0.000 - MP 6.213)	4	2	2WU	NO	NO	6.213	20		260			126		6,159		370	183											
TOTAL FOR MAP NO. 7										6.213		260			126		6,159		370	183												
2018CPT.03.01.20311	Duplin	8	SR 1826 (BACK SWAMP RD.)	FROM THE INTERSECTION OF SR 1827 TO THE ONSLOW COUNTY LINE (NO WORK DUPLIN BRIDGE # 188) (MP 0.000 - MP 3.450)	4	2	2WU	NO	NO	3.45	19		140			331		3,252		195	97					30.00						
TOTAL FOR MAP NO. 8										3.45		140			331		3,252		195	97							30.00					
2018CPT.03.01.20311	Duplin	9	SR 1828 (CYPRESS CREEK RD.)	FROM PENDER CO. LINE TO THE INTERSECTION OF NC 50 (NO ASPHALT WORK DUPLIN BRIDGE # 187) (MP 0.000 - MP 7.756)	4	2	2WD	NO	NO	7.756	19		300			331		7,314		439	217											
TOTAL FOR MAP NO. 9										7.756		300			331		7,314		439	217												
2018CPT.03.01.20311	Duplin	10	SR 1818 (COLE SWAMP RD.)	FROM NC 50 TO THE INTERSECTION OF SR 1816 (MP 0.000 - MP 1.920)	4	2	2WU	NO	NO	1.92	19		90			111		1,810		109	54											
TOTAL FOR MAP NO. 10										1.92		90			111		1,810		109	54												
2018CPT.03.01.20311	Duplin	11	SR 1813 (ARLISS ALBERTSON RD.)	FROM NC 41 TO THE INTERSECTION OF SR1802 (MP 0.000 - MP 0.614)	4	2	2WU	NO	NO	0.614	20		40			111		605		36	18											
TOTAL FOR MAP NO. 11										0.614		40			111		605		36	18												
2018CPT.03.01.20311	Duplin	12	SR 1959 (PAUL ED DAIL RD.)	FROM THE INTERSECTION OF NC HIGHWAY 24 TO NC HIGHWAY 50 (MP 0.000 - MP 4.414)	4	2	2WU	NO	NO	4.414	20.5		220			116		4,486		269	133											
TOTAL FOR MAP NO. 12										4.414		220			116		4,486		269	133												
2018CPT.03.01.20311	Duplin	13	SR 1965 (GEORGE SUMMER RD.)	FROM THE INTERSECTION OF SR 1800 TO SR 1964 (MP 0.000 - MP 1.100)	4	2	2WU	NO	NO	1.1	20		80			244		1,090		65	32											
TOTAL FOR MAP NO. 13										1.1		80			244		1,090		65	32												
2018CPT.03.01.20311	Duplin	14	SR 1104 (BEASLEYS RD./ BEASLEYS MILL RD.)	FROM SAMPSON CO. LINE TO NC 903 (MP 0.000 - MP 5.298)	4	2	2WU	NO	NO	5.298	20		190			262		5,256		315	156											
TOTAL FOR MAP NO. 14										5.298		190			262		5,256		315	156												
2018CPT.03.01.20311	Duplin	15	SR 1335 (JOHN WARREN RD.)	FROM SAMPSON CO. LINE TO THE INTERSECTION OF SR 1301 (MP 0.000 - MP 0.767)	5	2	2WU	NO	NO	0.767	22		10			100	446	840		70	20											
TOTAL FOR MAP NO. 15										0.767		10			100	446	840		70	20												
TOTAL FOR PROJ NO. 2018CPT.03.01.20311										38.758			1,505		2,070	446	37,973		2,298	1,123												30.00
GRAND TOTAL										51.793		360	1,705	7.10	215,503	2,120	446	56,172	25	3,393	1,123	46	15	2	20			30.00	50			