PROJ. REFERENCE NO.	SHEET NO.
U-5935	X-1D

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT.

CROSS-SECTION SUMMARY

Station	Uncl. Exc.	Embt
EY20	(cu. yd.)	(cu. yd.)
46+00.00	3	14
46+50.00	3	9
47+00.00	2	9
47+50.00	1	7
49+00.00	14	7
49+50.00	10	0
50+00.00	10	0
50+50.00	6	1
51+00.00	3	1
51+50.00	5	1
52+00.00	7	0
52+50.00	8	0
53+00.00	9	0
53+50.00	11	0
54+00.00	12	0
54+50.00	12	1
55+00.00	14	1
55+50.00	15	1
56+00.00	17	1
56+50.00	22	1