

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.04.10.10511.1	4	

## SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	1.5" MILLING SY	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, S9.5C TONS	ASPHALT BINDER FOR PLANT MIX TONS	ADJ. OF MANHOLES EA	RETROFIT EXSITING CURB RAMP (STD. 848.06) EA	ADJ. OF METER OR VALVE BOX EA	PORTABLE LIGHTING LS	INDUCTIVE LOOP LF
2016CPT.04.10.10511.1	Johnston	1	US70 BUS. WEST BOUND	FROM US 70 BYPASS BRIDGE TO WAKE COUNTY LINE	1	2	MD	YES	NO	7.88	24-36	196,594		16,562	977	3			*	2,200
<b>TOTAL FOR MAP NO. 1</b>										<b>7.88</b>		<b>196,594</b>		<b>16,562</b>	<b>977</b>	<b>3</b>				<b>2,200</b>
2016CPT.04.10.10511.1	Johnston	2	US70 BUS. EAST BOUND	WAKE COUNTY LINE TO BRIDGE AT US70 BYPASS	1	2	MD	YES	NO	7.83	24-36	212,356		18,120	1,069	1		2	*	1,800
<b>TOTAL FOR MAP NO. 2</b>										<b>7.83</b>		<b>212,356</b>		<b>18,120</b>	<b>1,069</b>	<b>1</b>		<b>2</b>		<b>1,800</b>
2016CPT.04.10.10511.1	Johnston	3	US70 BUS. RAMP WEST BOUND	ENTRANCE RAMP FROM US 70 TO US 70 BUS.	2	2	2WU	YES	NO	0.7	16	6,570	556		33				*	
<b>TOTAL FOR MAP NO. 3</b>										<b>0.7</b>		<b>6,570</b>	<b>556</b>		<b>33</b>					
2016CPT.04.10.10511.1	Johnston	4	BARBOUR /HAMBY ST.	FROM US HWY 70 BUS. TO NC HWY 42 WEST	3	2	2WU	NO	NO	0.21	24-36	3,942	332		20	1	2			
<b>TOTAL FOR MAP NO. 4</b>										<b>0.21</b>		<b>3,942</b>	<b>332</b>		<b>20</b>	<b>1</b>	<b>2</b>			
<b>TOTAL FOR PROJ NO. 2016CPT.04.10.10511.1</b>										<b>16.62</b>		<b>419,462</b>	<b>888</b>	<b>34,682</b>	<b>2,099</b>	<b>5</b>	<b>2</b>	<b>2</b>	<b>1</b>	<b>4,000</b>
<b>GRAND TOTAL</b>										<b>16.62</b>		<b>419,462</b>	<b>888</b>	<b>34,682</b>	<b>2,099</b>	<b>5</b>	<b>2</b>	<b>2</b>	<b>1</b>	<b>4,000</b>