

PROJECT NO.	SHEET NO.	TOTAL NO.
2016CPT.04.10.10511.1	5	

**THERMOPLASTIC AND PAINT QUANTITIES**

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	LENGTH	WIDTH	4688000000-E		469000000	4695000000-E		4700000000-E	4702000000-E	4705000000-E	4710000000-E	4721000000-E	4725000000-E								
										6" X 90 M YELLOW THERMO	6" X 90 M WHITE THERMO	6" X 120 M WHITE THERMO	8" X 90 M WHITE THERMO	8" X 90 M YELLOW THERMO	12" X 90 M WHITE THERMO	12" X 120 M WHITE THERMO	16" X 120 M WHITE THERMO	24" X 120 M WHITE THERMO	THERMO RXR 120 M	THERMO MSG ONLY 120 M EA	THERMO STR ARROW 90 M EA	THERMO STR & RT ARROW 90 M EA	THERMO STR & LT ARROW 90 M EA	THERMO RT ARROW 90 M EA	THERMO MERGE ARROW 90 M EA	THERMO LT ARROW 90 M EA		
2016CPT.04.10.10511.1	Johnston	1	US70 BUS. WEST BOUND	FROM US 70 BYPASS BRIDGE TO WAKE COUNTY LINE	1	2	MD	7.88	24-36	41,606	41,606	10,741	2,712	2,750	2,085	1,460	100	783	4	32	60	2	72	58	3			
		2	US70 BUS. EAST BOUND	WAKE COUNTY LINE TO BRIDGE AT US70 BYPASS	1	2	MD	7.83	24-36	41,184	41,184	12,490	2,560	40	2,085	2565			576		48	60	2		55		66	
		3	US70 BUS. RAMP WEST BOUND	ENTRANCE RAMP FROM US 70 TO US 70 BUS.	2	2	2WU	0.7	16	3,700	3,700					395												
		4	BARBOUR /HAMBY ST.	FROM US HWY 70 BUS. TO NC HWY 42 WEST	3	2	2WU	0.21	24-36																			
<b>GRAND TOTAL FOR PROJ NO. 2016CPT.04.10.10511.1</b>																												
										86,490	86,490	23,231	5,272	2,790	4,565	4,025	100	1,359	4	80	120	4	72	113	3	66		
										172,980			8,062						84		378							

**THERMOPLASTIC AND PAINT QUANTITIES**

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP	LANES	LANE TYPE	LENGTH	WIDTH	4810000000	4815000000-E		4820000000-E		4825000000-E	4830000000-E	4835000000-E	4840000000-N		4845000000-N							050000000	4935000000-N	4945000000-N
										4" WHITE PAINT	6" WHITE PAINT	6" YELLOW PAINT	8" WHITE PAINT	8" YELLOW PAINT	12" WHITE PAINT	16" WHITE PAINT	24" WHITE PAINT	PAINT MSG RXR	PAINT MSG ONLY	PAINT STR ARROW	PAINT STR & RT ARROW	PAINT STR & LT ARROW	PAINT RT ARROW	PAINT MERGE ARROW	PAINT LT ARROW	SNOW PLOWABLE	FLEXIBLE DELINEATORS (CRYSTAL)	FLEXIBLE DELINEATORS	
2016CPT.04.10.10511.1	Johnston	1	US70 BUS. WEST BOUND	FROM US 70 BYPASS BRIDGE TO WAKE COUNTY LINE	1	2	MD	7.88	24-36		52,347	41,606	2,712	275	1,500	100	783	4	32	60	2	72	58	3		1,110		48	
		2	US70 BUS. EAST BOUND	WAKE COUNTY LINE TO BRIDGE AT US70 BYPASS	1	2	MD	7.83	24-36		53,674	41,184	2,560	40	1,500			576		48	60	2		55		66	1,280		
		3	US70 BUS. RAMP WEST BOUND	ENTRANCE RAMP FROM US 70 TO US 70 BUS.	2	2	2WU	0.7	16		3,700	3,700																	
		4	BARBOUR /HAMBY ST.	FROM US HWY 70 BUS. TO NC HWY 42 WEST	3	2	2WU	0.21	24-36	2,400																		8	
<b>GRAND TOTAL FOR PROJ NO. 2016CPT.04.10.10511.1</b>																													
										2,400	109,721	86,490	5,272	315	3,000	100	1,359	4	80	120	4	72	113	3	66	2,390	8	48	
											196,211		5,587						84		378								