

COMPUTED BY: SCS DATE: 04-15-2017
 CHECKED BY: GAM DATE: 04-19-2017

PROJECT NO.
 U-4751

SHEET NO.
 3B-4

PAVEMENT REMOVAL SUMMARY

IN SQUARE YARDS

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	ASPHALT REMOVAL	ASPHALT BREAKUP
L	31+03	31+51	LT	89	
L	31+51	35+02	LT	405	
L	34+32	37+37	RT	446	
Y1	19+47	25+25	CL	1,756	
Y1	32+09	35+84	CL	1,171	
Y1	40+59	57+32	CL	5,017	
Y1	45+15	49+65	RT	1,653	
Y1	65+26	72+74	CL	2,245	
Y1RPB	26+89	30+97	CL	1,454	
SR1	12+50	13+73	CL	307	
Y4	16+34	16+76	LT	12	
Y4	17+00	18+40	CL	308	
Y5	15+80	16+15	CL	76	
Y8	31+20	73+28	LT	4,487	
Y8	49+11	69+88	RT	2,103	
Y8	85+80	101+85	LT	1,645	
Y8	88+90	94+75	RT	584	
Y8	97+35	102+30	RT	481	
Y8	109+35	121+98	RT	1,261	
Y21	11+40	End of Culdesac	CL	433	
Y22	10+56	11+15	CL	99	
Y24	12+07	11+33	CL	109	
L	29+00	36+40	RT		2,585
L	29+50	34+67	LT		1,281
L	92+24	100+01	CL		2,410
L	111+98	112+40	CL		167
L	127+95	128+33	CL		278
Y3	13+00	14+12	CL		336
Y3	15+25	15+50	CL		62
Y4	15+83	17+00	LT		236
Y5	13+75	14+39	CL		194
Y5	15+53	15+80	CL		80
Y12	15+02	15+39	CL		184
Y12 (TEMPORARY)	11+03	11+43	CL		249
		TOTAL:		26,389	7,791
		SAY:		26,400	7,800

SHOULDER BERM GUTTER SUMMARY

LINE	Station	Station	LOCATION LT/RT/CL	LENGTH
L	54+17.84	62+61.96	LT	844.12
L	56+92.62	62+01.25	RT	508.63
L	63+50.73	68+70.62	RT	519.89
L	64+11.44	68+32.58	LT	421.14
L	223+35.21	224+66.71	LT	131.50
Y8RPC	24+00.00	33+00.00	RT	900.00
Y8RPD	11+00.00	22+08.89	RT	1,108.89
Y8RPDB	36+50.55	36+82.81	LT	32.26
		TOTAL:		4,466.43
		SAY:		4,500

WOVEN WIRE FENCE, 47" FABRIC

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	A	B	C	D	E	F
				FABRIC L.F.	END BRACE	CORNER BRACE	LINE BRACE	4" POSTS	5" POSTS
L	138+20.00	143+80.00	RT	610.37	2	4	0	35	16
L	145+35.00	150+34.35	RT	608.72	2	5	0	33	19
L	150+84.37	175+50.40	RT	2,558.24	2	6	6	161	40
L	138+38.64	202+94.01	LT	6,590.93	2	13	17	419	94
L	176+55.00	200+00.00	RT	2,395.00	1	4	6	154	32
L	-L- END	235+55.00		1,218.43	0	0	3	82	9
Y8	63+00.00	64+03.66	RT	105.48	1			6	2
Y8	40+09.39	40+62.49	LT	69.67				0	9
Y8RPA	15+00.00	33+72.99	LT	1,754.54	1	2	4	114	20
Y8RPB	27+60.00	33+03.84	RT	532.20		1	2	33	9
Y8RPC	10+00.00	34+66.23	LT	2,441.94		2	7	160	27
Y8RPCA	52+33.79	68+92.88	LT	1,638.24		0	5	109	15
Y8RPD	10+00.00	27+93.10	RT	1,702.36	1	1	5	111	20
Y8RPDB	10+04.74	22+93.35	RT	1,264.86		2	3	82	15
Y8RPDB	55+79.90	68+50.00	RT	1,229.85	1	1	3	80	14
		TOTAL:		24,720.83				1,579	341
		SAY:		24,730				1,580	341

CHAIN LINK FENCE, 48" FABRIC

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	A	B	C	D	E	F
				FABRIC L.F.	END BRACE	CORNER BRACE	LINE BRACE	4" POSTS	5" POSTS
Y1RPD	11+57.92	52+50.00	RT	2,857.11	2	5	6	240	13
L	27+00.00	30+00.00	LT	323.45	2	3	0	27	5
Y1	37+15.00	62+85.83	LT	3,058.95	2	6	7	257	15
Y1	51+96.54	62+23.87	RT	2,367.33	2	3	6	198	11
L	63+88.83	84+10.42	LT	2,148.82	2	4	5	180	11
Y2	15+22.01	16+05.22	LT	75.74	2			6	2
L	62+89.54	74+00.00	RT	1,193.93	1	4	3	100	8
L	90+00.00	92+45.00	RT	241.72	2	1	0	20	3
L	93+15.20	102+19.72	LT	911.81	2	1	2	76	5
L / Y12	97+81.15	11+54.84	RT	251.09	2	2		21	4
Y12	10+86.30	11+26.91	LT	38.33	2			3	2
L / Y4	107+64.53	18+21.29	RT	382.21	2	3	0	32	5
Y4 / L	17+16.97	116+68.00	LT/RT	546.86	2	2	1	46	5
L / Y5	111+27.00	16+30.00	RT	1,122.34	2	3	2	94	7
Y5 / L	13+66.58	138+38.64	LT	1,047.75	2	2	1	87	5
Y5 / L	16+72.26	138+20.00	LT/RT	996.85	2		3	83	5
		TOTAL:		17,564.29				1471	106
		SAY:		17,565				1472	106

CHAIN LINK FENCE, 72" FABRIC

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	A	B	C	D	E	F
				FABRIC L.F.	END BRACE	CORNER BRACE	LINE BRACE	4" POSTS	5" POSTS
L	33+27.86	38+50.51	RT	1045.73	2	3	1	87.48	6
L	93+15.20	102+20.02	LT	911.81	2	1	2	76.15	5
L	128+36.55	134+59.03	LT	621.50	2	1	1	51.79	4
Y1RPD	20+97.79	34+90.71	LT	2056.65	1	7	2	172.72	10
		TOTAL:		4,635.69				388.14	25
		SAY:		4,636				389	25