STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

SIGNING PLAN ALEXANDER COUNTY

LOCATION: BRIDGE No. 139 OVER GLADE CREEK ON SR 1609 (COUNTY HOME ROAD)

PROJECT REFERENCE NO.	SHEET NO.	
B-5391	SIGN-1	
APPROVED: Revue B. Roadu B3C6C6F7CF4640D		
DATE: 8/29/2017		
SEAL		
SEAL O24921 OFESSION SEAL O24921	THE WILLIAM STATES OF THE STAT	

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SUMMARY OF QUANTITIES

ITEM NO.		ITEM DESCRIPTION	OHANTITY	LINITT
DESC. NO.	SECT. NO.	TILM DESCRIPTION	QUANTITY	UNIT
4072000000 4102000000 4155000000	903 904 907	SUPPORTS, 3 LB STEEL U-CHANNEL SIGN ERECTION, TYPE E DISPOSAL OF SIGN SYSTEM, U-CHANNEL	152 14 8	L.F. EA. EA.

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" -PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

TITLE STD. NO.

904.10

ORIENTATION OF GROUND MOUNTED SIGNS

MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS 904.50

GENERAL NOTES

- . SIGNS FURNISHED BY STATE
- . CONFIRM IN WRITING AT LEAST 4 MONTHS IN ADVANCE, THE ACTUAL DATE THE DEPARTMENT FURNISHED SIGNS WILL BE REQUIRED.
- WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- . ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- . THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
- . SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

INDEX

SHEET NO.

DESCRIPTION

SIGN-1

TITLE SHEET

SIGN-2

SIGN DETAIL SHEET AND "E" SIGNS

PLAN PREPARED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

KELVIN JORDAN

SIGNING & DELINEATION REGIONAL ENGINEER

DERRICK BEARD

SIGNING & DELINEATION PROJECT DESIGN ENGINEER

