

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

PROJ. REFERENCE NO.	SHEET NO.
B-5239	X-1A

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

CROSS-SECTION SUMMARY

PHASE I CONSTRUCTION				Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt
Station	Uncl. Exc.	Embt		Y1Det	(cu. yd.)	(cu. yd.)	L	(cu. yd.)	(cu. yd.)	L	(cu. yd.)	(cu. yd.)	TEMP DRV	(cu. yd.)	(cu. yd.)
L	(cu. yd.)	(cu. yd.)													
				11+20.00	0	0	17+77.00	0	0	10+04.15	0	0	20+40.65	0	0
10+04.15	0			11+50.00	11	0	18+00.00	0	216	10+50.00	0	0	20+50.00	14	1
10+50.00	5	0		12+00.00	42	0	18+27.00	0	177	11+00.00	38	0	20+61.61	13	2
11+00.00	29	0		12+50.00	53	7	18+50.00	0	99	11+50.00	55	6	21+00.00	28	5
11+50.00	78	0		12+68.06	22	5	18+68.38	0	90	12+00.00	31	72			
12+00.00	176	0								12+35.44	17	140			
12+35.44	232	0		Station	Uncl. Exc.	Embt	Station	Uncl. Exc.	Embt	12+50.00	7	75			
12+50.00	131	0		Y2Det	(cu. yd.)	(cu. yd.)	L	(cu. yd.)	(cu. yd.)	12+74.46	17	129			
12+74.46	257	0								13+00.00	22	150			
13+00.00	279	0		10+11.25	0	0	19+41.00	0	0	13+50.00	69	245			
13+50.00	415	0		10+30.00	19	1	19+50.00	0	35	14+00.00	90	113			
14+00.00	174	7		10+50.00	14	1	19+63.00	0	50	14+22.09	44	17			
14+22.09	16	30		10+75.00	8	0	20+00.00	0	123	14+50.00	110	14			
14+50.00	15	134		10+88.00	2	0	20+37.85	0	93	14+67.00	112	5			
14+67.00	6	137					20+50.00	0	26	14+92.00	248	3			
14+92.00	3	263		Station	Uncl. Exc.	Embt	20+61.61	0	22	15+00.00	112	0			
15+00.00	0	109		Temp Drv	(cu. yd.)	(cu. yd.)	21+00.00	0	36	15+01.98	31	0			
15+01.98	0	30		9+76.32	0	0	21+50.00	87	8						
				10+30.00	5	19	22+00.00	210	9	Station	Uncl. Exc.	Embt			
				10+40.00	18	2	22+50.00	220	8	L	(cu. yd.)	(cu. yd.)			
				10+50.00	50	1	23+00.00	97	2						
17+66.99	0	0	0	10+60.00	74	0				17+66.99					
17+77.00	1	0	236	10+70.00	89	0	Station	Uncl. Exc.	Embt	17+77.00	235	2			
18+00.00	2	74	591	10+80.65	101	0	Y1	(cu. yd.)	(cu. yd.)	18+00.00	539	2			
18+27.00	0	373	780				10+85.00	0	0	18+27.00	626	0			
18+50.00	0	341	674	Station	Uncl. Exc.	Embt	11+00.00	16	0	18+50.00	512	0			
18+73.00	0	163	554	Temp Drv	(cu. yd.)	(cu. yd.)	11+25.00	46	0	18+73.00	469	0			
18+90.38	0	0	339	20+40.65	0	0	11+50.00	24	2	18+90.38	334	0			
				20+50.00	41	0	11+75.00	4	11	Station	Uncl. Exc.	Embt			
				20+61.61	65	0	12+22.00	0	32	L	(cu. yd.)	(cu. yd.)			
				21+00.00	301	0									
19+76.60	0	0	0	PHASE II CONSTRUCTION			Station	Uncl. Exc.	Embt	19+76.60	0	0			
20+00.00	0	78	13	Station	Uncl. Exc.	Embt	10+12.27	0	0	20+00.00	17	0			
20+37.85	3	114	11	L	(cu. yd.)	(cu. yd.)	10+30.00	2	0	20+37.85	21	0			
20+50.00	2	33	0				10+50.00	4	0	20+50.00	4	0			
20+61.61	2		0	10+50.00	0	0	10+75.00	9	0	22+00.00	47	58			
21+00.00	5		5	11+00.00	136	1	11+00.00	5	0	22+50.00	17	45			
22+00.00	71		13	11+50.00	208	6				23+00.00	19	34			
22+50.00	72		1	12+00.00	133	28	Station	Uncl. Exc.	Embt	23+50.00	13	21			
23+00.00	48		8	12+35.44	72	53	Y3	(cu. yd.)	(cu. yd.)	24+00.00	9	21			
23+50.00	22		10	12+50.00	23	35				24+80.07	9	13			
24+00.00	22		5	12+74.46	25	75	10+15.00	0	0						
24+50.00	13		3	13+00.00	8	83	10+21.99	1	0						
24+80.07	6		1	13+50.00	0	166	10+41.78	3	37						
				14+00.00	0	269	10+66.75	0	217						
				14+22.08	0	162	10+85.22	0	153						
				14+50.00	0	224									
				14+67.00	0	150	PHASE III DETOUR REMOVAL								
				14+92.00	0	229									

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".