

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANE S	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	01060000	03180000	03200000	04483	099500000	122000	124500000	1297000000-E					130800	1330000	1489000	14980000	15190000	15200000	15250000	152510000	15750000	18800000	18800000					
												BORROW EXCAVATION	FOUND. COND. MAT., MINOR STRS	FOUND. COND. GEOTEX TILE	18" RCP, CLASS IV	PIPE REMOVAL (CONTINGENCY)	INC. STONE BASE	SHOULDER RECONST.	1.5" MILLING	1" MILLING	1.25" MILLING	5.5" MILLING	2.5" MILLING	0" - 4" MILLING	INC. MILLING	BASE COURSE, B25.0B	INTER-MEDIATE COURSE, I19.0B	SURFACE COURSE, S9.5B	LEVELING COURSE, S9.5B	SURFACE COURSE, SF9.5A	LEVELING COURSE, SF9.5A	ASPHALT BINDER FOR PLANT MIX	PATCHING EXI. PAV. (MILL)	PATCHING EXI. PAV. (FULL DEPTH)					
												MI	FT	CY	TON	SY	LF	LF	TON	SMI	SY	SY	SY	SY	SY	SY	SY	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON	TON
2018CPT.03.03.10101	Brunswick	1	NC 130 (WHITEVILLE RD.)	FROM US 17 BUS. TO SR 1335 + 1.216 MILES (MP 10.206 - MP 16.350) [NO WORK BRIDGE # 221- MP 11.124 - MP 11.172]	1 & 2	2 - 3	2WU	NO	NO	6.144	28 - 40	188					150	4.10	112,598																				
		2	NC 179 (OLD GEORGETOWN RD.)	FROM 179 BUS. TO NC 904 (MP 2.185 - MP 5.910)	3	2 - 3	2WU	NO	NO	3.725	28 - 40	355					75	7.45																					
		3	NC 904 (LONGWOOD RD.)	FROM SR 1321 TO SR 1304 (MP 5.608 - MP 8.185)	1 & 3	2	2WU	NO	NO	2.577	28	235					180	5.15	3,285																				
		4	179 BUSINESS (SUNSET BLVD.)	FROM TRAFFIC CIRCLE AT SHORELINE DRIVE TO PAVEMENT SEAM .045 WEST OF NC 904 (MP 3.635 - MP 5.305)	1 & 4	2 - 4	2WU	NO	NO	1.67	34 - 46	130					20	2.78	4,440	36,338																			
TOTAL FOR PROJ NO. 2018CPT.03.03.10101										14.116		908				425	19.48	120,323	36,338																				
2018CPT.03.03.20101	Brunswick	5	SR 1319 (UNION SCHOOL RD)	FROM SR 1316 TO US 17 (MP 0.00 - MP 0.585)	5	2	2WU	NO	NO	0.585	20					15																							
		6	SR 1504 (CLEMMONS RD)	FROM SR 1501 TO SR 1505 (MP 0.000 - MP 1.280)	6	2	2WU	NO	NO	1.28	20					20		15,019																					
		7	SR 1333 (PROJECT RD)	FROM SR 1326 TO END PVMT (MP 3.970 - MP 6.820)	7	2	2WU	NO	NO	2.85	20					100																							
		8	SR 1327 (NEW BRITTON LOOP RD)	FROM SR 1333 TO SR 1326 (MP 0.000 - MP 1.804)	6	2	2WU	NO	NO	1.804	18					50		19,050																					
		9	SR 1337 (MARLOW RD)	FROM SR 1336 TO SR 1333 (MP 0.000 - MP 1.382)	6	2	2WU	NO	NO	1.382	18					50		14,594																					
		10	SR 1308 (ETHERIDGE RD)	FROM SR 1300 TO NC 904 (MP 0.000 - MP 1.993)	6	2	2WU	NO	NO	1.993	18					60		21,046																					
		11	SR 1335 (MYRTLEHEAD RD)	FROM SR 1333 TO SR 1336 (MP 0.000 - MP 5.299)	6 & 9	2	2WU	NO	NO	5.299	18					530				31,365																			
		12	SR 1356 (MARLOWTOWN RD)	FROM SR 1302 TO SR EOM (MP 0.000 - MP 0.840)	6	2	2WU	NO	NO	0.84	20					30																							
		13	SR 1301 (MCLAMB RD)	FROM SR 1300 TO SC LINE (MP 0.000 - MP 0.782)	6	2	2WU	NO	NO	0.782	18					15																							
		14	SR 1316 (OLD SHALLOTTE RD)	FROM NC 904 TO US 17 (MP 0.000 - MP 5.202)	6	2	2WU	NO	NO	5.202	20					120																							
		15	SR 1155 (GOOSE CREEK RD)	FROM NC 179 TO SR 1143 (MP 0.723 - MP 2.507)	6	2	2WU	NO	NO	1.784	20					30																							
		16	SR 1304 (PEA LANDING RD)	FROM US 17 TO NC 904 (MP 0.000 - MP 3.271)	8	2	2WU	NO	NO	3.271	22					70																							
		17	SR 1305 (NO. 5 SCHOOL RD)	FROM SR 1300 TO SR 1304 (MP 0.000 - MP 3.123)	6, 9 & 10	2	2WU	NO	NO	3.123	20					80					7,275																		
		18	SR 1165 (THOMASBORO RD)	FROM US 17 TO SR 1164 (MP 0.000 - MP 2.407)	5	2	2WU	NO	NO	2.407	22					50		31,066																					
		19	SR 1720 (WASHINGTON RD)	FROM US 17 BUS. TO EOM (MP 0.000 - MP 0.157)	6	2	2WU	NO	NO	0.157	18					5		2,215																					
		20	SR 1312 (MT. ZION CHURCH RD)	FROM NC 904 TO EOM (MP 0.000 - MP 0.296)	6	2	2WU	NO	NO	0.296	18					15																							
		21	SR 1315 (RUSSTOWN RD)	FROM SR 1313 TO NC 904 (MP 1.75 - MP 4.20)	11 & 12	2	2WU	YES	NO	2.45	20			665		75	4.90							670		1,145	3,395	2,440								360			
		TOTAL FOR PROJ NO. 2018CPT.03.03.20101										35.505		665			1,315	4.90	102,990		38,640	5,015		670	800	4,015	3,395	5,425					25,180	125	2,358	2,525			
		45333	Brunswick	.3.25	SR 1115 (STONE CHIMNEY RD./OLD FERRY CONNECTION)	FROM PAVEMENT SEAM AT NC 211 TO INTRACOASTAL WATERWAY (MP 0.45 - MP 7.91)	3, 13 - 16	2	2WU	NO	NO	7.46	18 - 26	690	22	68	104	48	625	14.19	3,680	825																	
		TOTAL FOR PROJ NO. 45333.3.25 W-5203Y										7.46		690	22	68	104	48	625	14.19	3,680	825														873	550	10	
		GRAND TOTAL										57.081		2,263	22	68	104	48	2,365	38.57	226,993	37,163	38,640	5,015	12,650	670	2,520	11,005	6,460	37,725	120	25,180	125	4,758	3,905	30			