

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

Kimley»Horn <small>©2017</small>	
<small>421 FAYETTEVILLE STREET, SUITE 600 RALEIGH, NC 27601</small>	
<small>RIGHT-OF-WAY REV.</small>	<small>CONST. REV.</small>

<small>PROJECT REFERENCE NO.</small> B-4637	<small>SHEET NO.</small> EC-3
<small>ROADWAY DESIGN ENGINEER</small>	<small>HYDRAULICS ENGINEER</small>

SOIL STABILIZATION TIMEFRAMES

<i>SITE DESCRIPTION</i>	<i>STABILIZATION TIME</i>	<i>TIMEFRAME EXCEPTIONS</i>
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

K:\RAL_Roadway\01036316 - B-4637\Erosion Control\B4637_ero_psh-2-3.dgn

3/31/2017