DocuSign Envelope ID: 6C48D7D9-863D-4910-A2E8-1A844F8B8ACD

TIP NO.	SHEET NO.
R-5749	PMP-1A

APPROVED: DocuSigned by: Joseph Kopaskie 9CDEEAEF80A54FA...

DATE: 12/8/2017

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 029669 ENGINEER JOSEPH B. KOPASKIE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION
	THERMOPLASTIC (24″, 120 MILS)
T2	WHITE STOPBAR
	THERMOPLASTIC (6″, 90 MILS)
T6	WHITE EDGELINE
T7	YELLOW EDGELINE
	THERMOPLASTIC (4″, 120 MILS)
T8	2 FT. - 6 FT./SP WHITE MINISKIP
TD	3 FT. - 9 FT./SP WHITE MINISKIP
TE	WHITE SOLID LANE LINE
TI	YELLOW DOUBLE CENTER
	THERMOPLASTIC (6″, 120 MILS)
T11	2 FT. - 6 FT./SP WHITE MINISKIP
T12	2 FT. - 6 FT./SP YELLOW MINISKIP
TJ	10 FT. WHITE SKIP
TK	3 FT. - 9 FT./SP WHITE MINISKIP
TL	WHITE SOLID LANE LINE
	THERMOPLASTIC (12″, 120 MILS)
TT	WHITE SOLID LANE LINE
	THERMOPLASTIC (4″, 90 MILS)
TA	WHITE EDGELINE
TB	YELLOW EDGELINE
	THERMOPLASTIC (8″, 90 MILS)
TN	WHITE GORELINE
TP	YELLOW DIAGONAL
	THERMOPLASTIC (12″, 90 MILS)
TS	WHITE GORELINE
TU	WHITE DIAGONAL
	THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS)
UA	LEFT TURN ARROW
UB	RIGHT TURN ARROW
UC	STRAIGHT ARROW
UD	COMBO LEFT/STRAIGHT ARROW
UN	24″ YIELD LINE TRIANGLE
UP	MERGE ARROW
UQ	RAMP ARROW
UT	U-TURN ARROW
	PERMANENT RAISED PAVEMENT MARKERS
MA	YELLOW & YELLOW
MB	CRYSTAL & RED

LEGEND

GENERAL

DIRECTION OF TRAFFIC FLOW

NORTH ARROW

PROPOSED PVMT. --------- EXIST. PVMT.

PAVEMENT MARKINGS

PAVEMENT MARKING SYMBOLS

SEPI ENGINEERING & CONSTRUCTION
1025 Wade Avenue
Raleigh, NC 27605
Tel:919-789-9977
Fax:919-789-9591
License: C-2197

FINAL PAVEMENT MARKING SCHEDULE & LEGEND

12/8/2017
R:\Pavement Markings\PMP-1A.dgn
USER: kopaskie