

GENERAL NOTES

CHANGES MAY BE REQUIRED WHEN PHYSICAL DIMENSIONS IN THE DETAIL DRAWINGS, STANDARD DETAILS, AND ROADWAY DETAILS ARE NOT ATTAINABLE TO MEET FIELD CONDITIONS OR RESULT IN DUPLICATE OR UNDESIRED OVERLAPPING OF DEVICES. MODIFICATION MAY INCLUDE: MOVING, SUPPLEMENTING, COVERING, OR REMOVAL OF DEVICES AS DIRECTED BY THE ENGINEER.

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR DIRECTED BY THE ENGINEER.

TRAFFIC PATTERN ALTERATIONS

- A) NOTIFY THE ENGINEER THIRTY (30) CALENDAR DAYS PRIOR TO ANY TRAFFIC PATTERN ALTERATION.

SIGNING

- B) PROVIDE SIGNING AND DEVICES REQUIRED TO CLOSE THE ROAD ACCORDING TO THE ROADWAY STANDARD DRAWINGS AND TRAFFIC CONTROL PLANS.

PROVIDE SIGNING REQUIRED FOR THE OFF-SITE DETOUR ROUTE AS SHOWN IN THE TRAFFIC CONTROL PLANS.

- C) COVER OR REMOVE ALL SIGNS AND DEVICES REQUIRED TO CLOSE THE ROAD WHEN ROAD CLOSURE IS NOT IN OPERATION.

COVER OR REMOVE ALL SIGNS REQUIRED FOR THE OFF-SITE DETOUR WHEN THE DETOUR IS NOT IN OPERATION.

- D) ENSURE ALL NECESSARY SIGNING IS IN PLACE PRIOR TO ALTERING ANY TRAFFIC PATTERN.

TRAFFIC CONTROL DEVICES

- E) PLACE TYPE III BARRICADES, WITH "ROAD CLOSED" SIGN R11-2 ATTACHED, OF SUFFICIENT LENGTH TO CLOSE ENTIRE ROADWAY.

PHASING

STEP 1: INSTALL CMS BOARDS TO WARN MOTORISTS OF THE UPCOMING ROAD CLOSURE 7-14 DAYS PRIOR TO ROAD BEING CLOSED, AS DIRECTED BY THE ENGINEER.

STEP 2: USING ROADWAY STANDARD DRAWING NO. 1101.03, SHEETS 1 OF 9, AND SHEET TMP-4, INSTALL ROAD CLOSURE AND DETOUR SIGNS FOR ENON RD AND LUCY AVERETTE RD. COVER SIGNS UNTIL DETOUR IS READY FOR OPERATION.

STEP 3: WHEN DETOUR IS READY UNCOVER SIGNS AND CLOSE ENON RD. REMOVE CMS BOARDS ONCE ROAD IS CLOSED. CONSTRUCT STRUCTURE, ROADWAY IMPROVEMENTS AND FINAL PAVEMENT MARKINGS ALONG ENON RD.


STEP 4: REMOVE ROAD CLOSURE DEVICES AND SIGNS ONCE CONSTRUCTION IS COMPLETE.

LOCAL NOTES

IN ORDER TO ALLOW EMERGENCY MANAGEMENT SERVICES (EMS) TIME TO PREPARE FOR ROAD CLOSURE, NCDOT WILL CONTACT THE DIRECTOR OF THE GRANVILLE COUNTY EMS AT (919) 603-1310 ONE MONTH PRIOR TO ROAD CLOSURE. IN ADDITION, THE BERA AND PROVIDENCE FIRE DEPARTMENTS WILL BE NOTIFIED ONE MONTH PRIOR TO ROAD CLOSURE.

IN ORDER TO ALLOW GRANVILLE COUNTY SCHOOLS TIME TO PREPARE FOR ROAD CLOSURE, NCDOT WILL CONTACT THE GRANVILLE COUNTY SCHOOLS TRANSPORTATION CREW LEAD AT (919) 693-6412 ONE MONTH PRIOR TO ROAD CLOSURE.

APPROVED:  DATE: 2/13/18



**TRANSPORTATION
MANAGEMENT PLAN
GENERAL NOTES AND
WRITTEN PHASING**