

PROJECT REFERENCE NO.	SHEET NO.
I-5853	7

SUMMARY OF DRAINAGE REPAIR

MAP #	STATION	LOCATION	REMOVE & REPLACE CONCRETE APRON & BACKFILL	4" CONCRETE PAVED DITCH	DRAINAGE STRUCTURE REPAIR		RIP RAP, CLASS 'B' AT PIPE OUTLETS	GEOTEXTILE FOR DRAINAGE
		LT or RT			GROUT UNDER FRAME WITH GRATE & HOOD & BACKFILL DRAINAGE	GROUT AROUND EXISTING SHOULDER DRAIN PIPE & CUT PIPE FLUSH WITH WALL		
			EA	SY	EA	EA	TON	SY
1	15+75	RT					5	14
1	45+50	RT			1			
1	53+60	RT			1			
1	55+25	RT			1			
1	66+30	RT			1			
1	67+85	RT			1			
1	77+20	RT	1					
1	78+30	RT	1			1		
1	90+00	RT	1					
TOTAL FOR MAP 1			3	0	6		5	14
2	12+35	RT	1					
TOTAL FOR MAP 2			1	0	0		0	0
5	22+75	RT			1			
TOTAL FOR MAP 5			0	0	1		0	0
7	18+20	MEDIAN	1					
7	37+32	RT				1		
7	43+10	RT	1					
7	65+27	RT	1					
7	70+75	RT	1					
7	104+70	RT	1	8				
TOTAL FOR MAP 7			5	8	1		0	0
GRAND TOTAL			9	8	8		5	14