PROJECT NO.	SHEET NO.	TOTAL NO.
TP.08.13.10621, 2018CPT.08.13.		
2018CTP.08.13.20621, ETC.	10	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW EXCAVATION	1243000000-E SHOULDER CONSTRUCTION	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1.5" MILLING	1330000000-E INCIDENTAL MILLING	1491000000-E BASE COURSE, B25.0C	1519000000-E SURFACE COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	1775500000-E ASPHALT SURFACE TREATMENT, MATCOAT, #67 STONE	1814500000-E ASPHALT SURFACE TREATMENT, SINGLE SEAL	1838000000-E EMULSION FOR ASPHALT SURFACE TREATMENT	1838500000-N VACUUM TRUCK	1891000000-E GENERIC PAVING ITEM - LATEX MODIFIED MICROSURFACING, TYPE II	2830000000-N ADJUST MANHOLES	2845000000-N ADJUST METER OR VALVE BOX	6000000000-E TEMPORARY SILT FENCE	6071010000-E WATTLE	6084000000-E SEED & MULCHING	7444000000-E INDUCTIVE LOOP SAWCUT
										MI	FT	CY	SMI	SMI	TON	SY	SY	TONS	TONS	TONS	TONS	TONS	SY	SY	GAL	WK	SY	EA	EA	LF	LF	AC	LF
2018CTP.08.13.10621	Montgomery	1	NC 109 BUS (ELDORADO ST)	FROM NC 109 BR (SMITHERMAN ST) TO NC 109 BYP (BILHEN ST)	1	2		NO	NO	0.523	22						515					100					14,115	12	5				820
TOTAL FOR MAP NO. 1										**0.523**							**515**					**100**					**14,115**	**12**	**5**				**820**
2018CTP.08.13.10621	Montgomery	2	NC 109	FROM NC 109 BYP (N BILHEN ST) TO PVMT JT 0.047 MI WEST OF SR 1138 (SHILOH RD)	2	2		NO	NO	0.682	22						120					70					8,820	2	3				448
TOTAL FOR MAP NO. 2										**0.682**							**120**					**70**					**8,820**	**2**	**3**				**448**
2018CTP.08.13.10621	Montgomery	3	NC 24/27	FROM US 220 ALT W OF RR TRACKS TO END C&G	3,4	2		NO	NO	1.81	60					25,600				2,160	130	100					65,142	1	4				300
TOTAL FOR MAP NO. 3										**1.81**						**25,600**				**2,160**	**130**	**100**					**65,142**	**1**	**4**				**300**
TOTAL FOR PROJ NO. 2018CTP.08.13.10621										**3.015**						**25,600**	**635**			**2,160**	**130**	**270**					**88,077**	**15**	**12**				**1,568**
2018CPT.08.13.10771	Richmond	4	NC 73	FROM MONT. CO LINE TO SR 1005 (CARTLEDGE CREEK RD)	8	2		NO	NO	6.29	22			12.58	1,761.00		2,000		8,225		494	600		89,035.00	31,162								
TOTAL FOR MAP NO. 4										**6.29**				**12.58**	**1,761.00**		**2,000**		**8,225**		**494**	**600**		**89,035.00**	**31,162**								
2018CPT.08.13.10771	Richmond	5	NC 73	FROM SR 1005 (CARTLEDGE CREEK RD) TO US 220	8	2		NO	NO	5.65	23			11.30	1,582.00		1,000		7,300		438	500		78,971.00	27,639								
TOTAL FOR MAP NO. 5										**5.65**				**11.30**	**1,582.00**		**1,000**		**7,300**		**438**	**500**		**78,971.00**	**27,639**	*							
TOTAL FOR PROJ NO. 2018CPT.08.13.10771										**11.94**				**23.88**	**3,343.00**		**3,000**		**15,525**		**932**	**1,100**		**168,006.00**	**58,801**	**1**							
2018CTP.08.13.20621	Montgomery	6	SR 1150 (RIVER RD)	FROM NC 109 TO SR 1146 (DUSTY LEVEL RD)	6	2	2WU	NO	NO	2.582	20			5.16	775.00	30,444	60		2,820		169	10											
TOTAL FOR MAP NO. 6										**2.582**				**5.16**	**775.00**	**30,444**	**60**		**2,820**		**169**	**10**											
2018CTP.08.13.20621	Montgomery	7	SR 1310 (LOVE JOY RD)	FROM TROY TOWN LIMIT (0.36MI N OF SR 1138 SHILOH RD) TO BRIDGE #133 OVER DOOMAS CREEK	7	2		NO	NO	1.405	23			2.81	422.00	300	150		1,765		106	100	19,000.00		7,600								
TOTAL FOR MAP NO. 7										**1.405**				**2.81**	**422.00**	**300**	**150**		**1,765**		**106**	**100**	**19,000.00**		**7,600**								
2018CTP.08.13.20621	Montgomery	8	SR 1130 (APPLE ORCHARD RD)	FROM SR 1174 (PEE DEE RD) TO SR 1132 (STONEY FORK CH RD)	6	2	2WU	NO	NO	2.18	20			4.36	654.00	25,780	115		2,380		143	10											
TOTAL FOR MAP NO. 8										**2.18**				**4.36**	**654.00**	**25,780**	**115**		**2,380**		**143**	**10**				*							
TOTAL FOR PROJ NO. 2018CTP.08.13.20621										**6.167**				**12.33**	**1,851.00**	**56,524**	**325**		**6,965**		**418**	**120**	**19,000.00**		**7,600**	**1**							
2018CPT.08.13.20771	Richmond	9	SR 1005 (CARTLEDGE CREEK RD)	FROM SR 1148 (JOHN WEBB RD) TO SR 1307 (PLEASENT HILL CH RD)	10	2		NO	NO	2.34	22			4.68	655.00		300		2,810		169	50											
TOTAL FOR MAP NO. 9										**2.34**				**4.68**	**655.00**		**300**		**2,810**		**169**	**50**											
2018CPT.08.13.20771	Richmond	10	SR 1148 (GRASSY ISLAND RD)	FROM SR 1309 (PAGE ST) TO SR 1005 (CARTLEDGE CREEK RD)	8	2		NO	NO	1.8	19			3.62	506.00		100		2,180		131	50		22,755.00	7,965								
TOTAL FOR MAP NO. 10										**1.8**				**3.62**	**506.00**		**100**		**2,180**		**131**	**50**		**22,755.00**	**7,965**								
2018CPT.08.13.20771	Richmond	11	SR 1966 (AIRPORT RD)	FROM NC 177 TO SR 1108 (MIZPAH RD)	8	2		NO	NO	2.94	24			5.88	823.00		600		4,770		286	150		53,981.00	18,893								
TOTAL FOR MAP NO. 11										**2.94**				**5.88**	**823.00**		**600**		**4,770**		**286**	**150**		**53,981.00**	**18,893**								
2018CPT.08.13.20771	Richmond	12	SR 1939 (HANNAH PICKETT RD)	FROM SR 1903 (MILL RD) TO SR 1966 (AIRPORT RD)	9,10	2		NO	NO	0.51	25			0.86	120.00	5,000	800		710		43												
TOTAL FOR MAP NO. 12										**0.51**				**0.86**	**120.00**	**5,000**	**800**		**710**		**43**					*							
TOTAL FOR PROJ NO. 2018CPT.08.13.20771										**7.59**				**15.04**	**2,104.00**	**5,000**	**1,800**		**10,470**		**629**	**250**		**76,736.00**	**26,858**	**1**							
WBS 47774	Montgomery	13	NC 73	FROM RICHMOND CO TO SW PVT JT OF NEW BRIDGE# 53 AT THE MOORE CO LINE	5	2		NO	NO	1.553	20	235	3.11					950	350		64									155	30	2.26	
TOTAL FOR MAP NO. 13										**1.553**		**235.00**	**3.11**					**950**	**350**		**64**									**155**	**30**	**2.26**	
TOTAL FOR PROJ NO. WBS 47774										**1.553**		**235**	**3.11**					**950**	**350**		**64**									**155**	**30**	**2.26**	
WBS 47775	Richmond	14	NC 73	FROM US 220 TO MONTGOMERY CO. LINE	5	2		NO	NO	2.96	4	435	5.92					1,890	665		125									300	50	4.31	
TOTAL FOR MAP NO. 14										**2.96**		**435.00**	**5.92**					**1,890**	**665**		**125**									**300**	**50**	**4.31**	
TOTAL FOR PROJ NO. WBS 47775										**2.96**		**435.00**	**5.92**					**1,890**	**665**		**125**									**300**	**50**	**4.31**	
GRAND TOTAL										**33.225**		**670.00**	**9.03**	**51.25**	**7,298.00**	**87,124**	**5,760**	**2,840**	**33,975**	**2,160**	**2,298**	**1,740**	**19,000.00**	**244,742.00**	**93,259**	**3**	**88,077**	**15**	**12**	**455**	**80**	**6.57**	**1,568**