



| PAVEMENT SCHEDULE | |
|-------------------|---|
| C1 | PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD. |
| C2 | PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. |
| C3 | PROP. APPROX. 1.25" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 137.5 LBS. PER SQ. YD. |
| M | MILLED RUMBLE STRIPS |
| S | AGGREGATE SHOULDER BORROW |
| U | EXISTING PAVEMENT. |
| V1 | MILLING 1.5" IN DEPTH |