

## REFORESTATION

□ TREE REFORESTATION SHALL JE PLANTED 6 FT. TO 10 FT. ON CENTER, RANDOM SPACING, AVERAGING 8 FT. ON CENTER, APPROXIMATELY 680 PLANTS PER ACRE.

**REFORESTATION** MIXTURE, TYPE, SIZE, AND FURNISH SHALL

40% PLATANUS OCCIDENTALIS

20% PINUS TAEDA

40% FRAXINUS PENNSYLVANICA

PROJECT REFERENCE NC	<b>)</b> .	SHEET NO.
B-4932		RF-I
RW SHEET NO.		
ROADWAY DESIGN ENGINEER		HYDRAULICS ENGINEER
	B-4932 rw sheet n roadway design	B-4932 rw sheet no. roadway design

CONFORM TO THE FOLLOWING:		
AMERICAN SYCAMORE	12 in – 18 in <i>J</i> R	
LOJLOLLY PINE	12 in – 18 in <b>3</b> R	
GREEN ASH	12 in – 18 in <b>3</b> R	

## **REFORESTATION DETAIL SHEET**

N.C.D.O.T. - ROADSIDE ENVIRONMENTAL UNIT