

**This electronic collection of documents is provided
for the convenience of the user
and is Not a Certified Document –**

**The documents contained herein were originally issued
and sealed by the individuals whose names and license
numbers appear on each page, on the dates appearing
with their signature on that page.**

**This file or an individual page
shall not be considered a certified document.**

GEOTECHNICAL ENGINEERING UNIT

RETAINING WALL INVENTORY

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS TO MAKE ANY INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

DATE NOVEMBER, 2008

1/17/2018


3

PROJECT: 34802.1.1

DRAWN BY: N. D. MOHS, W. D. FIELDS

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.




NORTH CAROLINA DEPARTMENT OF TRANSPORTATION



DIVISION OF HIGHWAYS

GEOTECHNICAL ENGINEERING UNIT

SUBSURFACE INVESTIGATION

SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

SOIL DESCRIPTION										GRADATION										ROCK DESCRIPTION										TERMS AND DEFINITIONS									
SOIL IS CONSIDERED UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO THE STANDARD PENETRATION TEST (AASHTO T 206, ASTM D1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY INCLUDE THE FOLLOWING: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. FOR EXAMPLE, <i>VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6</i>										WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORMLY GRADED - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLE SIZES OF TWO OR MORE SIZES.										HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT REFUSAL IF TESTED. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS IN NON-COASTAL PLAIN MATERIAL. THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS: WEATHERED ROCK (WR)  NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES > 100 BLOWS PER FOOT IF TESTED. CRYSTALLINE ROCK (CR)  FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC. NON-CRYSTALLINE ROCK (NCR)  FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC. COASTAL PLAIN SEDIMENTARY ROCK (CP)  COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.										ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, SUCH AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLOGGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM.) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (RQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SREC.) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SROD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.									
SOIL LEGEND AND AASHTO CLASSIFICATION										MINERALOGICAL COMPOSITION										WEATHERING																			
GENERAL CLASS.										MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHEN THEY ARE CONSIDERED OF SIGNIFICANCE.										FRESH ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE.																			
GROUP CLASS.										COMPRESSIBILITY										VERY SLIGHT (V SL.) ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN, CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.																			
SYMBOL										PERCENTAGE OF MATERIAL										SLIGHT (SL.) ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.																			
%										GROUND WATER										MODERATE (MOD.) SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.																			
MATERIAL PASSING #40 LL PI										MISCELLANEOUS SYMBOLS										MODERATELY SEVERE (MOD. SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. IF TESTED, WOULD YIELD SPT REFUSAL																			
GROUP INDEX										RECOMMENDATION SYMBOLS										SEVERE (SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. IF TESTED, WOULD YIELD SPT N VALUES > 100 BPF																			
USUAL TYPES OF MAJOR MATERIALS										ABBREVIATIONS										VERY SEVERE (V SEV.) ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE THAT ONLY MINOR VESTIGES OF ORIGINAL ROCK FABRIC REMAIN. IF TESTED, WOULD YIELD SPT N VALUES < 100 BPF																			
GEN. RATING AS SUBGRADE										EQUIPMENT USED ON SUBJECT PROJECT										COMPLETE ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.																			
PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30																				ROCK HARDNESS																			
CONSISTENCY OR DENSENESS																				VERY HARD CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.																			
PRIMARY SOIL TYPE																				HARD CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.																			
COMPACTNESS OR CONSISTENCY																				MODERATELY HARD CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.																			
RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)																				MEDIUM HARD CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.																			
RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)																				SOFT CAN BE GROVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.																			
TEXTURE OR GRAIN SIZE																				VERY SOFT CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGERNAIL.																			
U.S. STD. SIEVE SIZE OPENING (MM)																				FRACTURE SPACING																			
BOULDER (BLDR.)																				BEDDING																			
COBBLE (COB.)																																							
GRAVEL (GR.)																																							
COARSE SAND (CSE. SD.)																																							
FINE SAND (F SD.)																																							
SILT (SL.)																																							
CLAY (CL.)																																							
GRAIN SIZE																																							
SOIL MOISTURE - CORRELATION OF TERMS																																							
SOIL MOISTURE SCALE (ATTERBERG LIMITS)																																							
FIELD MOISTURE DESCRIPTION																																							
GUIDE FOR FIELD MOISTURE DESCRIPTION																																							
LL - LIQUID LIMIT																																							
PL - PLASTIC LIMIT																																							
OM - OPTIMUM MOISTURE SHRINKAGE LIMIT																																							
SL - SHRINKAGE LIMIT																																							
PLASTICITY																																							
NON PLASTIC																																							
SLIGHTLY PLASTIC																																							
MODERATELY PLASTIC																																							
HIGHLY PLASTIC																																							
COLOR																																							
DESCRIPTORS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.																																							



REFERENCE: U-2412A

PROJECT: 34802

CONTENTS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	LEGEND (SOIL & ROCK)
2A	SUPPLEMENTAL LEGEND (GSI)
3	SITE PLAN
4-5	PROFILES
6-12	CROSS SECTIONS
13-44	BORE LOGS, CORE LOGS & ROCK CORE PHOTOS
45	ROCK TEST RESULTS
46	SITE PHOTOS

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

COUNTY GUILFORD
PROJECT DESCRIPTION GREENSBORO/HIGH POINT -
SR 1486/SR 4121 (GREENSBORO/HIGH POINT RD)
FROM PROPOSED US 311 BYPASS TO WEST OF
SR 1480 (VICKERY CHAPEL RD)
SITE DESCRIPTION STRUCTURE NO. 270 & 271 ON
SR 4121 OVER NSRR AND UNNAMED TRIBUTARY
TO DEEP RIVER

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	U-2412A	1	46

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT, AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
 - BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

PERSONNEL

M. ELLIS, E.I.

K. PLUMMER

N. MCLAREN

S. CARPENTER

M&W DRILLING

HPC

INVESTIGATED BY ECS SOUTHEAST, LLP

DRAWN BY M. BREWER, P.E.

CHECKED BY M. WALKO, P.E.

SUBMITTED BY ECS SOUTHEAST, LLP

DATE MAY 2018

Prepared in the Office of:



ECS SOUTHEAST, LLP
1812 CENTER PARK DRIVE, SUITE D
CHARLOTTE, NC 28217
(704) 525-5152 [PHONE]
(704) 357-0023 [FAX]
NC REGISTERED
ENGINEERING
FIRM # F-1078



DocuSigned by:

Michael J. Walko, PE 5/1/2018

54F1F8F352D2406...

SIGNATURE DATE

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED






NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

SUBSURFACE INVESTIGATION

SUPPLEMENTAL LEGEND, GEOLOGICAL STRENGTH INDEX (GSI) TABLES
FROM AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS

AASHTO LRFD Figure 10.4.6.4-1 — Determination of GSI for Jointed Rock Mass (Marinos and Hoek, 2000)


AASHTO LRFD Figure 10.4.6.4-2 — Determination of GSI for Tectonically Deformed Heterogeneous Rock Masses (Marinos and Hoek, 2000)


GEOLOGICAL STRENGTH INDEX (GSI) FOR JOINTED ROCKS (Hoek and Marinos, 2000) From the lithology, structure and surface conditions of the discontinuities, estimate the average value of GSI. Do not try to be too precise. Quoting a range from 33 to 37 is more realistic than stating that GSI = 35. Note that the table does not apply to structurally controlled failures. Where weak planar structural planes are present in an unfavorable orientation with respect to the excavation face, these will dominate the rock mass behaviour. The shear strength of surfaces in rocks that are prone to deterioration as a result of changes in moisture content will be reduced if water is present. When working with rocks in the fair to very poor categories, a shift to the right may be made for wet conditions. Water pressure is dealt with by effective stress analysis.	SURFACE CONDITIONS VERY GOOD Very rough, fresh unweathered surfaces GOOD Rough, slightly weathered, iron stained surfaces FAIR Smooth, moderately weathered and altered surfaces POOR Slickensided, highly weathered surfaces with compact coatings or fillings or angular fragments VERY POOR Slickensided, highly weathered surfaces with soft clay coatings or fillings	STRUCTURE INTACT OR MASSIVE - intact rock specimens or massive in situ rock with few widely spaced discontinuities BLOCKY - well interlocked undisturbed rock mass consisting of cubical blocks formed by three intersecting discontinuity sets VERY BLOCKY - interlocked, partially disturbed mass with multi-faceted angular blocks formed by 4 or more joint sets BLOCKY/DISTURBED/SEAMY - folded with angular blocks formed by many intersecting discontinuity sets. Persistence of bedding planes or schistosity DISINTEGRATED - poorly interlocked, heavily broken rock mass with mixture of angular and rounded rock pieces LAMINATED/SHEARED - Lack of blockiness due to close spacing of weak schistosity or shear planes	DECREASING SURFACE QUALITY ➡ 90 80 70 60 50 40 30 20 10 N/A N/A	GSI FOR HETEROGENEOUS ROCK MASSES SUCH AS FLYSCH (Marinos, P and Hoek E., 2000) From a description of the lithology, structure and surface conditions (particularly of the bedding planes), choose a box in the chart. Locate the position in the box that corresponds to the condition of the discontinuities and estimate the average value of GSI from the contours. Do not attempt to be too precise. Quoting a range from 33 to 37 is more realistic than giving GSI = 35. Note that the Hoek-Brown criterion does not apply to structurally controlled failures. Where unfavourably oriented continuous weak planar discontinuities are present, these will dominate the behaviour of the rock mass. The strength of some rock masses is reduced by the presence of groundwater and this can be allowed for by a slight shift to the right in the columns for fair, poor and very poor conditions. Water pressure does not change the value of GSI and it is dealt with by using effective stress analysis.	SURFACE CONDITIONS OF DISCONTINUITIES (Predominantly bedding planes) VERY GOOD - Very Rough, fresh unweathered surfaces GOOD - Rough, slightly weathered surfaces FAIR - Smooth, moderately weathered and altered surfaces POOR - Very smooth, occasionally slickensided surfaces with compact coatings or fillings with angular fragments VERY POOR - Very smooth, slickensided or highly weathered surfaces with soft clay coatings or fillings	COMPOSITION AND STRUCTURE A. Thick bedded, very blocky sandstone. The effect of pelitic coatings on the bedding planes is minimized by the confinement of the rock mass. In shallow tunnels or slopes these bedding planes may cause structurally controlled instability. B. Sandstone with thin inter-layers of siltstone C. Sandstone and siltstone in similar amounts D. Siltstone or silty shale with sandstone layers E. Weak siltstone or clayey shale with sandstone layers C, D, E, and G - may be more or less folded than illustrated but this does not change the strength. Tectonic deformation, faulting and loss of continuity moves these categories to F and H. F. Tectonically deformed, intensively folded/faulted, sheared clayey shale or siltstone with broken and deformed sandstone layers forming an almost chaotic structure G. Undisturbed silty or clayey shale with or without a few very thin sandstone layers H. Tectonically deformed silty or clayey shale forming a chaotic structure with pockets of clay. Thin layers of sandstone are transformed into small rock pieces. ➡ Means deformation after tectonic disturbance	70 60 50 40 30 20 10
---	--	---	---	---	---	--	---



ECS SOUTHEAST, LLP
1812 CENTER PARK DRIVE, SUITE D
CHARLOTTE, NC 28217
(704) 525-5152 [PHONE]
(704) 357-0023 [FAX]
NC REGISTERED
ENGINEERING
FIRM # F-1078

PROJECT REFERENCE NO.	SHEET NO.
U-2412A	3
SITE PLAN	
0 60 120 FEET	
STRUCTURE NO. 270 & 271 ON SR 4121 OVER NSRR AND UNNAMED TRIBUTARY TO DEEP RIVER	
BRIDGE 270 & 271 SKEW	
END BENT 1	108 DEGREES
BENT 1	110 DEGREES
BENT 2	112 DEGREES
BENT 3	114 DEGREES
BENT 4	116 DEGREES
BENT 5	118 DEGREES
END BENT 2	120 DEGREES






5/14/99

04-MAY-2018 15:41
C:\2018\PROJECTS\12000-12999\12600\12612 - U-2412A Structure No. 270 and No. 271 over NSRR and Deep River Tributary\CAADD.GEOTECH\SiteSub\U-2412A_GEO_PFL_2.dgn


Prepared in the Office of:

ECS SOUTHEAST, LLP
1111 COUNTRY CLUB DRIVE, SUITE 200
CHARLOTTE, NC 28211
(704) 363-1111
(704) 363-1112
FAX (704) 363-1113
ECS@ECS-SE.COM
www.ecs-engineering.com

0 50 100

VE=5:1


PROJECT REFERENCE NO.	SHEET NO.
U-2412A	5
PROFILE BORINGS PROJECTED 40' RT OF -L- ALONG BRIDGE 271 (RL)	

-L- (EBL FUTURE SR 4121)




6/23/16

03-MAY-2018 16:51
I:\260TECH\02-PROJECTS\12000-12999\12600\12612 - U-2412A Structure No. 270 and No. 271 over NSRR and Deep River Tributary\CA00.GEOTECH\XSC\U-2412A.GEO.BROG270.271.XSL.dgn
\$\$\$\$\$USERNAME\$\$\$\$\$



—L— GROUNDLINE ALONG BENT 2 SKEW TAKEN FROM ROADWAY DESIGN FILES PROVIDED BY NCDOT ON DATE 03/05/18. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORING, WITH BOTH PROJECTED ON THE CROSS SECTION.

93+25.73	-L- GROUNDLINE ALONG BENT 3 SKEW TAKEN FROM ROADWAY DESIGN FILES PROVIDED BY NCDOT ON DATE 03/05/18. INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORING,	6
C	WITH BOTH PROJECTED ON THE CROSS SECTION.	






6/23/16

03-MAY-2018 16:52
I:\2\GEO\TECH\02-PROJECTS\12000-12999\12600\12612 - U-2412A Structure No. 270 and No. 271 over NSRR and Deep River Tributary\CAADD\GEO\TECH\XSC\U-2412A_GEO_BROG270_271.XSL.dgn
\$\$\$\$\$USERNAME\$\$\$\$\$

Prepared in the Office of:
ECS
ECS SOUTHEAST, LLP
1812 CENTER PARK DRIVE, SUITE D
CHARLOTTE, NC 28217
(704) 537-1100 (PHONE)
(704) 537-0023 (FAX)
NC REGISTERED
ENGINEERING
FIRM # E-10798



PROJ. REFERENCE NO.	SHEET NO.
U-2412A	12
BRIDGE 270 & 271 ON SR 4121 OVER NSRR & DEEP RIVER TRIBUTARY END BENT 2 SKEW: 120 DEGREES	



WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST S. Carpenter						
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary											GROUND WTR (ft)				
BORING NO. RW-1			STATION 89+67			OFFSET 43 ft LT			ALIGNMENT -L-			0 HR. Dry			
COLLAR ELEV. 786.8 ft			TOTAL DEPTH 23.7 ft			NORTHING 814,688			EASTING 1,719,516			24 HR. Dry			
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic						
DRILLER B. Snow			START DATE 02/02/18			COMP. DATE 02/02/18			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
790															
	786.8	0.0	1	5	6									786.8	0.0
785														RESIDUAL	
	783.3	3.5	18	28	41									Stiff to Hard, Orange-Brown-Tan-Black, Fine to Coarse Sandy SILT (A-4)	
780														780.8	6.0
	780.8	6.0	15	26	32									Very Dense, Tan-Black-Brown, Silty Fine to Coarse SAND (A-2-4)	
	778.3	8.5	100/0.4											778.3	8.5
775														WEATHERED ROCK	
	773.3	13.5	38	62/0.3										Tan-Brown (METAMPRPHOSED GRANITIC ROCK)	
770															
	768.3	18.5	100/0.4												
765															
	763.2	23.6	60/0.1											763.2	23.6
														763.1	23.7
CRYSTALLINE ROCK (METAMORPHOSED GRANITIC ROCK) Boring Terminated with Standard Penetration Test Refusal at Elevation 763.1 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK) Notes: Surficial Organics Soils from 0.0 to 0.2 ft. Weathered and Crystalline Rock Boulders / Outcrops were observed in the Railroad Cut.															

NCDOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT_GDT 5/3/18

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1				TIP U-2412A		COUNTY GUILFORD		GEOLOGIST M. Ellis						
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary												GROUND WTR (ft)		
BORING NO. EB1-A (LL)			STATION 90+15			OFFSET 55 ft LT			ALIGNMENT -L-			0 HR.	Dry	
COLLAR ELEV. 785.7 ft			TOTAL DEPTH 19.7 ft			NORTHING 814,693			EASTING 1,719,564			24 HR.	Dry	
DRILL RIG/HAMMER EFF./DATE HPC2473 CME-550 85% 01/10/2018						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER J. Cain			START DATE 04/26/18			COMP. DATE 04/26/18			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft)	DEPTH (ft)
790														
785	785.7	0.0											785.7	GROUND SURFACE 0.0
780	782.2	3.5	1	1	2								782.7	RESIDUAL Soft, Brown-Orange, Fine Sandy CLAY (A-6) 3.0
	779.7	6.0	10	18	49								779.7	Hard, Brown-Green, Fine to Coarse Sandy SILT (A-4), with trace gravel-sized quartz fragments 6.0
	777.2	8.5	37	63/0.4										
775			33	57	43/0.3									WEATHERED ROCK Gray-Brown-Green, (METAMORPHOSED GRANITIC ROCK)
770	772.2	13.5											773.7	RESIDUAL Very Dense, Gray-Green-Brown, Silty Fine to Coarse SAND (A-2-4) 12.0
	767.2	18.5											767.2	
	766.0	19.7	100/0.2										766.0	WEATHERED ROCK Gray-Green, (METAMORPHOSED GRANITIC ROCK) 19.7
			60/0.0											Boring Terminated with Standard Penetration Test Refusal at Elevation 766.0 ft On Crystalline Rock (METAMORPHOSED GRANITIC ROCK)

WBS 34802.1.1				TIP U-2412A		COUNTY GUILFORD		GEOLOGIST M. Ellis					
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary											GROUND WTR (ft)		
BORING NO. EB1-B (LL)			STATION 90+03			OFFSET 19 ft LT			ALIGNMENT -L-		0 HR.	Dry	
COLLAR ELEV. 785.2 ft			TOTAL DEPTH 18.9 ft			NORTHING 814,659			EASTING 1,719,547		24 HR.	Dry	
DRILL RIG/HAMMER EFF./DATE HPC2473 CME-550 85% 01/10/2018						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic				
DRILLER J. Cain			START DATE 04/26/18			COMP. DATE 04/26/18			SURFACE WATER DEPTH N/A				
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			
790													
785	785.2	0.0											
780	781.7	3.5	WOH	WOH	WOH								785.2 GROUND SURFACE 0.0
	779.2	6.0	4	6	10								RESIDUAL Very Soft, Brown-Orange, Fine Sandy CLAY (A-6) 3.0
	776.7	8.5	8	12	13								782.2 Very Stiff, Orange, Clayey SILT (A-5) 3.0
775	771.7	13.5	54	46/0.4									779.7 Very Stiff, Tan-Orange, Fine Sandy SILT (A-4) 5.5
	766.7	18.5	100/0.2										776.7 Very Stiff, Tan-Orange, Fine Sandy SILT (A-4) 8.5
770													WEATHERED ROCK Gray-Green, (METAMORPHOSED GRANITIC ROCK) 8.5
													766.3 Boring Terminated at Elevation 766.3 ft In Weathered Rock (METAMORPHOSED GRANITIC ROCK) 18.9

NCDOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT.GDT 5/3/18

WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST M. Ellis					
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary										GROUND WTR (ft)				
BORING NO. B1-A (LL)			STATION 91+29			OFFSET 55 ft LT			ALIGNMENT -L-		0 HR. Dry			
COLLAR ELEV. 771.7 ft			TOTAL DEPTH 15.3 ft			NORTHING 814,678			EASTING 1,719,675		24 HR. Dry			
DRILL RIG/HAMMER EFF./DATE HPC2473 CME-550 85% 01/10/2018						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER J. Cain			START DATE 04/26/18			COMP. DATE 04/26/18			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft)	DEPTH (ft)
775														
	771.7	0.0											771.7	0.0
770			2	2	3							M	GROUND SURFACE	
	768.2	3.5										M	RESIDUAL	
765			3	5	7							M	Medium Stiff, Brown-Orange, Fine Sandy CLAY (A-6)	
	765.7	6.0										M	Stiff to Very Stiff, Orange, Fine Sandy SILT (A-4)	
	763.2	8.5	5	9	9							M		
760			20	44	24							M	Very Dense, Orange-Tan, Silty Fine to Coarse SAND (A-2-4), with trace gravel-sized quartz fragments and mica	
	758.2	13.5											757.7	14.0
	756.4	15.3	23	67	33/0.1								756.4	15.3
			60/0.0										WEATHERED ROCK	
													Tan-White-Orange, (METAMORPHOSED GRANITIC ROCK)	
													Boring Terminated with Standard Penetration Test Refusal at Elevation 756.4 ft On Crystalline Rock (METAMORPHOSED GRANITIC ROCK)	

NCDOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT_GDT 5/3/18

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST M. Ellis					
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary									GROUND WTR (ft)					
BORING NO. B1-B (LL)			STATION 91+15			OFFSET 19 ft LT			ALIGNMENT -L-					
COLLAR ELEV. 774.5 ft			TOTAL DEPTH 39.8 ft			NORTHING 814,644			EASTING 1,719,658					
DRILL RIG/HAMMER EFF./DATE HPC2473 CME-550 85% 01/10/2018						DRILL METHOD SPT Core Boring			HAMMER TYPE Automatic					
DRILLER J. Cain			START DATE 04/25/18			COMP. DATE 04/25/18			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft) DEPTH (ft)
775														
	774.5	0.0	1	1	1							M		774.5 GROUND SURFACE 0.0
														RESIDUAL
														Very Soft to Stiff, Black-Brown-Orange, Fine Sandy CLAY (A-6)
770	771.0	3.5	2	4	6							M		
	768.5	6.0												
			7	12	10							M		768.2 6.3
	766.0	8.5												766.5 8.0
765			5	6	10							W		Medium Dense, Orange-Tan, Silty Fine to Coarse SAND (A-2-4), with trace gravel-sized quartz fragments and mica
														Very Stiff, Orange-Tan, Fine Sandy SILT (A-4), with trace mica
	761.0	13.5	100/0.4											761.0 13.5
760														WEATHERED ROCK
	758.3	16.2	60/0.1											Tan, (METAMORPHOSED GRANITIC ROCK)
														758.3 16.2
														758.2 16.3
755														756.5 18.0
														CRYSTALLINE ROCK
														Severely to Moderately Weathered, Soft to Medium Hard, Tan-Gray, (METAMORPHOSED GRANITIC ROCK), with Very Close Fracture Spacing
														REC = 29%, RQD = 0%, GSI = 15 to 20
														Slightly Weathered to Fresh, Medium Hard to Hard, Gray-Blue, (METAMORPHOSED GRANITIC ROCK), with Very Close to Moderately Close Fracture Spacing
750														
745														744.1 30.4
														742.6 31.9
														WEATHERED ROCK (METAMORPHOSED GRANITIC ROCK)
740											RS-9			REC = 0%
														CRYSTALLINE ROCK
														Fresh, Hard, Blue, (METAMORPHOSED QUARTZ DIORITE), with Close to Moderately Close Fracture Spacing
735														734.7 39.8
														REC = 100%, RQD = 96%, GSI = 80 to 85
														Boring Terminated at Elevation 734.7 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)




NCDOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT.GDT 5/4/18

GEOTECHNICAL BORING REPORT
CORE LOG

SHEET 16

WBS 34802.1.1					TIP U-2412A			COUNTY GUILFORD			GEOLOGIST M. Ellis			
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary											GROUND WTR (ft)			
BORING NO. B1-B (LL)					STATION 91+15			OFFSET 19 ft LT			ALIGNMENT -L-		0 HR. N/A	
COLLAR ELEV. 774.5 ft					TOTAL DEPTH 39.8 ft			NORTHING 814,644			EASTING 1,719,658		24 HR. 10.4	
DRILL RIG/HAMMER EFF./DATE HPC2473 CME-550 85% 01/10/2018								DRILL METHOD SPT Core Boring				HAMMER TYPE Automatic		
DRILLER J. Cain					START DATE 04/25/18			COMP. DATE 04/25/18			SURFACE WATER DEPTH N/A			
CORE SIZE NQ2					TOTAL RUN 23.5 ft									
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) % RQD (ft) %		SAMP. NO.	STRATA REC. (ft) % RQD (ft) %		LOG	DESCRIPTION AND REMARKS			
											ELEV. (ft)	DEPTH (ft)		
758.17											Begin Coring @ 16.3 ft			
	758.2	16.3	3.5	0:48/0.5 0:42/1.0 1:41/1.0 2:01/1.0	(2.3) 66%	(1.6) 46%		(0.5) 29%	(0.0) 0%		758.2 756.5	16.3 18.0	CRYSTALLINE ROCK Severely to Moderately Weathered, Soft to Medium Hard, Tan-Gray, (METAMORPHOSED GRANITIC ROCK), with Very Close Fracture Spacing	
755	754.7	19.8						(12.1) 98%	(11.5) 93%				GSI = 15 to 20	
			5.0	2:03/1.0 2:53/1.0 2:36/1.0 3:13/1.0 3:52/1.0	(4.7) 94%	(4.3) 86%							Slightly Weathered to Fresh, Hard, Gray-Blue, (METAMORPHOSED GRANITIC ROCK), with Very Close to Moderately Close Fracture Spacing	
750	749.7	24.8											GSI = 75 to 80	
			5.0	3:56/1.0 3:27/1.0 1:47/1.0 2:31/1.0 2:47/1.0	(5.0) 100%	(5.0) 100%								
745	744.7	29.8						(0.0) 0%	(0.0) 0%		744.1 742.6	30.4 31.9	WEATHERED ROCK (METAMORPHOSED GRANITIC ROCK)	
			5.0	0:50/1.0 0:48/1.0 1:27/1.0 1:31/1.0 1:44/1.0	(3.5) 70%	(3.2) 64%		(7.9) 100%	(7.6) 96%				CRYSTALLINE ROCK Fresh, Hard, Blue, (METAMORPHOSED GRANITIC ROCK), with Close to Moderately Close Fracture Spacing	
740	739.7	34.8					RS-9							
			5.0	1:54/1.0 1:42/1.0 1:35/1.0 1:52/1.0 1:35/1.0	(5.0) 100%	(5.0) 100%					734.7	39.8	RS-9: 33.1' - 33.5' Unit Weight: 191.4 pcf Unconfined Compressive Strength: 19,780 psi (2848 ksf)	
735	734.7	39.8											GSI = 80 to 85 Boring Terminated at Elevation 734.7 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)	

NCDOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT.GDT 5/4/18

**Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Tributary to Deep River****ECS Southeast Project No. 08:12612****WBS: 34802.1.1 Tip No.: U-2412A****Rock Core Photographs: Boring - B1-B (LL)****Station: 91+15 Offset: 19' LT**

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST M. Ellis						
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary										GROUND WTR (ft)					
BORING NO. B2-A (LL)			STATION 92+40			OFFSET 55 ft LT			ALIGNMENT -L-			0 HR. N/A			
COLLAR ELEV. 760.8 ft			TOTAL DEPTH 45.8 ft			NORTHING 814,668			EASTING 1,719,784			24 HR. 16.2			
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017						DRILL METHOD SPT Core Boring				HAMMER TYPE Automatic					
DRILLER B. Snow			START DATE 01/30/18			COMP. DATE 01/30/18			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
765															
760	760.8	0.0												760.8	GROUND SURFACE
			2	2	2										
	757.3	3.5	2	4	50									758.3	ARTIFICIAL FILL
755	754.8	6.0	3	3	3									755.3	Soft, Red-Tan, Fine Sandy SILT (A-4) with trace mica and clay
	752.3	8.5	5	6	4									752.8	Hard, Brown, Fine Sandy CLAY (A-6) with trace to little concrete fragments (High N-value likely influenced by concrete debris)
750															RESIDUAL
	747.3	13.5	4	5	6										Medium Stiff, Red-Brown, Fine Sandy CLAY (A-6) with trace mica
745															Stiff, Tan-Orange, Fine to Coarse Sandy SILT (A-4) with trace mica
	742.3	18.5	5	6	6										
740	738.9	21.9												738.9	
		60/0.1												738.8	CRYSTALLINE ROCK
735															Fresh to Slightly Weathered, Moderately Hard to Hard, Blue-Gray, (METAMORPHOSED GRANITIC ROCK), with Very Close to Moderately Close Fracture Spacing
															REC = 93%, RQD = 61%, GSI = 45 - 50
730															
725														725.0	Fresh to Very Slightly Weathered, Hard, Blue-Gray, (METAMORPHOSED GRANITIC ROCK), with Very Close to Wide Fracture Spacing
															REC = 98%, RQD = 92%, GSI = 75 - 80
720														715.0	Boring Terminated at Elevation 715.0 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)
															Notes: Surficial Organic Soils from 0.0 to 0.2 ft

GEOTECHNICAL BORING REPORT

CORE LOG

WBS 34802.1.1				TIP U-2412A				COUNTY GUILFORD				GEOLOGIST M. Ellis			
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary												GROUND WTR (ft)			
BORING NO. B2-A (LL)				STATION 92+40				OFFSET 55 ft LT				ALIGNMENT -L-		0 HR.	N/A
COLLAR ELEV. 760.8 ft				TOTAL DEPTH 45.8 ft				NORTHING 814,668				EASTING 1,719,784		24 HR.	16.2
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017								DRILL METHOD SPT Core Boring				HAMMER TYPE Automatic			
DRILLER B. Snow				START DATE 01/30/18				COMP. DATE 01/30/18				SURFACE WATER DEPTH N/A			
CORE SIZE NQ2				TOTAL RUN 23.8 ft											
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) %		ROD (ft) %	SAMP. NO.	STRATA REC. (ft) %		ROD (ft) %	L O G	DESCRIPTION AND REMARKS		DEPTH (ft)
738.82													Begin Coring @ 22.0 ft		
	738.8	22.0	3.8	1:39/1.0 2:21/1.0 2:32/1.0 2:05/0.8	(3.3) 87%	(1.8) 47%			(12.9) 93%	(8.4) 61%			738.8	CRYSTALLINE ROCK Fresh to Slightly Weathered, Moderately Hard to Hard, Blue-Gray, (METAMORPHOSED GRANITIC ROCK), with Very Close to Moderately Close Fracture Spacing	22.0
735	735.0	25.8		2:22/1.0 2:50/1.0 2:53/1.0 2:48/1.0 3:08/1.0	(4.8) 96%	(4.2) 84%								RS-1: 29.0' - 29.4' Unit Weight: 170.9 pcf Unconfined Compressive Strength: 20,850 psi (3002 ksf)	
730	730.0	30.8	5.0					RS-1						GSI = 45 - 50	
			5.0	2:40/1.0 3:54/1.0 4:20/1.0 4:37/1.0 5:55/1.0	(4.8) 96%	(2.4) 48%									
725	725.0	35.8							(9.8) 98%	(9.2) 92%			725.0	Fresh to Very Slightly Weathered, Hard, Blue-Gray, (METAMORPHOSED GRANITIC ROCK), with Very Close to Wide Fracture Spacing	35.8
			5.0	3:52/1.0 3:27/1.0 3:19/1.0 3:24/1.0 3:26/1.0	(5.0) 100%	(5.0) 100%								GSI = 75 - 80	
720	720.0	40.8													
			5.0	3:41/1.0 5:12/1.0 5:05/1.0 5:02/1.0 5:11/1.0	(4.8) 96%	(4.2) 84%							715.0	Boring Terminated at Elevation 715.0 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)	45.8
	715.0	45.8												Notes: Surficial Organic Soils from 0.0 to 0.2 ft	

NCDDOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT.GDT 5/3/18

NCDOT CORE DOUBLE U2412A GEO BORELOGS.GPJ NC DOT.GDT 5/3/18






Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Tributary to Deep River


ECS Southeast Project No. 08:12612

WBS: 34802.1.1 Tip No.: U-2412-A

Rock Core Photographs: Boring - B2-A (LL)

Station: 92+40 Offset: 55' LT




WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST S. Carpenter					
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary											GROUND WTR (ft)			
BORING NO. B3-A (LL)			STATION 93+46			OFFSET 40 ft LT			ALIGNMENT -L-			0 HR.	27.8	
COLLAR ELEV. 745.3 ft			TOTAL DEPTH 22.2 ft			NORTHING 814,647			EASTING 1,719,887			24 HR.	14.0	
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017						DRILL METHOD H.S Augers			HAMMER TYPE Automatic					
DRILLER B. Snow			START DATE 02/02/18			COMP. DATE 02/02/18			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	L O G	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
750														
745	745.3	0.0												745.3 GROUND SURFACE 0.0
740	741.8	3.5	7	12	6						M		RESIDUAL Stiff to Hard, Tan-Brown-Gray-Orange, Fine to Coarse Sandy SILT (A-4) with trace gravel-sized rock fragments	
	739.3	6.0	2	4	6						M			
	736.8	8.5	8	9	25						M			
735	731.8	13.5	15	29	42						M			
	730	726.8	18.5	21	28	24						M		
725	723.2	22.1	48	52/0.2										726.8 WEATHERED ROCK Tan (METAMORPHOSED GRANITIC ROCK) 18.5
			60/0.1											723.2 CRYSTALLINE ROCK (METAMORPHOSED GRANITIC ROCK) 22.1 Boring Terminated with Standard Penetration Test Refusal at Elevation 723.1 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK) 22.2

GEOTECHNICAL BORING REPORT

CORE LOG

NCDOT CORE DOUBLE U2412A GEO BORELOGS.GPJ NC DOT.GDT 5/3/18

WBS 34802.1.1				TIP U-2412A		COUNTY GUILFORD		GEOLOGIST K. Plummer				
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary										GROUND WTR (ft)		
BORING NO. B3-B (LL)				STATION 93+34		OFFSET 14 ft LT		ALIGNMENT -L-		0 HR.	N/A	
COLLAR ELEV. 747.1 ft				TOTAL DEPTH 50.6 ft		NORTHING 814,621		EASTING 1,719,874		24 HR.	Dry	
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017						DRILL METHOD SPT Core Boring			HAMMER TYPE Automatic			
DRILLER B. Snow				START DATE 01/23/18		COMP. DATE 01/24/18		SURFACE WATER DEPTH N/A				
CORE SIZE NQ2				TOTAL RUN 26.1 ft								
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) %	ROD (ft) %	SAMP. NO.	STRATA REC. (ft) %	ROD (ft) %	L O G	DESCRIPTION AND REMARKS	DEPTH (ft)
722.61											Begin Coring @ 24.5 ft	
720	722.6 721.5	24.5 25.6	1.1 5.0	N=60/0.0 3:30/1.1 2:00/1.0 1:30/1.0 1:30/1.0 1:15/1.0 2:00/1.0	(0.5) 45% (4.4) 88%	(0.0) 0% (0.9) 18%		(10.4) 86%	(4.1) 34%		722.6 CRYSTALLINE ROCK Severely to Slightly Weathered, Moderately Hard, Gray-Brown-White, (METAMORPHOSED GRANITIC ROCK), with Very Close to Close Fracture Spacing RS-3: 32.6' - 33.0' Unit Weight: 166.7 pcf Unconfined Compressive Strength: 4,140 psi (596 ksf) GSI = 30 - 35	24.5
715	716.5	30.6	5.0	1:30/1.0 2:30/1.0 2:30/1.0 2:00/1.0 2:30/1.0	(4.5) 90%	(2.8) 56%	RS-3					
710	711.5	35.6	5.0	2:45/1.0 2:00/1.0 2:15/1.0 2:50/1.0 2:50/1.0	(4.6) 92%	(3.6) 72%		(12.8) 91%	(9.0) 64%		710.5 Fresh to Very Slightly Weathered, Hard, Gray-White, (METAMORPHOSED GRANITIC ROCK), with Very Close to Close Fracture Spacing GSI = 45 - 50	36.6
705	706.5	40.6	5.0	2:50/1.0 2:15/1.0 1:50/1.0 1:50/1.0 2:00/1.0	(4.8) 96%	(2.9) 58%						
700	701.5	45.6	5.0	2:00/1.0 2:00/1.0 2:00/1.0 2:00/1.0 2:00/1.0	(4.4) 88%	(2.9) 58%						
	696.5	50.6		2:00/1.0							696.5 Boring Terminated at Elevation 696.5 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK) Notes: Surficial Organics Soils from 0.0 to 0.3 ft.	50.6






Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Tributary to Deep River

ECS Southeast Project No. 08:12612

WBS: 34802.1.1 Tip No.: U-2412A

Rock Core Photographs: Boring - B3-B (LL)

Station: 93+34 Offset: 14' LT







GEOTECHNICAL BORING REPORT

CORE LOG

NCDOT CORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC DOT.GDT 5/3/18

WBS 34802.1.1				TIP U-2412A		COUNTY GUILFORD		GEOLOGIST K. Plummer			
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary										GROUND WTR (ft)	
BORING NO. B4-A (LL)				STATION 94+63			OFFSET 55 ft LT		ALIGNMENT -L-		0 HR. N/A
COLLAR ELEV. 734.2 ft				TOTAL DEPTH 35.0 ft			NORTHING 814,660		EASTING 1,720,003		24 HR. 9.5
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017							DRILL METHOD SPT Core Boring			HAMMER TYPE Automatic	
DRILLER B. Snow				START DATE 01/16/18			COMP. DATE 01/16/18		SURFACE WATER DEPTH N/A		
CORE SIZE NQ2				TOTAL RUN 21.7 ft							
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) % ROD (ft) %		SAMP. NO.	STRATA REC. (ft) % ROD (ft) %		L O G	DESCRIPTION AND REMARKS ELEV. (ft) DEPTH (ft)
720.9											Begin Coring @ 13.3 ft
720	720.9 719.2	13.3 15.0	1.7	3:00/1.0 2:00/0.7	(1.2) 71%	(0.3) 18%		(6.6) 79%	(3.5) 42%		720.9 Slightly to Moderately Weathered, Moderately Hard to Hard, Brown-Gray, (METAMORPHOSED GRANITIC ROCK), with Very Close to Close Fracture Spacing 13.3
			5.0	1:40/1.0 1:20/1.0 2:00/1.0	(4.0) 80%	(2.2) 44%			GSI = 35 - 40		
715	714.2	20.0		1:40/1.0 1:30/1.0					712.5 21.7		
			5.0	1:30/1.0 1:20/1.0 2:00/1.0	(4.8) 96%	(3.0) 60%			Slightly Weathered to Fresh, Hard, Gray, (METAMORPHOSED GRANITIC ROCK), with Very Close to Close Fracture Spacing		
710	709.2	25.0		3:00/1.0 3:15/1.0				(13.0) 98%	(11.3) 85%		RS-5: 24.6' - 25.0' Unit Weight: 168.3 pcf Unconfined Compressive Strength: 11,770 psi (1,695 ksf)
			5.0	3:15/1.0 4:00/1.0 3:30/1.0	(4.6) 92%	(4.3) 86%	RS-5				GSI = 65 - 70
705	704.2	30.0		2:00/1.0 2:15/1.0							
			5.0	2:00/1.0 2:00/1.0 2:30/1.0	(5.0) 100%	(5.0) 100%					
700	699.2	35.0		3:15/1.0 3:45/1.0							699.2 35.0
											Notes: Surficial Organics Soils from 0.0-0.2 ft.

**Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Tributary to Deep River****ECS Southeast Project No. 08:12612****WBS: 34802.1.1 Tip No.: U-2412A****Rock Core Photographs: Boring - B4-A (LL)****Station: 94+63 Offset: 55' LT**

NC DOT BORE DOUBLE U2412A GEO_BORELOGS.GPJ NC_DOT.GDT 5/3/18

WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST S. Carpenter					
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary											GROUND WTR (ft)			
BORING NO. B5-A (LL)			STATION 95+77			OFFSET 55 ft LT			ALIGNMENT -L-			0 HR.	Dry	
COLLAR ELEV. 736.2 ft			TOTAL DEPTH 11.4 ft			NORTHING 814,662			EASTING 1,720,114			24 HR.	Dry	
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER B. Snow			START DATE 01/21/18			COMP. DATE 01/21/18			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
740														
735	736.2	0.0	2	3	6									736.2 GROUND SURFACE 0.0
	733.2	3.0	3	4	10						M			RESIDUAL Stiff to Very Stiff, Red-Tan-Brown, Fine to Coarse, Sandy SILT (A-4)
730	730.2	6.0	5	8	9						M			
	727.7	8.5	20	24	76/0.4						M			
725	724.8	11.4	60/0.0											727.2 9.0
														724.8 WEATHERED ROCK Tan-Brown (METAMORPHOSED GRANITIC ROCK) 11.4
Boring Terminated with Standard Penetration Test Refusal at Elevation 724.8 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)														
Notes: Surficial Organics Soils from 0.0 to 0.2 ft.														

GEOTECHNICAL BORING REPORT
BORE LOG


WBS 34802.1.1		TIP U-2412A		COUNTY GUILFORD		GEOLOGIST K. Plummer									
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary							GROUND WTR (ft)								
BORING NO. B5-B (LL)		STATION 95+57		OFFSET 19 ft LT		ALIGNMENT -L-		0 HR. N/A							
COLLAR ELEV. 734.9 ft		TOTAL DEPTH 30.2 ft		NORTHING 814,625		EASTING 1,720,096		24 HR. Dry							
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017				DRILL METHOD SPT Core Boring			HAMMER TYPE Automatic								
DRILLER B. Snow		START DATE 01/22/18		COMP. DATE 01/22/18		SURFACE WATER DEPTH N/A									
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT				SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft)	DEPTH (ft)	
735														734.9	0.0
	734.9	0.0	1	1	1							M		GROUND SURFACE	
	731.4	3.5										M		Very Soft, Brown, Fine to Coarse Sandy CLAY (A-6)	3.0
730	728.9	6.0												Stiff, Brown, Fine to Coarse Sandy SILT (A-4)	6.0
	728.3	6.6	100/0.3											60/0.0	6.6
725															
720															
715															
710															
705														704.7	30.2
														Boring Terminated at Elevation 704.7 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)	

NCDOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT.GDT 5/3/18

GEOTECHNICAL BORING REPORT
CORE LOG

WBS 34802.1.1					TIP U-2412A			COUNTY GUILFORD			GEOLOGIST K. Plummer		
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary										GROUND WTR (ft)			
BORING NO. B5-B (LL)					STATION 95+57			OFFSET 19 ft LT			ALIGNMENT -L-		0 HR. N/A
COLLAR ELEV. 734.9 ft					TOTAL DEPTH 30.2 ft			NORTHING 814,625			EASTING 1,720,096		24 HR. Dry
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017							DRILL METHOD SPT Core Boring			HAMMER TYPE Automatic			
DRILLER B. Snow					START DATE 01/22/18			COMP. DATE 01/22/18			SURFACE WATER DEPTH N/A		
CORE SIZE NQ2					TOTAL RUN 23.6 ft								
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS		
					REC. (ft) %	RQD (ft) %		REC. (ft) %	RQD (ft) %				
728.3													
	728.3	6.6	3.6	N=60/0.0 5:30/1.0 4:00/1.0 4:15/1.0 2:30/0.6	(3.5) 97%	(3.4) 94%		(23.3) 99%	(21.7) 92%		728.3	6.6	
725	724.7	10.2		3:30/1.0 3:45/1.0 3:30/1.0 7:00/1.0 9:15/1.0	(5.0) 100%	(4.5) 90%							
			5.0										
720	719.7	15.2		7:30/1.0 6:30/1.0 6:00/1.0 6:45/1.0 4:30/1.0	(5.0) 100%	(5.0) 100%							
			5.0				RS-7						
715	714.7	20.2		5:25/1.0 5:01/1.0 5:00/1.0 5:45/1.0 6:50/1.0	(4.8) 96%	(4.6) 92%							
			5.0										
710	709.7	25.2		5:15/1.0 4:38/1.0 4:10/1.0 5:00/1.0 6:00/1.0	(5.0) 100%	(4.2) 84%							
			5.0										
705	704.7	30.2									704.7	30.2	
											Boring Terminated at Elevation 704.7 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)		

NCDOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT.GDT 5/3/18



Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Tributary to Deep River

ECS Southeast Project No. 08:12612

WBS: 34802.1.1 Tip No. : U-2412A

Rock Core Photographs: Boring - B5-B (LL)

Station: 95+57 Offset: 19' LT

Begin Run 1
6.6'




Begin Run 2
10.2'

0.0 0.2 0.4 0.6 0.8 1.0 1.2 1.4 1.6 1.8 2.0

SCALE IN FEET

Begin Run 3
15.2'



Begin Run 4
20.2'

0.0 0.2 0.4 0.6 0.8 1.0 1.2 1.4 1.6 1.8 2.0

SCALE IN FEET

Begin Run 5
25.2'




End Run 5
30.2'

0.0 0.2 0.4 0.6 0.8 1.0 1.2 1.4 1.6 1.8 2.0

SCALE IN FEET

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST S. Carpenter						
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary									GROUND WTR (ft)						
BORING NO. EB2-A (LL)			STATION 96+90			OFFSET 55 ft LT			ALIGNMENT -L-			0 HR. Dry			
COLLAR ELEV. 751.7 ft			TOTAL DEPTH 18.6 ft			NORTHING 814,668			EASTING 1,720,225			24 HR. Dry			
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic						
DRILLER B. Snow			START DATE 01/21/18			COMP. DATE 01/21/18			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
755															
750	751.7	0.0	2	2	4									751.7	0.0
	748.2	3.5	9	13	22							M		RESIDUAL Medium Stiff to Hard, Tan-Brown, Fine to Coarse Sandy SILT (A-4)	
745	745.7	6.0	15	16	21							M			
	743.2	8.5	27	40	60/0.3							M		742.7	9.0
740														WEATHERED ROCK Tan-Brown (METAMORPHOSED GRANITIC ROCK)	
	738.2	13.5	100/0.4								100/0.4				
735															
	733.2	18.5	60/0.1								60/0.1			733.2	18.5
														733.1	18.6
CRYSTALLINE ROCK (METAMORPHOSED GRANITIC ROCK) Boring Terminated with Standard Penetration Test Refusal at Elevation 733.1 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)															


WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST S. Carpenter					
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary										GROUND WTR (ft)				
BORING NO. EB2-B (LL)			STATION 96+69			OFFSET 19 ft LT			ALIGNMENT -L-		0 HR. Dry			
COLLAR ELEV. 753.1 ft			TOTAL DEPTH 18.8 ft			NORTHING 814,631			EASTING 1,720,207		24 HR. Dry			
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER B. Snow			START DATE 01/21/18			COMP. DATE 01/21/18			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
755														
750	753.1	0.0	2	3	4									753.1 GROUND SURFACE 0.0
	749.6	3.5	21	29	38									750.1 RESIDUAL Medium Stiff, Orange-Brown, Clayey SILT (A-5) 3.0
	747.1	6.0	20	27	29									Hard, Tan, Fine to Coarse Sandy SILT (A-4)
745	744.6	8.5	27	51	49/0.4									744.1 WEATHERED ROCK Tan (METAMORPHOSED GRANITIC ROCK) 9.0
	739.6	13.5	100/0.3											
740														
735	734.6	18.5	100/0.3											734.3 Boring Terminated at Elevation 734.3 ft In Weathered Rock (METAMORPHOSED GRANITIC ROCK) 18.8

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST S. Carpenter											
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary									GROUND WTR (ft)											
BORING NO. RW-2			STATION 89+29			OFFSET 46 ft RT			ALIGNMENT -L-			0 HR. Dry								
COLLAR ELEV. 784.8 ft			TOTAL DEPTH 18.1 ft			NORTHING 814,607			EASTING 1,719,463			24 HR. Dry								
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic											
DRILLER B. Snow			START DATE 02/02/18			COMP. DATE 02/02/18			SURFACE WATER DEPTH N/A											
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION						
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)					
785	784.8	0.0	1	1	3									784.8	GROUND SURFACE	0.0				
	781.3	3.5	5	3	7													781.8	ARTIFICIAL FILL Soft, Red-Brown, Fine to Coarse Sandy SILT (A-4)	3.0
780	778.8	6.0	20	29	32													778.8	RESIDUAL Stiff, Red-Brown, Clayey SILT (A-5)	6.0
	776.3	8.5	17	34	48													770.8	Hard, Orange-Brown, Fine Sandy SILT (A-4)	14.0
775	771.3	13.5	30	55	45/0.3													766.8	WEATHERED ROCK Orange-Brown (METAMORPHOSED GRANITIC ROCK)	18.0
770	766.8	18.0	60/0.1											766.7	CRYSTALLINE ROCK (METAMORPHOSED GRANITIC ROCK)	18.1				
Boring Terminated with Standard Penetration Test Refusal at Elevation 766.7 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)																				
Notes: Surficial Organics Soils from 0.0 to 0.2 ft. Weathered and Crystalline Rock Boulders / Outcrops were observed in the Railroad Cut.																				

NCDOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT.GDT 5/3/18

NC DOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT.GDT 5/3/18

WBS 34802.1.1				TIP U-2412A				COUNTY GUILFORD				GEOLOGIST M. Ellis					
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary												GROUND WTR (ft)					
BORING NO. EB1-B (RL)				STATION 89+80				OFFSET 55 ft RT				ALIGNMENT -L-				0 HR. Dry	
COLLAR ELEV. 783.3 ft				TOTAL DEPTH 22.2 ft				NORTHING 814,589				EASTING 1,719,513				24 HR. Dry	
DRILL RIG/HAMMER EFF./DATE HPC2473 CME-550 85% 01/10/2018								DRILL METHOD H.S. Augers				HAMMER TYPE Automatic					
DRILLER J. Cain				START DATE 04/26/18				COMP. DATE 04/26/18				SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100							
785																	
	783.3	0.0	2	1	2									783.3 GROUND SURFACE 0.0			
780	779.8	3.5	8	9	12							M		RESIDUAL Soft to Hard, Orange-Brown, Fine Sandy SILT (A-4), with trace gravel-sized rock fragments			
	777.3	6.0	13	16	25							M					
775	774.8	8.5	10	14	20							M					
	769.8	13.5	100/0.3									M					
770	769.8	13.5	100/0.3											769.8 WEATHERED ROCK 13.5			
														Tan-Brown, (METAMORPHOSED GRANITIC ROCK)			
765	764.8	18.5	11	89/0.5													
	761.1	22.2	60/0.0														
														761.1 Boring Terminated with Standard Penetration Test Refusal at Elevation 761.1 ft On Crystalline Rock (METAMORPHOSED GRANITIC ROCK) 22.2			

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST M. Ellis						
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary									GROUND WTR (ft)						
BORING NO. B1-A (RL)			STATION 91+02			OFFSET 19 ft RT			ALIGNMENT -L-						
COLLAR ELEV. 775.2 ft			TOTAL DEPTH 30.4 ft			NORTHING 814,608			EASTING 1,719,640						
									0 HR. 25.8						
									24 HR. 12.3						
DRILL RIG/HAMMER EFF./DATE HPC2473 CME-550 85% 01/10/2018						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic						
DRILLER J. Cain			START DATE 04/26/18			COMP. DATE 04/26/18			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
780															
775	775.2	0.0	WOH	WOH	2									775.2	GROUND SURFACE 0.0
770	771.7	3.5	3	4	7									772.2	RESIDUAL Very Soft, Black-Brown-Orange, Fine Sandy CLAY (A-6) 3.0
	769.2	6.0	8	12	18									769.2	Stiff, Orange, Silty CLAY (A-7-5) 6.0
	766.7	8.5	6	8	9									767.2	Very Stiff, Orange, Fine Sandy SILT (A-4), with trace mica 8.0
765															
760	761.7	13.5	6	8	9										
	756.7	18.5	6	7	7										
755															
750	751.7	23.5	18	31	26										
	746.7	28.5	25	30	70/0.3										
745	744.8	30.4	60/0.0											746.2	WEATHERED ROCK 29.0
														744.8	Green-Gray, (METAMORPHOSED GRANITIC ROCK) 30.4
						</									

GEOTECHNICAL BORING REPORT




CORE LOG

NCDOT CORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC DOT.GDT 5/4/18

WBS 34802.1.1				TIP U-2412A				COUNTY GUILFORD				GEOLOGIST M. Ellis										
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary												GROUND WTR (ft)										
BORING NO. B1-B (RL)				STATION 90+89				OFFSET 54 ft RT				ALIGNMENT -L-				0 HR. N/A						
COLLAR ELEV. 775.8 ft				TOTAL DEPTH 50.4 ft				NORTHING 814,574				EASTING 1,719,623				24 HR. 12.3						
DRILL RIG/HAMMER EFF./DATE HPC2473 CME-550 85% 01/10/2018								DRILL METHOD SPT Core Boring				HAMMER TYPE Automatic										
DRILLER J. Cain				START DATE 04/25/18				COMP. DATE 04/26/18				SURFACE WATER DEPTH N/A										
CORE SIZE NQ2				TOTAL RUN 22.9 ft																		
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) % ROD (ft) %		SAMP. NO.	STRATA REC. (ft) % ROD (ft) %		L O G	DESCRIPTION AND REMARKS											
											ELEV. (ft)	DEPTH (ft)										
748.31												Begin Coring @ 27.5 ft										
	748.3	27.5	2.9	1:38/0.9 1:50/1.0 2:16/1.0	(2.9) 100%	(2.2) 76%		(22.8) 100%	(20.4) 89%		748.3	CRYSTALLINE ROCK 27.5										
745	745.4	30.4										Very Slightly Weathered to Fresh, Blue-Gray-Green, Moderately Hard to Very Hard, (METAMORPHOSED GRANITIC ROCK), with Very Close to Wide Fracture Spacing										
			5.0	1:51/1.0 1:49/1.0 2:01/1.0 1:51/1.0 3:30/1.0	(5.0) 100%	(3.8) 76%						RS-10: 35.4' - 35.9' Unit Weight: 175.1 pcf Unconfined Compressive Strength: 10,810 psi (1557 ksf)										
740	740.4	35.4	5.0	3:48/1.0 3:43/1.0 3:06/1.0 2:06/1.0 2:18/1.0	(5.0) 100%	(5.0) 100%	RS-10					GSI = 70 to 75										
			5.0	2:21/1.0 2:17/1.0 2:06/1.0 2:03/1.0 2:07/1.0	(5.0) 100%	(4.8) 96%																
735	735.4	40.4																				
			5.0	2:28/1.0 4:57/1.0 6:30/1.0 6:28/1.0 5:06/1.0	(4.9) 98%	(4.6) 92%																
730	730.4	45.4																				
			5.0																			
	725.4	50.4									725.4	Boring Terminated at Elevation 725.4 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK) 50.4										



Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Tributary to Deep River
ECS Southeast Project No. 08: 12612
WBS: 34802.1.1 Tip No.: U-2412A
Rock Core Photographs: Boring - B1-B (RL)
Station: 90+89 Offset: 54' RT



GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST M. Ellis						
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary									GROUND WTR (ft)						
BORING NO. B2-A (RL)			STATION 92+11			OFFSET 19 ft RT			ALIGNMENT -L-						
COLLAR ELEV. 762.8 ft			TOTAL DEPTH 55.5 ft			NORTHING 814,596			EASTING 1,719,749						
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017						DRILL METHOD SPT Core Boring			HAMMER TYPE Automatic						
DRILLER B. Snow			START DATE 02/01/18			COMP. DATE 02/01/18			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
765															
	762.8	0.0	2	2	3									762.8	GROUND SURFACE 0.0
760														760.3	RESIDUAL Medium Stiff, Brown, Fine Sandy CLAY (A-6) 2.5
	759.3	3.5	6	8	9										Stiff to Very Stiff, Tan-Orange-Gray, Fine Sandy SILT (A-4) with trace clay
	756.8	6.0	6	5	6										
755															
	754.3	8.5	6	7	13										
750														750.8	12.0
	749.3	13.5	5	6	7										Stiff, Tan-Orange-Brown-Gray, Clayey SILT (A-5)
														747.8	15.0
745															Hard, Brown-Gray, Fine to Coarse Sandy SILT (A-4) with trace mica
	744.3	18.5	12	14	19										
740														739.4	23.4
	739.4	23.4	60/0.0												CRYSTALLINE ROCK
															Very Slightly to Moderately Weathered, Moderately Hard to Hard, Gray-Green, (METAVOLCANIC ROCK), with Very Close to Close Fracture Spacing
735														733.2	29.6
															REC = 94%, RQD = 52%, GSI = 40 - 45
															Very Slightly to Freshly Weathered, Moderately Hard to Hard, Gray-Blue, (METAMORPHOSED GRANITIC ROCK), with Very Close to Moderately Close Fracture Spacing
730															
725														724.7	38.1
														723.5	39.3
															WEATHERED ROCK Green-Gray (PHYLLITE) REC = 25%
720											RS-2				NON-CRYSTALLINE ROCK
														717.3	45.5
															Very Slightly to Moderately Weathered, Moderately Hard, Green-Gray, (PHYLLITE), with Very Close to Close Fracture Spacing
															REC = 97%, RQD = 29%, GSI = 25 - 30
															CRYSTALLINE ROCK
															Very Slightly Weathered, Moderately Hard to Hard, Gray-Green-Blue, (METAMORPHOSED GRANITIC ROCK), with Very Close to Close Fracture Spacing
710														707.3	55.5
															REC = 90%, RQD = 69%, GSI = 50 - 55
															Boring Terminated at Elevation 707.3 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)

NCDOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT.GDT 5/3/18

GEOTECHNICAL BORING REPORT
CORE LOG





SHEET 34

WBS 34802.1.1					TIP U-2412A			COUNTY GUILFORD			GEOLOGIST M. Ellis				
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary											GROUND WTR (ft)				
BORING NO. B2-A (RL)					STATION 92+11			OFFSET 19 ft RT			ALIGNMENT -L-		0 HR. N/A		
COLLAR ELEV. 762.8 ft					TOTAL DEPTH 55.5 ft			NORTHING 814,596			EASTING 1,719,749		24 HR. 43.0		
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017								DRILL METHOD SPT Core Boring				HAMMER TYPE Automatic			
DRILLER B. Snow					START DATE 02/01/18			COMP. DATE 02/01/18			SURFACE WATER DEPTH N/A				
CORE SIZE NQ2					TOTAL RUN 32.1 ft										
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) % RQD (ft) %		SAMP. NO.	STRATA REC. (ft) % RQD (ft) %		L O G	DESCRIPTION AND REMARKS		DEPTH (ft)		
739.37											Begin Coring @ 23.4 ft				
735	739.4	23.4	2.1	N=60/0.0	(2.0)	(1.7)	RS-2	(5.8)	(3.2)		739.4	CRYSTALLINE ROCK		23.4	
	737.3	25.5		3:34/1.0	95%	81%						Very Slightly to Moderately Weathered, Moderately Hard to Hard, Gray-Green, (METAVOLCANIC ROCK), with Very Close to Close Fracture Spacing			
			5.0	4:49/1.0	(5.0)	(1.8)									
730				0:19/0.1								733.2	GSI = 40 - 45		29.6
				3:23/1.0	100%	36%							Very Slightly to Freshly Weathered, Moderately Hard to Hard, Gray-Blue, (METAMORPHOSED GRANITIC ROCK), with Very Close to Moderately Close Fracture Spacing		
	732.3	30.5		3:13/1.0				(8.3)	(5.8)				GSI = 50 - 55		
725				3:59/1.0									Very Slightly to Freshly Weathered, Moderately Hard to Hard, Gray-Blue, (METAMORPHOSED GRANITIC ROCK), with Very Close to Moderately Close Fracture Spacing		
				3:23/1.0											
				3:52/1.0	(4.9)	(3.6)									
720				4:08/1.0	98%	72%						724.7			38.1
	727.3	35.5		4:57/1.0											
				6:31/1.0	80%	40%		(0.3)	(0.0)			723.5	WEATHERED ROCK Green-Gray (PHYLLITE)		39.3
715				1:44/1.0											
				1:48/1.0											
				1:44/1.0			(6.0)	(1.8)			NON-CRYSTALLINE ROCK				
710				2:04/1.0	(4.5)	(1.7)					Very Slightly to Moderately Weathered, Moderately Hard, Green-Gray, (PHYLLITE), with Very Close to Close Fracture Spacing				
	717.3	45.5		1:24/1.0	90%	34%				717.3	RS-2: 41.3' - 41.7' Unit Weight: 166.0 pcf Unconfined Compressive Strength: 720 psi (104 ksf)		45.5		
				2:34/1.0											
710				1:49/1.0											
				1:02/1.0											
				1:30/1.0	(4.0)	(3.1)	(9.0)	(6.9)			CRYSTALLINE ROCK				
710				2:08/1.0	80%	62%					Very Slightly Weathered, Moderately Hard to Hard, Gray-Green-Blue, (METAMORPHOSED GRANITIC ROCK), with Very Close to Close Fracture Spacing				
	712.3	50.5		2:02/1.0											
				2:17/1.0											
710				3:21/1.0											
				1:59/1.0	(5.0)	(3.8)									
				2:01/1.0	100%	76%									
710				2:28/1.0											
				1:46/1.0											
	707.3	55.5		2:22/1.0						707.3	GSI = 50 - 55		55.5		
											Boring Terminated at Elevation 707.3 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)				


NCDOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT.GDT 5/3/18



Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Tributary to Deep River
ECS Southeast Project No. 08: 12612
WBS: 34802.1.1 Tip No.: U-2412A
Rock Core Photographs: Boring - B2-A (RL)
Station: 92+11 Offset: 19' RT



GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1		TIP U-2412A		COUNTY GUILFORD		GEOLOGIST M. Ellis								
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary							GROUND WTR (ft)							
BORING NO. B2-B (RL)		STATION 91+97		OFFSET 55 ft RT		ALIGNMENT -L-		0 HR. Dry						
COLLAR ELEV. 763.2 ft		TOTAL DEPTH 24.6 ft		NORTHING 814,562		EASTING 1,719,732		24 HR. Dry						
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017				DRILL METHOD H.S Augers			HAMMER TYPE Automatic							
DRILLER B. Snow		START DATE 01/31/18		COMP. DATE 02/01/18		SURFACE WATER DEPTH N/A								
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT				SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft) DEPTH (ft)
765														
	763.2	0.0	1	2	4								763.2	GROUND SURFACE 0.0
760	759.7	3.5	4	5	7						M		RESIDUAL Medium Stiff to Stiff, Red-Brown, Fine Sandy CLAY (A-6) with trace quartz fragments	
	757.2	6.0	8	6	10						M		757.7	Very Stiff to Hard, Red-Tan-Gray, Fine Sandy SILT (A-4) 5.5
755	754.7	8.5	4	6	9						M			
	749.7	13.5	7	16	43						M			
750	744.7	18.5	16	27	73/0.4						M			
													744.2	WEATHERED ROCK Gray-Green (METAMORPHOSED GRANITIC ROCK) 19.0
740	739.7	23.5											738.7	24.5
	738.7	24.5	100/0.3										738.6	24.6
			60/0.1										CRYSTALLINE ROCK (METAMORPHOSED GRANITIC ROCK)	
													Boring Terminated with Standard Penetration Test Refusal at Elevation 738.6 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)	
													Notes: Surficial Organic Soils from 0.0 to 0.2 ft.	

WBS 34802.1.1		TIP U-2412A		COUNTY GUILFORD		GEOLOGIST K. Plummer								
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary							GROUND WTR (ft)							
BORING NO. B3-A (RL)		STATION 93+19		OFFSET 19 ft RT		ALIGNMENT -L-		0 HR. N/A						
COLLAR ELEV. 748.4 ft		TOTAL DEPTH 19.6 ft		NORTHING 814,589		EASTING 1,719,858		24 HR. Dry						
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017				DRILL METHOD H.S. Augers			HAMMER TYPE Automatic							
DRILLER B. Snow			START DATE 01/24/18		COMP. DATE 01/24/18		SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT				SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
750														
	748.4	0.0	WOH	7	7									748.4 GROUND SURFACE 0.0
745	744.9	3.5										M		745.9 RESIDUAL Stiff, Red-Brown, Clayey SILT (A-5) 2.5
	742.4	6.0	4	5	10							M		Medium Dense, Tan, Silty Fine SAND (A-2-4) with trace clay
740	739.9	8.5	5	7	9							M		
			5	5	6							M		
735	734.9	13.5	3	8	20							M		
730	729.9	18.5												729.9 18.5
	728.9	19.5	50	50/0.1										728.9 19.5
			60/0.1											728.8 WEATHERED ROCK Brown (METAPHOSED GRANITIC ROCK) 19.6
														CRYSTALLINE ROCK METAPHOSED GRANITIC ROCK
														Boring Terminated with Standard Penetration Test Refusal at Elevation 728.8 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)
														Notes: Surficial Organics Soils from 0.0 to 0.4 ft.


NCDOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT.GDT 5/3/18

GEOTECHNICAL BORING REPORT

CORE LOG

NCDOT CORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC DOT.GDT 5/3/18

WBS 34802.1.1				TIP U-2412A				COUNTY GUILFORD				GEOLOGIST M. Ellis					
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary												GROUND WTR (ft)					
BORING NO. B3-B (RL)				STATION 93+03				OFFSET 55 ft RT				ALIGNMENT -L-				0 HR. N/A	
COLLAR ELEV. 754.9 ft				TOTAL DEPTH 35.0 ft				NORTHING 814,554				EASTING 1,719,840				24 HR. 23.0	
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017								DRILL METHOD SPT Core Boring				HAMMER TYPE Automatic					
DRILLER B. Snow				START DATE 01/29/18				COMP. DATE 01/30/18				SURFACE WATER DEPTH N/A					
CORE SIZE NQ2				TOTAL RUN 23.6 ft													
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) % ROD (ft) %		SAMP. NO.	STRATA REC. (ft) % ROD (ft) %		L O G	DESCRIPTION AND REMARKS ELEV. (ft) DEPTH (ft)						
743.54											Begin Coring @ 11.4 ft						
	743.5	11.4	4.8	N=60/0.0 2:48/1.0 2:33/1.0 1:38/1.0 1:49/1.0 0:52/0.8	(4.0) 83%	(2.0) 42%		(22.2) 94%	(19.6) 83%		743.5	CRYSTALLINE ROCK		11.4			
740											Fresh to Very Slightly Weathered, Moderately Hard to Very Hard, Gray-White, (METAMORPHOSED GRANITIC ROCK), with Very Close to Wide Fracture Spacing						
	738.7	16.2									RS-4: 26.2' - 26.6' Unit Weight: 175.5 psi Unconfined Compressive Strength: 6,130 psi (883 ksf)						
735			5.0	1:32/1.0 1:48/1.0 1:30/1.0 1:50/1.0 1:32/1.0	(4.7) 94%	(4.5) 90%					GSI = 65 - 70						
	733.7	21.2															
			5.0	1:55/1.0 2:01/1.0 1:44/1.0 1:53/1.0 1:48/1.0	(4.8) 96%	(4.6) 92%											
730																	
	728.7	26.2					RS-4										
			5.0	2:24/1.0 2:00/1.0 2:17/1.0 2:37/1.0 2:29/1.0	(4.9) 98%	(4.7) 94%											
725																	
	723.7	31.2															
			3.8	2:28/1.0 1:46/1.0 2:10/1.0 2:23/0.8	(3.8) 100%	(3.8) 100%											
720	719.9	35.0								719.9	Boring Terminated at Elevation 719.9 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)		35.0				
Notes: Surficial Organic Soils from 0.0 to 0.2 ft.																	



Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Tributary to Deep River

ECS Southeast Project No. 08: 12612

WBS: 34802.1.1 Tip No.: U-2412A

Rock Core Photographs: Boring - B3-B (RL)

Station: 93+03 Offset: 55' RT

Begin Run 1
11.4'



Begin Run 2
16.2'

0.0 0.2 0.4 0.6 0.8 1.0 1.2 1.4 1.6 1.8 2.0

SCALE IN FEET

Begin Run 3
21.2'

Begin Run 4
26.2' ft



0.0 0.2 0.4 0.6 0.8 1.0 1.2 1.4 1.6 1.8 2.0

SCALE IN FEET

Begin Run 5
31.2'



End Run 5
35.0'

0.0 0.2 0.4 0.6 0.8 1.0 1.2 1.4 1.6 1.8 2.0

SCALE IN FEET

GEOTECHNICAL BORING REPORT


BORE LOG

[illegible]



GEOTECHNICAL BORING REPORT

CORE LOG


WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST K. Plummer		
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary									GROUND WTR (ft)		
BORING NO. B4-A (RL)			STATION 94+27			OFFSET 19 ft RT			ALIGNMENT -L-		0 HR. N/A
COLLAR ELEV. 734.9 ft			TOTAL DEPTH 37.5 ft			NORTHING 814,586			EASTING 1,719,966		24 HR. 3.8
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017						DRILL METHOD SPT Core Boring			HAMMER TYPE Automatic		
DRILLER B. Snow			START DATE 01/16/18			COMP. DATE 01/19/18			SURFACE WATER DEPTH N/A		
CORE SIZE NQ2			TOTAL RUN 27.4 ft								
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) %	RUN ROD (ft) %	SAMP. NO.	STRATA REC. (ft) %	STRATA ROD (ft) %	L O G	DESCRIPTION AND REMARKS
											ELEV. (ft) DEPTH (ft)
725	725.0	9.9	1.0	2:45/1.0	(0.5)	(0.0)		(2.5)	(0.5)		Begin Coring @ 9.9 ft
	724.0	10.9	5.0	2:00/1.0	50%	0%		50%	10%		CRYSTALLINE ROCK
				1:20/1.0	(2.0)	(0.5)					Severely to Slightly Weathered, Medium Hard to Hard, Gray, (METAMORPHOSED GRANITIC ROCK), with Very Close Fracture Spacing
720				1:20/1.0	40%	10%					
	719.0	15.9		1:20/1.0				(0.0)	(0.0)		GSI = 20 - 25
	718.8	16.1	4.4	0:20/0.2	(4.4)	(3.5)		0%	0%		720.0 14.9
				1:45/0.4	100%	80%		(21.4)	(20.0)		718.8 16.1
				1:20/1.0				100%	93%		WEATHERED ROCK
715				1:20/1.0							Gray (METAMORPHOSED GRANITIC ROCK)
	714.4	20.5		1:00/1.0							CRYSTALLINE ROCK
				1:30/1.0							Fresh to Slightly Weathered, Hard to Very Hard, Gray-White, (METAMORPHOSED GRANITIC ROCK) with Close to Moderately Close Fracture Spacing
			5.0	1:40/1.0	(5.0)	(5.0)					RS-6: 25.5' - 25.9'
				2:00/1.0	100%	100%					Unit Weight: 166.6 pcf
710				2:10/1.0							Unconfined Compressive Strength: 7,890 psi (1,136 ksf)
	709.4	25.5		3:30/1.0							GSI = 75 - 80
				4:00/1.0							
			5.0	5:00/1.0	(5.0)	(4.7)	RS-6				
				4:30/1.0	100%	94%					
705				5:10/1.0							
	704.4	30.5		7:00/1.0							
				10:15/1.0							
			5.0	7:40/1.0	(5.0)	(4.8)					
				6:00/1.0	100%	96%					
700				5:20/1.0							
	699.4	35.5		8:05/1.0							
				7:45/1.0							
	697.4	37.5	2.0	5:45/1.0	(2.0)	(2.0)					697.4 37.5
				15:40/1.0	100%	100%					Boring Terminated at Elevation 697.4 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)
											Notes: Possible Boulders at a depth of 5.6 to 7.5 ft

**Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Tributary to Deep River****ECS Southeast Project No. 08:12612****WBS: 34802.1.1 Tip No.: U-2412A****Rock Core Photographs: Boring - B4-A (RL)****Station: 94+27 Offset: 19' RT****Begin Run 1
9.9'**



SCALE IN FEET

**Begin Run 2
10.9'****End Run 2
15.9'****Begin Run 5
25.5'**

SCALE IN FEET

**Begin Run 6
30.5'****Begin Run 3
16.1'****Begin Run 4
20.5'**

SCALE IN FEET

**Begin Run 7
35.5'****End Run 7
37.5'**

SCALE IN FEET

NC DOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT.GDT 5/3/18


WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST K. Plummer					
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary									GROUND WTR (ft)					
BORING NO. B5-A (RL)			STATION 95+37			OFFSET 19 ft RT			ALIGNMENT -L-			0 HR. 6.5		
COLLAR ELEV. 733.0 ft			TOTAL DEPTH 8.0 ft			NORTHING 814,587			EASTING 1,720,077			24 HR. 2.5		
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER B. Snow			START DATE 01/22/18			COMP. DATE 01/22/18			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
735														
730	733.0	0.0	1	1	2							M		733.0 GROUND SURFACE 0.0
	729.5	3.5	1	2	2							W		727.5
	727.0	6.0	31	25	47							M		725.1
725	725.1	7.9	60/0.1											725.0
Notes: Surficial Organics Soils from 0.0 to 0.3 ft.														

GEOTECHNICAL BORING REPORT

CORE LOG

NCDOT CORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC DOT.GDT 5/3/18

WBS 34802.1.1				TIP U-2412A				COUNTY GUILFORD				GEOLOGIST K. Plummer					
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary												GROUND WTR (ft)					
BORING NO. B5-B (RL)				STATION 95+17				OFFSET 55 ft RT				ALIGNMENT -L-		0 HR. N/A			
COLLAR ELEV. 734.1 ft				TOTAL DEPTH 30.4 ft				NORTHING 814,550				EASTING 1,720,058		24 HR. 4.0			
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017								DRILL METHOD SPT Core Boring				HAMMER TYPE Automatic					
DRILLER B. Snow				START DATE 01/22/18				COMP. DATE 01/23/18				SURFACE WATER DEPTH N/A					
CORE SIZE NQ2				TOTAL RUN 25.0 ft													
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) %		ROD (ft) %	SAMP. NO.	STRATA REC. (ft) %		ROD (ft) %	L O G	DESCRIPTION AND REMARKS		DEPTH (ft)		
728.73													Begin Coring @ 5.4 ft				
725	728.7	5.4	0.4	N=60/0.0	(0.4)	(0.3)			(25.0)	(24.4)			728.7	CRYSTALLINE ROCK Freshly Weathered, Hard, Gray, (METAMORPHOSED GRANITIC ROCK), with Close Fracture Spacing RS-8: 25.8' - 26.2' Unit Weight: 169.4 psi Unconfined Compressive Strength: 5,210 psi (750 ksf) GSI = 80 - 85	5.4		
	728.3	5.8	5.0	2:00/0.4	100%	75%			100%	98%							
				2:30/1.0	(5.0)	(5.0)											
720	723.3	10.8	5.0	1:30/1.0	(5.0)	(5.0)											
				2:15/1.0	100%	100%											
				2:30/1.0	(5.0)	(4.7)											
715				2:30/1.0	100%	94%											
	718.3	15.8	5.0	3:30/1.0	(5.0)	(5.0)											
				4:15/1.0	100%	100%											
710				4:00/1.0	(5.0)	(5.0)											
	713.3	20.8	5.0	6:45/1.0	(5.0)	(5.0)											
				3:30/1.0	100%	100%											
705				4:45/1.0	(5.0)	(4.9)											
	708.3	25.8	4.6	5:00/1.0	(5.0)	(4.9)											
				5:15/1.0	(5.0)	(4.9)											
	703.7	30.4		5:30/1.0	(4.6)	(4.5)	RS-8						703.7		30.4		
				10:00/1.0	100%	98%							Boring Terminated at Elevation 703.7 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)				
				15:30/1.0	(4.6)	(4.5)							Notes: Surficial Organics Soils from 0.0 to 0.3 ft.				
				20:45/0.6	(4.6)	(4.5)											



Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Tributary to Deep River


ECS Southeast Project No. 08:12612

WBS: 34802.1.1 Tip No. : U-2412A

Rock Core Photographs: Boring - B5-B (RL)

Station: 95+17 Offset: 55' RT



Begin Run 1
5.4'



Begin Run 2
5.8'

Begin Run 5
20.8'


Begin Run 6
25.8'



End Run 6
30.4'

Begin Run 3
10.8'

Begin Run 4
15.8'



GEOTECHNICAL BORING REPORT
 BORE LOG

WBS 34802.1.1				TIP U-2412A				COUNTY GUILFORD				GEOLOGIST S. Carpenter					
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary												GROUND WTR (ft)					
BORING NO. EB2-A (RL)				STATION 96+46				OFFSET 19 ft RT				ALIGNMENT -L-				0 HR. Dry	
COLLAR ELEV. 752.3 ft				TOTAL DEPTH 13.6 ft				NORTHING 814,591				EASTING 1,720,187				24 HR. Dry	
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017								DRILL METHOD H.S. Augers				HAMMER TYPE Automatic					
DRILLER B. Snow				START DATE 01/21/18				COMP. DATE 01/21/18				SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)		
755																	
	752.3	0.0												752.3	GROUND SURFACE 0.0		
750			1	1	1							M		RESIDUAL Soft to Hard, Red-Brown-Tan, Fine to Coarse Sandy SILT (A-4)			
	748.8	3.5	19	23	27							M					
	746.3	6.0	10	26	36							M					
745														743.8	8.5		
	743.8	8.5	100/0.3												WEATHERED ROCK Tan-Brown (METAMORPHOSED GRANITIC ROCK)		
740														738.8	13.5		
	738.8	13.5	60/0.1											738.7	13.6		
															CRYSTALLINE ROCK Tan-Brown (METAMORPHOSED GRANITIC ROCK) Boring Terminated with Standard Penetration Test Refusal at Elevation 738.7 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)		

WBS 34802.1.1			TIP U-2412A			COUNTY GUILFORD			GEOLOGIST S. Carpenter				
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary									GROUND WTR (ft)				
BORING NO. EB2-B (RL)			STATION 96+27			OFFSET 55 ft RT			ALIGNMENT -L-			0 HR. Dry	
COLLAR ELEV. 751.0 ft			TOTAL DEPTH 14.1 ft			NORTHING 814,554			EASTING 1,720,169			24 HR. Dry	
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic				
DRILLER B. Snow			START DATE 01/21/18			COMP. DATE 01/21/18			SURFACE WATER DEPTH N/A				
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100	MOI		
755													
	751.0	0.0											751.0 GROUND SURFACE 0.0
750			1	1	2						M		
	747.5	3.5	9	15	22						M		748.0 Soft, Tan-Brown, Fine to Coarse Sandy CLAY (A-6) 3.0
745	745.0	6.0											744.5 Hard, Red-Tan-Brown, Fine to Coarse Sandy SILT (A-4) 6.5
	742.5	8.5	30	60	40/0.4								WEATHERED ROCK
740			24	76/0.3									Tan-Brown (METAMORPHOSED GRANITIC ROCK)
	737.5	13.5	88	12/0.1									736.9 Boring Terminated at Elevation 736.9 ft In Weathered Rock (METAMORPHOSED GRANITIC ROCK) 14.1
													Notes: Surficial Organics Soils from 0.0 to 0.2 ft.

ROCK TEST RESULTS							
SAMPLE NO.	BORING	OFFSET	STATION -L-	DEPTH INTERVAL	Rock Type	Unit Weight LB/FT ³	Unconfined Compressive Stregth (PSI/KSF)
RS-9	B1-B (LL)	19' LT	91+15	33.1-33.5	Metamorphosed Granitic Rock	191.0	19,780 psi / 2,848 ksf
RS-10	B1-B (RL)	54' RT	90+89	35.4-35.8	Metamorphosed Granitic Rock	175.1	10,810 psi / 1,557 ksf
RS-1	B2-A (LL)	55' LT	92+40	29.0-29.4	Metamorphosed Granitic Rock	170.9	20,850 psi / 3,002 ksf
RS-2	B2-A (RL)	19' RT	92+11	41.3-41.7	Phyllite	166.0	720 psi / 104 ksf
RS-3	B3-B (LL)	14' LT	93+34	32.6-33.0	Metamorphosed Granitic Rock	166.7	4,140 psi / 596 ksf
RS-4	B3-B (RL)	55' RT	93+03	26.2-26.6	Metamorphosed Granitic Rock	175.4	6,130 psi / 883 ksf
RS-5	B4-A (LL)	55' LT	94+63	24.6-25.0	Metamorphosed Granitic Rock	168.3	11,770 psi / 1,695 ksf
RS-6	B4-A (RL)	19' RT	94+27	25.5-25.9	Metamorphosed Granitic Rock	166.6	7,890 psi / 1,136 ksf
RS-7	B5-B (LL)	19' LT	95+57	17.2-17.6	Metamorphosed Granitic Rock	178.5	8,840 psi / 1,273 ksf
RS-8	B5-B (RL)	55' RT	95+17	25.8-26.2	Metamorphosed Granitic Rock	169.4	5,210 psi / 750 ksf

RS = NQ2 Rock Core Barrel Sample (ASTM D-2113)



LOOKING DOWN STATION (WEST) FROM BENT 1 (LL) TO END BENT 1 (LL & RL)



LOOKING NORTH ALONG BENT 2 FROM (RL) TO (LL) ALONG SEWER EASEMENT



LOOKING DOWN STATION (WEST) FROM BENT 1 (RL) AT ROCK OUTCROP BELOW EB1-A (RL)



LOOKING SOUTH ALONG BENT 4 FROM (LL) TO (RL) AT DEEP RIVER TRIBUTARY

PROJECT: 34802 ID: U-2412A

CONTENTS

SHEET	DESCRIPTION
1	TITLE SHEET
2	LEGEND
3	SITE PLAN
4	PROFILE
5-9	CROSS SECTIONS
10-23	BORE LOGS & CORE REPORTS
24, 25	SOIL TEST RESULTS
26-29	CORE PHOTOGRAPHS
30	SITE PHOTOGRAPH

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

PROJ. REFERENCE NO. 34802.1.1 (U-2412A) F.A. PROJ. STP-4121(1)
COUNTY GUILFORD
PROJECT DESCRIPTION GREENSBORO/HIGH POINT RD. FROM
PROPOSED US 311 BYPASS TO WEST OF ST 1480

SITE DESCRIPTION STRUCTURES NO. 3 & 4 ON -L- (SR 4121,
GREENSBORO/HIGH POINT RD.) OVER DEEP RIVER AT
STATION 140+22

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	U-2412A	1	30

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING, AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 250-4088. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA ARE PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

PERSONNEL

N.D. MOHS

J. HOWARD

MACTEC

INVESTIGATED BY N.D. MOHS

CHECKED BY N.T. ROBERSON


SUBMITTED BY N.T. ROBERSON

DATE MAY 2009

DRAWN BY: N.D. MOHS

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

DocuSigned by:
Neil T. Roberson
4081D9A8C6C649C...
2/19/2018


PROJECT REFERENCE NO.	SHEET NO.
U-2412A	2


SUBSURFACE INVESTIGATION


SOIL DESCRIPTION						
SOIL IS CONSIDERED TO BE THE UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER, AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO STANDARD PENETRATION TEST (AASHTO T206, ASTM D-1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY SHALL INCLUDE: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. EXAMPLE: <i>VERY STIFF, GRAY-SILTY CLAY, MOST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6</i>						
SOIL LEGEND AND AASHTO CLASSIFICATION						
GENERAL CLASS.	GRANULAR MATERIALS (≤ 35% PASSING #200)			SILT-CLAY MATERIALS (> 35% PASSING #200)		ORGANIC MATERIALS
GROUP CLASS.	A-1	A-3	A-2	A-4	A-5	A-7
CLASS.	A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7
SUBGROUP						
% PASSING						
# 10						
# 40						
# 200						
LIQUID LIMIT PLASTIC INDEX						
GROUP INDEX						
USUAL TYPES OF MAJOR MATERIALS						
GEN. RATING AS A SUBGRADE						
PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS > LL - 30						
CONSISTENCY OR DENSENESS						
PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY		RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)		RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/F ²)	
GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE		<4 4 TO 10 10 TO 30 30 TO 50 >50		N/A	
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD		<2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 >30		<0.25 0.25 TO 0.50 0.5 TO 1.0 1 TO 2 2 TO 4 >4	
TEXTURE OR GRAIN SIZE						
U.S. STD. SIEVE SIZE OPENING (MM)						
4 10 40 60 200 270						
4.76 2.00 0.42 0.25 0.075 0.053						
BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F SD.)	SILT (SL.)	CLAY (CL.)
GRAIN SIZE MM IN.	305 12	75 3	2.0	0.25	0.05	0.005
SOIL MOISTURE - CORRELATION OF TERMS						
SOIL MOISTURE SCALE (ATTERBERG LIMITS)		FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION			
LL		- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE			
PLASTIC RANGE (PI)		- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE			
OM		- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE			
SL		- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE			
PLASTICITY						
		PLASTICITY INDEX (PI)	DRY STRENGTH			
NONPLASTIC		0-5	VERY LOW			
LOW PLASTICITY		6-15	SLIGHT			
MED. PLASTICITY		16-25	MEDIUM			
HIGH PLASTICITY		26 OR MORE	HIGH			
COLOR						
DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.						


GRADATION			
WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORM - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. (ALSO POORLY GRADED) GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLES OF TWO OR MORE SIZES.			
ANGULARITY OF GRAINS			
THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS: ANGULAR, SUBANGULAR, SUBROUNDED, OR ROUNDED.			
MINERALOGICAL COMPOSITION			
MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHENEVER THEY ARE CONSIDERED OF SIGNIFICANCE.			
COMPRESSIBILITY			
SLIGHTLY COMPRESSIBLE		LIQUID LIMIT LESS THAN 31	
MODERATELY COMPRESSIBLE		LIQUID LIMIT EQUAL TO 31-50	
HIGHLY COMPRESSIBLE		LIQUID LIMIT GREATER THAN 50	
PERCENTAGE OF MATERIAL			
ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME
HIGHLY ORGANIC	>10%	>20%	HIGHLY
GROUND WATER			
	WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING		
	STATIC WATER LEVEL AFTER 24 HOURS		
	PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA		
	SPRING OR SEEP		
MISCELLANEOUS SYMBOLS			
	ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION		
	SOIL SYMBOL		
	ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT		
	INFERRED SOIL BOUNDARY		
	INFERRED ROCK LINE		
	ALLUVIAL SOIL BOUNDARY		
	DIP & DIP DIRECTION OF ROCK STRUCTURES		
	SOUNDING ROD		
	TEST BORING		
	AUGER BORING		
	CORE BORING		
	MONITORING WELL		
	PIEZOMETER INSTALLATION		
	SLOPE INDICATOR INSTALLATION		
	SPT N-VALUE		
	SPT REFUSAL		
ABBREVIATIONS			
AR - AUGER REFUSAL	HL - HIGHLY MED., - MEDIUM	m - MOISTURE CONTENT	v - VERY
BT - BORING TERMINATED	MICA - MICACEOUS	VST - VANE SHEAR TEST	WEA. - WEATHERED
CL - CLAY	MOD. - MODERATELY NP - NON PLASTIC	γ - UNIT WEIGHT	γd - DRY UNIT WEIGHT
CPT - CONE PENETRATION TEST	ORG. - ORGANIC		
CSE. - COARSE	PMT - PRESSUREMETER TEST		
DMT - DILATOMETER TEST	SAP. - SAPROLITE		
DPT - DYNAMIC PENETRATION TEST	SD. - SAND, SANDY		
e - VOID RATIO	SL. - SILT, SILTY		
F - FINE	SLI. - SLIGHTLY		
FOSS. - FOSSILIFEROUS	TCR - TRICONE REFUSAL		
FRAC. - FRACTURED, FRACTURES			
FRAGS. - FRAGMENTS			
EQUIPMENT USED ON SUBJECT PROJECT			
DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:	
☐ MOBILE B- ____	☐ CLAY BITS	☒ AUTOMATIC ☐ MANUAL	
☐ BK-51	☐ 6" CONTINUOUS FLIGHT AUGER		
☐ CME-45C	☒ 8" HOLLOW AUGERS	CORE SIZE:	
	☒ HARD FACED FINGER BITS	☐ -B ____	
☒ CME-55	☐ TUNG.-CARBIDE INSERTS	☒ -NO ____	
	☒ CASING ☐ W/ ADVANCER	☐ -H ____	
☐ PORTABLE HOIST	☒ TRICONE 2 5/8 " STEEL TEETH	HAND TOOLS:	

SKEW ANGLE = 40°









GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1				TIP U-2412A				COUNTY Guilford				GEOLOGIST Howard, J.					
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22												GROUND WTR (ft)					
BORING NO. EB1-A				STATION 137+56				OFFSET 52 ft LT				ALIGNMENT -L-				0 HR. 10.1	
COLLAR ELEV. 720.2 ft				TOTAL DEPTH 13.7 ft				NORTHING 815,257				EASTING 1,724,189				24 HR. 3.3	
DRILL RIG/HAMMER EFF./DATE CME-45C								DRILL METHOD H.S. Augers				HAMMER TYPE Automatic					
DRILLER Contract Driller				START DATE 03/30/09				COMP. DATE 03/30/09				SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)		
725																	
720	720.2	0.0												720.2	GROUND SURFACE 0.0		
715	716.7	3.5	1	1	2						SS-1	M		718.2	ALLUVIAL Brown, Sandy Clay 2.0		
															Red-Brown, Sandy Silt		
710	711.7	8.5	1	WOH	1						SS-2	M		713.2	RESIDUAL Brown and Gray, Sandy Clay 7.0		
	706.7	13.5	5	8	10						SS-3	M					
	706.5	13.7	100/0.2											707.2	WEATHERED ROCK (Diabase) 13.0		
			60/0.0											706.5	13.7 Boring Terminated with Standard Penetration Test Refusal at Elevation 706.5 ft On Crystalline Rock (Diabase)		

WBS 34802.1.1				TIP U-2412A		COUNTY Guilford		GEOLOGIST Howard, J.						
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22										GROUND WTR (ft)				
BORING NO. EB1-B			STATION 138+86			OFFSET 47 ft RT			ALIGNMENT -L-		0 HR. 2.5			
COLLAR ELEV. 718.0 ft			TOTAL DEPTH 19.1 ft			NORTHING 815,209			EASTING 1,724,345		24 HR. 3.0			
DRILL RIG/HAMMER EFF./DATE CME-45C						DRILL METHOD H.S. Augers				HAMMER TYPE Automatic				
DRILLER Contract Driller			START DATE 03/31/09			COMP. DATE 03/31/09			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
720														
715	718.0	0.0	WOH	1	2						SS-1	M		718.0 GROUND SURFACE 0.0
	714.5	3.5	WOH	1	2						SS-2	W		715.0 ALLUVIAL Brown, Sandy Silt 3.0
710														
	709.5	8.5		9	19	19						SS-3	M	
705														
	704.5	13.5		16	19	17						SS-4	M	
700														
	699.5	18.5												
	699.2	18.8												
	698.9	19.1												

NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Mohs, N. D.							
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22									GROUND WTR (ft)							
BORING NO. EB1-C			STATION 138+00			OFFSET 20 ft LT			ALIGNMENT -L-			0 HR. 15.5				
COLLAR ELEV. 718.3 ft			TOTAL DEPTH 18.6 ft			NORTHING 815,243			EASTING 1,724,241			24 HR. 6.5				
DRILL RIG/HAMMER EFF./DATE CME-45C						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic							
DRILLER Contract Driller			START DATE 09/04/08			COMP. DATE 09/04/08			SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)	
720																
														718.3	GROUND SURFACE	0.0
715	714.8	3.5												715.3	ALLUVIAL Brown, Sandy Silt	3.0
			6	8	10									RESIDUAL Brown and Orange, Sandy Clay		
710	709.8	8.5									SS-16	M				
			7	12	17							M				
705	704.8	13.5														
			8	19	47											
700	699.8	18.5												701.8	WEATHERED ROCK (Granite)	16.5
			60/0.1											700.3	CRYSTALLINE ROCK (Granite)	18.0
														699.7	CRYSTALLINE ROCK (Granite)	18.6
														Boring Terminated with Standard Penetration Test Refusal at Elevation 699.7 ft In Crystalline Rock (Granite)		

WBS 34802.1.1				TIP U-2412A		COUNTY Guilford		GEOLOGIST Howard, J.						
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22										GROUND WTR (ft)				
BORING NO. EB1-D		STATION 138+43		OFFSET 17 ft RT		ALIGNMENT -L-		0 HR.		2.1				
COLLAR ELEV. 719.0 ft		TOTAL DEPTH 21.9 ft		NORTHING 815,223		EASTING 1,724,294		24 HR.		2.0				
DRILL RIG/HAMMER EFF./DATE CME-45C						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER Contract Driller			START DATE 03/31/09		COMP. DATE 03/31/09		SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
720														
	719.0	0.0	1	1	2	3	...	...	...	...	SS-1	M	719.0	GROUND SURFACE 0.0
						4	...	...	...	...				
715	714.7	4.3	2	2	3	5	...	...	...	...	SS-2	M	715.0	ALLUVIAL Brown, Sandy Silt 4.0
						6	...	...	...	...				
710	709.4	9.6	6	9	91/0.2	...	...	...	...	...	SS-3	M	708.9	Red-Brown, Silty Sand 10.1
						...	...	...	...	100/0.7				
705	704.6	14.4	8	10	90/0.4	...	...	...	...	...	SS-4		706.0	WEATHERED ROCK (Granite) 13.0
						...	...	...	...	100/0.9			704.1	RESIDUAL Tan and Orange, Sandy Clay 14.9
						...	...	...	...	...				
700	700.1	18.9	22	38	62/0.2	...	...	...	...	...			700.1	WEATHERED ROCK (Granite) 18.9
						...	...	...	...	100/0.7				
	697.2	21.8	60/0.1			...	...	...	...	60/0.1			697.2	(Diabase) 18.9
													697.1	CRSTALLINE ROCK (Diabase) 21.8
														21.9
														Boring Terminated with Standard Penetration Test Refusal at Elevation 697.1 ft In Crystalline Rock (Diabase)

NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Howard, J.					
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22									GROUND WTR (ft)					
BORING NO. B1-A			STATION 138+40			OFFSET 51 ft LT			ALIGNMENT -L-			0 HR. 0.8		
COLLAR ELEV. 717.1 ft			TOTAL DEPTH 35.6 ft			NORTHING 815,286			EASTING 1,724,268			24 HR. 0.6		
DRILL RIG/HAMMER EFF./DATE CME-45C						DRILL METHOD NW Casing W/SPT & Core			HAMMER TYPE Automatic					
DRILLER Contract Driller			START DATE 04/01/09			COMP. DATE 04/01/09			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft)	DEPTH (ft)
720														
	717.1	0.0											717.1	GROUND SURFACE 0.0
715			WOH	1	2						SS-1	M		ALLUVIAL Brown, Silty Sand
	713.2	3.9												
710			WOH	WOH	WOH						SS-2	W		
	709.2	7.9											710.9	Red, Brown, and Black, Sandy Silt 6.2
705			1	1	2						SS-3	W		
	704.2	12.9											706.1	Tan, Coarse Sand and Gravel 11.0
	703.0	14.1	7	93/0.4							SS-4	W	703.7	
700			60/0.0								RS-1		703.0	WEATHERED ROCK (Granite) 13.4
695											RS-2		696.7	CRYSTALLINE ROCK Black and White, Fresh to Slightly Weathered, Hard, Close to Moderately Close Fracture Spacing, Granite REC=83% RQD=67% 20.4
													695.6	Blue-Gray, Very Slightly to Severely Weathered, Moderately Hard to Soft, Close Fracture Spacing, 2 Fractures at 40°, 3 at 10°, Diabase REC=100% RQD=0% 21.5
690														
685													681.7	Black and White, Fresh to Moderately Weathered, Hard to Moderately Hard, Close to Moderately Close Fracture Spacing, 4 Fractures at 80°, Granite REC=92% RQD=81% 35.4
													681.5	Blue-Gray, Very Slightly Weathered, Moderately Hard, Close Fracture Spacing, Diabase REC=100% RQD=0% 35.6
														Boring Terminated at Elevation 681.5 ft In Crystalline Rock (Diabase)


NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT
CORE LOG

WBS 34802.1.1				TIP U-2412A				COUNTY Guilford				GEOLOGIST Howard, J.											
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22												GROUND WTR (ft)											
BORING NO. B1-A				STATION 138+40				OFFSET 51 ft LT				ALIGNMENT -L-				0 HR. 0.8							
COLLAR ELEV. 717.1 ft				TOTAL DEPTH 35.6 ft				NORTHING 815,286				EASTING 1,724,268				24 HR. 0.6							
DRILL RIG/HAMMER EFF./DATE CME-45C								DRILL METHOD NW Casing W/SPT & Core				HAMMER TYPE Automatic											
DRILLER Contract Driller				START DATE 04/01/09				COMP. DATE 04/01/09				SURFACE WATER DEPTH N/A											
CORE SIZE NQ				TOTAL RUN 21.5 ft																			
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) % ROD (ft) %		SAMP. NO.	STRATA REC. (ft) % ROD (ft) %		L O G	DESCRIPTION AND REMARKS ELEV. (ft) DEPTH (ft)												
703	703.0	14.1	1.5	N=60/0.0 2:30/1.0 45/0.5	(1.5) 100%	(1.3) 87%	RS-1	(5.2) 83%	(4.2) 67%		703.0	Begin Coring @ 14.1 ft											
700	701.5	15.6	5.0	1:15/1.0 1:30/1.0 1:45/1.0 2:00/1.0 1:00/1.0	(3.9) 78%	(2.9) 58%						CRYSTALLINE ROCK 14.1											
												Black and White, Fresh to Slightly Weathered, Hard, Close to Moderately Close Fracture Spacing, Granite											
695	696.5	20.6	5.0	2:30/1.0 1:15/1.0 1:45/1.0 1:30/1.0 1:00/1.0	(4.4) 88%	(3.0) 60%	RS-2	(1.1) 100%	(0.0) 0%		696.7	Blue-Gray, Very Slightly to Severely Weathered, Moderately Hard to Soft, Close Fracture Spacing, 2 Fractures at 40°, 3 at 10°, Diabase 20.4											
											695.6	Black and White, Fresh to Moderately Weathered, Hard to Moderately Hard, Close to Moderately Close Fracture Spacing, 4 Fractures at 80°, Granite 21.5											
690	691.5	25.6	5.0	2:30/1.0 2:00/1.0 2:15/1.0 2:30/1.0 2:00/1.0	(4.8) 96%	(3.8) 76%		(12.8) 92%	(11.3) 81%														
685	686.5	30.6	5.0	2:15/1.0 1:45/1.0 1:30/1.0 1:30/1.0	(4.8) 96%	(4.5) 90%																	
	681.5	35.6						(0.2) 100%	(0.0) 0%		681.7	Blue-Gray, Very Slightly Weathered, Moderately Hard, Close Fracture Spacing, Diabase 35.4											
											681.5	Boring Terminated at Elevation 681.5 ft In Crystalline Rock (Diabase) 35.6											

NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Howard, J.						
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22									GROUND WTR (ft)						
BORING NO. B1-B			STATION 139+54			OFFSET 56 ft RT			ALIGNMENT -L-			0 HR. 2.3			
COLLAR ELEV. 717.5 ft			TOTAL DEPTH 32.3 ft			NORTHING 815,224			EASTING 1,724,412			24 HR. 2.0			
DRILL RIG/HAMMER EFF./DATE CME-45C						DRILL METHOD NW Casing W/SPT & Core			HAMMER TYPE Automatic						
DRILLER Contract Driller			START DATE 04/01/09			COMP. DATE 04/01/09			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
720															
715	717.5	0.0	WOH	WOH	1						SS-1	M		717.5	GROUND SURFACE 0.0
	714.5	3.0	1	WOH	1						SS-2	W		710.5	ALLUVIAL Red-Brown and Orange, Sandy Silt 7.0
710	709.3	8.2	1	3	4						SS-3	M		706.5	Brown and Gray, Clayey Sand 11.0
705	704.3	13.2	8	10	17						SS-4	M		700.5	RESIDUAL Black, White and Brown, Coarse Sand 17.0
700	699.3	18.2	100/0.2			100/0.2					RS-3			697.9	WEATHERED ROCK (Granite) 19.6
695	697.9	19.6	60/0.0			60/0.0									
690											RS-4			685.2	Boring Terminated at Elevation 685.2 ft In Crystalline Rock (Granite) 32.3

NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT
CORE LOG

WBS 34802.1.1				TIP U-2412A				COUNTY Guilford				GEOLOGIST Howard, J.											
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22												GROUND WTR (ft)											
BORING NO. B1-B				STATION 139+54				OFFSET 56 ft RT				ALIGNMENT -L-				0 HR. 2.3							
COLLAR ELEV. 717.5 ft				TOTAL DEPTH 32.3 ft				NORTHING 815,224				EASTING 1,724,412				24 HR. 2.0							
DRILL RIG/HAMMER EFF./DATE CME-45C								DRILL METHOD NW Casing W/SPT & Core				HAMMER TYPE Automatic											
DRILLER Contract Driller				START DATE 04/01/09				COMP. DATE 04/01/09				SURFACE WATER DEPTH N/A											
CORE SIZE NQ				TOTAL RUN 12.7 ft																			
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) % RQD (ft) %		SAMP. NO.	STRATA REC. (ft) % RQD (ft) %		LOG	DESCRIPTION AND REMARKS												
											ELEV. (ft)	DEPTH (ft)											
697.9												Begin Coring @ 19.6 ft											
	697.9	19.6	2.7	N=60/0.0 2:30/1.0 3:00/1.0 3:45/0.7	(2.3) 85%	(2.2) 81%	RS-3	(10.8) 85%	(10.3) 81%		697.9	19.6											
695	695.2	22.3	5.0	1:30/1.0 3:00/1.0 2:45/1.0 2:30/1.0 2:15/1.0	(3.6) 72%	(3.6) 72%						Black and White, Fresh to Moderately Weathered, Hard, Close to Moderately Close Fracture Spacing, 1 Fracture at 45°, Granite											
690	690.2	27.3	5.0	3:15/1.0 2:30/1.0 2:30/1.0 2:15/1.0 2:00/1.0	(4.9) 98%	(4.5) 90%	RS-4																
	685.2	32.3									685.2	32.3											
														Boring Terminated at Elevation 685.2 ft In Crystalline Rock (Granite)									


NCDOT CORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Howard, J.					
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22									GROUND WTR (ft)					
BORING NO. B1-C			STATION 139+22			OFFSET 24 ft RT			ALIGNMENT -L-			0 HR. 0.6		
COLLAR ELEV. 716.3 ft			TOTAL DEPTH 22.6 ft			NORTHING 815,243			EASTING 1,724,371			24 HR. 0.6		
DRILL RIG/HAMMER EFF./DATE CME-45C						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER Contract Driller			START DATE 03/31/09			COMP. DATE 03/31/09			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft)	DEPTH (ft)
720														
	716.3	0.0	WOH	1	1								716.3	GROUND SURFACE 0.0
715											SS-1	M		713.3
														Red, Brown and Orange, Silty Clay 3.0
	711.3	5.0	3	4	5									Brown, Sandy Clay
710											SS-2	M		
	707.5	8.8	5	13	11								708.3	8.0
														RESIDUAL
705											SS-3	M		Black and White, Silty Sand
	702.4	13.9	48	52	0.2								702.4	13.9
														WEATHERED ROCK
700														(Granite)
	696.9	19.4	100	0.2										
695														
	693.7	22.6	60	0.0									693.7	22.6
													Boring Terminated with Standard Penetration Test Refusal at Elevation 693.7 ft On Crystalline Rock (Granite)	

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Howard, J.								
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22									GROUND WTR (ft)								
BORING NO. B2-B			STATION 140+07			OFFSET 52 ft RT			ALIGNMENT -L-			0 HR. 2.1					
COLLAR ELEV. 720.0 ft			TOTAL DEPTH 32.6 ft			NORTHING 815,245			EASTING 1,724,460			24 HR. 2.3					
DRILL RIG/HAMMER EFF./DATE CME-45C						DRILL METHOD NW Casing W/SPT & Core			HAMMER TYPE Automatic								
DRILLER Contract Driller			START DATE 04/06/09			COMP. DATE 04/06/09			SURFACE WATER DEPTH N/A								
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)		
720														720.0	GROUND SURFACE	0.0	
715	720.0	0.0	1	WOH	1						SS-1	M		718.0	ALLUVIAL Brown, Silty Sand	2.0	
	716.5	3.5	1	1	WOH						SS-2	M		713.0	Brown, Sandy Silt		
710	711.5	8.5	WOH	WOH	1						SS-3	W		708.5	Gray, Silty Sand	7.0	
705	706.5	13.5	16	19	20						SS-4	M		702.0	RESIDUAL Brown, Black and White, Silty Sand	11.5	
700	701.5	18.5	60/0.1								701.4	CRYSTALLINE ROCK (Diabase)		18.6			
695															Green to Blue-Gray, Fresh to Very Slightly Weathered, Hard, Close to Moderately Close Fracture Spacing, 2 Fractures at 45°, 1 at 20°, 1 at 80°, Diabase REC=91% RQD=86%		
690																	
															687.4	Boring Terminated at Elevation 687.4 ft In Crystalline Rock (Diabase)	32.6

NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT
CORE LOG

SHEET 16

WBS 34802.1.1				TIP U-2412A				COUNTY Guilford				GEOLOGIST Howard, J.							
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22												GROUND WTR (ft)							
BORING NO. B2-B				STATION 140+07				OFFSET 52 ft RT				ALIGNMENT -L-				0 HR. 2.1			
COLLAR ELEV. 720.0 ft				TOTAL DEPTH 32.6 ft				NORTHING 815,245				EASTING 1,724,460				24 HR. 2.3			
DRILL RIG/HAMMER EFF./DATE CME-45C								DRILL METHOD NW Casing W/SPT & Core				HAMMER TYPE Automatic							
DRILLER Contract Driller				START DATE 04/06/09				COMP. DATE 04/06/09				SURFACE WATER DEPTH N/A							
CORE SIZE NQ				TOTAL RUN 14.0 ft															
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) %		RQD (ft) %	SAMP. NO.	STRATA REC. (ft) %		RQD (ft) %	L O G	DESCRIPTION AND REMARKS ELEV. (ft) DEPTH (ft)						
701.4	701.4	18.6	4.0	1:15/1.0 2:30/1.0 3:30/1.0 4:15/1.0	(2.8) 70%	(2.2) 55%			(12.8) 91%	(12.0) 86%			Begin Coring @ 18.6 ft						
	697.4	22.6		3:45/1.0 2:45/1.0 2:30/1.0 5:00/1.0 6:30/1.0	(5.0) 100%	(5.0) 100%					701.4		Green to Blue-Gray, Fresh to Very Slightly Weathered, Hard, Close to Moderately Close Fracture Spacing, 2 Fractures at 45°, 1 at 20°, 1 at 80°, Diabase 18.6						
695			5.0																
	692.4	27.6																	
690			5.0																
	687.4	32.6		7:30/1.0 3:30/1.0 11:00/1.0 1:45/1.0 1:45/1.0	(5.0) 100%	(4.8) 96%							687.4	Boring Terminated at Elevation 687.4 ft In Crystalline Rock (Diabase) 32.6					

NCDOT CORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

[illegible][illegible]

BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNT Guilford			GEOLOGIST Howard, J.								
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22									GROUND WTR (ft)								
BORING NO. B2-D			STATION 139+90			OFFSET 32 ft RT			ALIGNMENT -L-			0 HR. 2.6					
COLLAR ELEV. 719.2 ft			TOTAL DEPTH 34.6 ft			NORTHING 815,258			EASTING 1,724,438			24 HR. FIAD					
DRILL RIG/HAMMER EFF./DATE CME-45C						DRILL METHOD NW Casing W/SPT & Core			HAMMER TYPE Automatic								
DRILLER Contract Driller			START DATE 04/08/09			COMP. DATE 04/08/09			SURFACE WATER DEPTH N/A								
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)		
720																	
	719.2	0.0	1	WOH	1						SS-1	D		719.2	GROUND SURFACE	0.0	
														717.2	ALLUVIAL Red-Brown, Silty Sand	2.0	
715	715.7	3.5	1	1	1						SS-2	W			712.2	Red-Brown, Sandy Silt	
710	710.7	8.5	1	WOH	3						SS-3	W			707.7	Gray, Silty Sand	7.0
705	705.7	13.5	60/0.0												705.7	WEATHERED ROCK (Granite)	11.5
											RS-7						13.5
700																	
695											RS-8				697.6	CRYSTALLINE ROCK Black and White, Fresh to Slightly Weathered, Hard, Close to Moderately Close Fracture Spacing, 2 Fractures at 80°, Granite REC=75% RQD=64%	21.6
690																	
685															684.6	Blue-Gray, Fresh to Slightly Weathered, Hard, Close Fracture Spacing, Diabase REC=92% RQD=78%	34.6
																Boring Terminated at Elevation 684.6 ft in Crystalline Rock (Diabase)	

CORE LOG

WBS 34802.1.1		TIP U-2412A		COUNTY Guilford		GEOLOGIST Howard, J.							
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22							GROUND WTR (ft)						
BORING NO. B2-D		STATION 139+90		OFFSET 32 ft RT		ALIGNMENT -L-		0 HR. 2.6					
COLLAR ELEV. 719.2 ft		TOTAL DEPTH 34.6 ft		NORTHING 815,258		EASTING 1,724,438		24 HR. FIAD					
DRILL RIG/HAMMER EFF./DATE CME-45C				DRILL METHOD NW Casing W/SPT & Core		HAMMER TYPE Automatic							
DRILLER Contract Driller		START DATE 04/08/09		COMP. DATE 04/08/09		SURFACE WATER DEPTH N/A							
CORE SIZE NQ		TOTAL RUN 21.1 ft											
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) % RQD (ft) %		SAMP. NO.	STRATA REC. (ft) % RQD (ft) %		L O G	DESCRIPTION AND REMARKS		DEPTH (ft)
705.7	705.7	13.5	1.1	N=60/0.0	(0.2)	(0.0)		(6.1)	(5.2)		Begin Coring @ 13.5 ft		
705	704.6	14.6	5.0	1:00/1.1	18%	0%		75%	64%		CRYSTALLINE ROCK		13.5
				30/1.0	(3.9)	(3.2)	RS-7				Black and White, Fresh to Slightly Weathered, Hard, Close to Moderately Close Fracture Spacing, 2 Fractures at 80°, Granite		
				1:30/1.0	78%	64%							
700	699.6	19.6		2:00/1.0									
				2:15/1.0									
			5.0	2:30/1.0									
				3:45/1.0	(4.6)	(4.5)							
				3:00/1.0	92%	90%		(11.9)	(10.1)		697.6		21.6
				3:15/1.0			RS-8	92%	78%		Blue-Gray, Fresh to Slightly Weathered, Hard, Close Fracture Spacing, Diabase		
695	694.6	24.6		3:30/1.0									
			5.0	2:15/1.0	(4.8)	(3.8)							
				3:15/1.0	96%	76%							
				1:45/1.0									
690	689.6	29.6		1:30/1.0									
				2:15/1.0									
			5.0	2:45/1.0	(5.0)	(4.3)							
				2:45/1.0	100%	86%							
				3:45/1.0									
685	684.6	34.6		4:00/1.0						684.6		34.6	
				4:30/1.0						Boring Terminated at Elevation 684.6 ft In Crystalline Rock (Diabase)			

NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

NC DOT CORE DOUBLE U2412A GEO BH.GPJ NC DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Howard, J.							
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22									GROUND WTR (ft)							
BORING NO. B3-B			STATION 141+62			OFFSET 51 ft RT			ALIGNMENT -L-			0 HR. 2.0				
COLLAR ELEV. 716.9 ft			TOTAL DEPTH 41.0 ft			NORTHING 815,295			EASTING 1,724,606			24 HR. 2.0				
DRILL RIG/HAMMER EFF./DATE CME-45C						DRILL METHOD NW Casing W/SPT & Core			HAMMER TYPE Automatic							
DRILLER Contract Driller			START DATE 03/24/09			COMP. DATE 03/24/09			SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
720																
	716.9	0.0														
715			1	1	1	2					SS-1				716.9 GROUND SURFACE	0.0
	713.4	3.5	WOH	WOH	WOH						SS-2	W			714.9 ALLUVIAL Brown, Silty Clay	2.0
710															Tan and Gray, Sandy Silt	
	708.4	8.5	13	6	8						SS-3	W			709.9 Tan, Silty Sand	7.0
705															707.0 RESIDUAL Black and White, Silty Sand	9.9
	703.4	13.5	18	37	63/0.4										706.4 WEATHERED ROCK (Granite)	10.5
700										100/0.4						
	698.4	18.5	60/0.0							60/0.0					698.5 CRYSTALLINE ROCK Blue-Gray, Fresh to Weathered, Hard to Very Hard, Close Fracture Spacing, Diabase REC=31% RQD=17%	18.4
695																
690																
685																
680															683.2 Black and White, Slightly Weathered, Hard, Close Fracture Spacing, Granite REC=100% RQD=71%	33.7
															682.5 Blue-Gray, Fresh to Moderately Severe Weathering, Moderately Hard to Hard, Very Close to Moderately Close Fracture Spacing, Diabase REC=86% RQD=55%	34.4
															675.9 Boring Terminated at Elevation 675.9 ft In Crystalline Rock (Diabase)	41.0

NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT
CORE LOG

SHEET 20

WBS 34802.1.1		TIP U-2412A		COUNTY Guilford		GEOLOGIST Howard, J.						
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22							GROUND WTR (ft)					
BORING NO. B3-B		STATION 141+62		OFFSET 51 ft RT		ALIGNMENT -L-	0 HR. 2.0					
COLLAR ELEV. 716.9 ft		TOTAL DEPTH 41.0 ft		NORTHING 815,295		EASTING 1,724,606	24 HR. 2.0					
DRILL RIG/HAMMER EFF./DATE CME-45C				DRILL METHOD NW Casing W/SPT & Core		HAMMER TYPE Automatic						
DRILLER Contract Driller		START DATE 03/24/09		COMP. DATE 03/24/09		SURFACE WATER DEPTH N/A						
CORE SIZE NQ		TOTAL RUN 22.6 ft										
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) % ROD (ft) %		SAMP. NO.	STRATA REC. (ft) % ROD (ft) %		L O G	DESCRIPTION AND REMARKS	DEPTH (ft)
698.5	698.5	18.4	2.6	4:15/1.0	(2.6)	(0.4)		(4.8)	(2.6)		Begin Coring @ 18.4 ft	18.4
695	695.9	21.0	5.0	3:15/1.0	100%	15%		31%	17%		Blue-Gray, Fresh to Weathered, Hard to Very Hard, Close Fracture Spacing, Diabase	
				2:00/0.6	(4.6)	(2.4)						
				3:45/1.0	92%	48%						
				2:00/1.0								
				3:00/1.0								
690	690.9	26.0	5.0	2:30/1.0	(5.0)	(5.0)						
				2:15/1.0	100%	100%						
				2:15/1.0								
				2:00/1.0								
685	685.9	31.0	5.0	1:30/1.0	(4.5)	(2.3)						
				1:45/1.0	90%	46%						
				2:30/1.0								
				3:00/1.0								
				3:40/1.0								
680	680.9	36.0	5.0	2:30/1.0	(0.7)	(0.5)		683.2			Black and White, Slightly Weathered, Hard, Close Fracture Spacing,	33.7
				4:00/1.0	100%	71%		682.5			Blue-Gray, Fresh to Moderately Severe Weathering, Moderately Hard to Hard, Very Close to Moderately Close Fracture Spacing, Diabase	34.4
				3:00/1.0	(5.7)	(3.6)						
				2:15/1.0	86%	55%						
				2:30/1.0								
				2:30/1.0								
	675.9	41.0		2:45/1.0								
											Boring Terminated at Elevation 675.9 ft In Crystalline Rock (Diabase)	41.0

NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Howard, J.						
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22									GROUND WTR (ft)						
BORING NO. B3-C			STATION 141+27			OFFSET 22 ft RT			ALIGNMENT -L-			0 HR. 2.0			
COLLAR ELEV. 716.3 ft			TOTAL DEPTH 16.7 ft			NORTHING 815,311			EASTING 1,724,564			24 HR. 2.0			
DRILL RIG/HAMMER EFF./DATE CME-45C						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic						
DRILLER Contract Driller			START DATE 03/25/09			COMP. DATE 03/25/09			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	L O G	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
720															
	716.3	0.0	WOH	1	1									716.3	GROUND SURFACE 0.0
715											SS-1	M		714.3	ALLUVIAL Tan and Red, Silty Clay 2.0
	713.3	3.0	1	WOH	WOH						SS-2	W			Tan and Gray, Sandy Silt
710														709.8	6.5
	708.3	8.0	34	13	6						SS-3	W			Tan and Gray, Sandy Clay
705														705.3	RESIDUAL Blue-Gray, Sandy Silt 11.0
	703.3	13.0	7	11	15						SS-4	D			
700	699.6	16.7												699.6	16.7
			60/0.0							60/0.0					Boring Terminated with Standard Penetration Test Refusal at Elevation 699.6 ft On Crystalline Rock (Diabase)

NC DOT BORE DOUBIE I12412A GEO BH GP1 NC DOT GDT 1/30/18

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Howard, J.					
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22									GROUND WTR (ft)					
BORING NO. EB2-B			STATION 142+83			OFFSET 59 ft RT			ALIGNMENT -L-			0 HR. Dry		
COLLAR ELEV. 749.7 ft			TOTAL DEPTH 27.2 ft			NORTHING 815,324			EASTING 1,724,723			24 HR. Dry		
DRILL RIG/HAMMER EFF./DATE CME-45C						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER Contract Driller			START DATE 03/23/09			COMP. DATE 03/23/09			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
750	749.7	0.0	1	2	2						SS-1	D		749.7 GROUND SURFACE 0.0
745	744.7	5.0	4	4	6						SS-2	M		ARTIFICIAL FILL Orange, Brown and Gray, Sandy Silt
740	739.7	10.0	2	6	4						SS-3	M		736.7 13.0
735	734.7	15.0	9	31	41						SS-4	M		RESIDUAL Orange and Black, Silty Sand
730	729.5	20.2	100/0.2			100/0.2								732.7 17.0
725	724.7	25.0	100/0.5			100/0.5								WEATHERED ROCK (Granite)
	722.5	27.2	60/0.0			60/0.0								
Boring Terminated with Standard Penetration Test Refusal at Elevation 722.5 ft On Crystalline Rock (Granite)														

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1				TIP U-2412A		COUNTY Guilford		GEOLOGIST Howard, J.								
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22										GROUND WTR (ft)						
BORING NO. EB2-C			STATION 142+01			OFFSET 17 ft LT			ALIGNMENT -L-		0 HR. Dry					
COLLAR ELEV. 723.1 ft			TOTAL DEPTH 13.7 ft			NORTHING 815,371			EASTING 1,724,622		24 HR. 3.6					
DRILL RIG/HAMMER EFF./DATE CME-45C						DRILL METHOD Mud Rotary				HAMMER TYPE Automatic						
DRILLER Contract Driller			START DATE 03/26/09			COMP. DATE 03/26/09			SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)	
725																
	723.1	0.0												723.1	0.0	GROUND SURFACE
			1	1	WOH						SS-1	W				ARTIFICIAL FILL
720	719.9	3.2												720.6	2.5	Red, Tan and Gray, Sandy Silt
			WOH	2	3						SS-2	M				RESIDUAL
																Red-Brown and Orange, Sandy Clay
715	714.9	8.2												716.4	6.7	Red-Orange, Sandy Silt
			9	18	20						SS-3	M				
710	709.9	13.2												710.6	12.5	
	709.4	13.7	100/0.3											709.4	13.7	WEATHERED ROCK (Granite)
			60/0.0													Boring Terminated with Standard Penetration Test Refusal at Elevation 709.4 ft On Crystalline Rock (Granite)

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Milkovits, J. I.					
SITE DESCRIPTION Structures No. 3 & 4 on -L- (Greensboro/High Point Rd.) over Deep River at Sta. 140+22									GROUND WTR (ft)					
BORING NO. EB2-D			STATION 142+50			OFFSET 20 ft RT			ALIGNMENT -L-			0 HR. Dry		
COLLAR ELEV. 731.1 ft			TOTAL DEPTH 14.1 ft			NORTHING 815,351			EASTING 1,724,680			24 HR. Dry		
DRILL RIG/HAMMER EFF./DATE CME-45C						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER Contract Driller			START DATE 09/24/08			COMP. DATE 09/24/08			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
735														
730	731.1	0.0	4	5	10						SS-168	M		731.1 GROUND SURFACE 0.0
	727.9	3.2	7	8	6						SS-169	M		728.1 ARTIFICIAL FILL Brown, Sandy Silt 3.0
725														
	722.9	8.2	54	46/0.4										722.9 RESIDUAL Brown, Sandy Silt 8.2
720														722.9 WEATHERED ROCK (Granite) 8.2
	717.9	13.2												
	717.0	14.1	30	70/0.3										717.0 Boring Terminated with Standard Penetration Test Refusal at Elevation 717.0 ft On Crystalline Rock (Granite) 14.1

NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

EB1-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	52 LT	137+56	0.0-1.5	A-6(5)	37	12	23.0	23.0	29.7	24.2	94	79	56	-	-
SS-2	52 LT	137+56	3.5-5.0	A-4(2)	24	8	21.0	26.1	30.7	22.2	94	80	56	-	-
SS-3	52 LT	137+56	8.5-10.0	A-6(3)	30	15	21.0	38.4	14.3	26.3	100	88	47	-	-

EB1-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	47 RT	138+86	0.0-1.5	A-4(4)	34	9	27.1	15.8	32.9	24.2	97	78	59	-	-
SS-2	47 RT	138+86	3.5-5.0	A-6(3)	31	12	13.5	42.2	18.0	26.3	100	95	52	-	-
SS-3	47 RT	138+86	8.5-10.0	A-2-4(0)	29	10	48.7	23.2	9.9	18.2	79	50	25	-	-
SS-4	47 RT	138+86	13.5-15.0	A-1-a(0)	24	2	48.3	24.6	19.0	8.1	43	27	14	-	-

EB1-C

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-16	20 LT	138+00	3.5-5.0	A-6(5)	33	13	18.2	25.1	28.3	28.4	94	83	58	-	-

EB1-D

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	17 RT	138+43	0.0-1.5	A-4(0)	28	5	38.2	29.1	18.6	14.1	96	75	36	-	-
SS-2	17 RT	138+43	4.3-5.8	A-2-4(0)	18	NP	31.7	41.0	17.2	10.1	100	85	33	-	-
SS-3	17 RT	138+43	9.6-10.6	A-2-4(0)	23	NP	63.6	22.9	5.4	8.1	97	57	15	-	-
SS-4	17 RT	138+43	14.4-15.4	A-6(6)	40	12	18.4	26.3	39.2	16.2	100	91	61	-	-

B1-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	51 LT	138+40	0.0-1.5	Material	Not enough		26.4	24.8	32.5	16.3	97	75	55	-	-
SS-2	51 LT	138+40	3.9-5.4	A-2-4(0)	19	NP	38.4	39.2	12.2	10.2	100	78	27	-	-
SS-3	51 LT	138+40	7.9-9.4	A-4(2)	30	8	4.9	49.2	23.6	22.4	100	99	57	-	-
SS-4	51 LT	138+40	12.9-13.4	A-1-b(0)	21	NP	56.9	25.8	9.1	8.1	57	32	12	-	-

B1-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	56 RT	139+54	0.0-1.5	Material	Not enough		8.5	54.9	16.3	20.3	100	98	43	-	-
SS-2	56 RT	139+54	3.0-4.5	A-4(0)	25	7	39.8	23.6	18.3	18.3	100	78	40	-	-
SS-3	56 RT	139+54	8.2-9.7	A-2-6(0)	29	11	36.8	32.3	8.5	22.4	92	71	32	-	-
SS-4	56 RT	139+54	13.2-14.7	A-1-b(0)	27	2	57.3	25.6	11.0	6.1	85	50	18	-	-

B1-C

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	24 RT	139+22	0.0-1.5	A-7-6(11)	43	15	10.0	22.4	37.2	30.5	100	94	74	-	-
SS-2	24 RT	139+22	5.0-6.5	A-6(2)	34	12	16.7	44.5	10.4	28.5	100	93	45	-	-
SS-3	24 RT	139+22	8.8-10.3	A-2-4(0)	22	2	36.8	38.8	14.2	10.2	69	54	21	-	-

B2-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	55 LT	138+90	0.0-1.5	A-4(0)	28	4	12.8	52.3	20.7	14.2	100	97	42	-	-
SS-2	55 LT	138+90	3.5-5.0	A-2-4(0)	24	2	39.1	30.3	22.5	8.1	100	83	35	-	-
SS-3	55 LT	138+90	8.5-10.0	Material	Not enough		56.2	25.2	14.5	4.1	82	55	18	-	-
SS-4	55 LT	138+90	13.5-14.0	A-1-b(0)	18	2	62.5	21.6	9.9	6.1	70	35	14	-	-
SS-5	55 LT	138+90	18.5-20.0	A-2-4(0)	28	NP	13.4	59.8	22.7	4.1	95	89	35	-	-

B2-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	52 RT	140+07	0.0-1.5	A-2-4(0)	26	NP	35.4	44.6	11.9	8.1	100	88	24	-	-
SS-2	52 RT	140+07	3.5-5.0	A-4(0)	25	5	31.3	32.1	24.3	12.2	100	84	43	-	-
SS-3	52 RT	140+07	8.5-10.0	A-2-4(0)	21	NP	44.4	41.7	7.8	6.1	100	84	17	-	-
SS-4	52 RT	140+07	13.5-15.0	A-2-4(0)	31	9	39.7	21.0	29.2	10.2	54	37	24	-	-

B2-C

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			% MOISTURE	% ORGANIC
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	CL	139+54	0.0-1.5	A-2-4(0)	29	5	22.8	46.2	18.8	12.2	96	88	35	-	-
SS-2	CL	139+54	3.2-4.7	A-2-4(0)	23	NP	43.3	33.0	15.6	8.1	100	84	27	-	-
SS-3	CL	139+54	7.8-9.3	A-4(0)	27	6	28.9	37.8	15.0	18.3	100	85	39	-	-
SS-4	CL	139+54	13.1-13.6	A-4(1)	31	3	2.8	36.0	53.0	8.1	92	91	67	-	-

B2-D

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	32 RT	139+90	0.0-1.5	A-2-4(0)	23	NP	36.0	40.9	15.0	8.1	100	82	28	-	-
SS-2	32 RT	139+90	3.5-5.0	A-4(0)	25	3	37.2	29.5	23.1	10.2	100	77	40	-	-
SS-3	32 RT	139+90	8.5-10.0	A-2-4(0)	20	NP	50.3	34.8	8.9	6.1	100	76	18	-	-

B3-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	48 LT	140+44	0.0-1.5	A-7-6(13)	45	17	3.2	28.5	38.0	30.3	100	99	76	-	-
SS-2	48 LT	140+44	3.8-5.3	A-4(6)	30	9	3.2	28.3	40.2	28.3	100	99	77	-	-
SS-3	48 LT	140+44	8.8-10.3	A-4(0)	20	1	22.8	46.9	14.1	16.2	100	93	37	-	-

B3-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	51 RT	141+62	0.0-1.5	A-7-6(12)	42	16	12.9	15.8	41.0	30.3	98	89	74	-	-
SS-2	51 RT	141+62	3.5-5.0	A-4(1)	25	7	12.5	39.2	22.0	26.3	100	95	56	-	-
SS-3	51 RT	141+62	8.5-9.9	A-2-4(0)	28	9	32.3	36.2	11.3	20.2	79	66	28	-	-

B3-C

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	22 RT	141+27	0.0-1.5	A-7-5(21)	49	19	3.4	8.3	43.8	44.4	100	98	91	-	-
SS-2	22 RT	141+27	3.0-4.5	A-4(0)	26	6	36.8	19.6	25.5	18.2	94	69	45	-	-
SS-3	22 RT	141+27	8.0-9.5	A-6(3)	33	13	19.4	36.8	13.5	30.3	98	91	48	-	-
SS-4	22 RT	141+27	13.0-14.5	A-4(4)	32	5	5.7	23.2	52.9	18.2	98	94	79	-	-

EB2-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	44 LT	141+57	0.0-1.5	A-4(0)	24	5	28.5	25.1	26.3	20.2	95	76	50	-	-
SS-2	44 LT	141+57	3.6-5.1	A-4(2)	27	10	27.9	22.2	23.6	26.3	98	80	53	-	-

EB2-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	59 RT	142+83	0.0-1.5	A-4(1)	29	8	30.7	25.5	23.6	20.2	96	76	48	-	-
SS-2	59 RT	142+83	5.0-6.5	A-4(2)	30	7	24.0	26.3	29.5	20.2	95	78	54	-	-
SS-3	59 RT	142+83	10.0-11.5	A-4(0)	29	8	37.6	24.2	22.0	16.2	93	67	40	-	-
SS-4	59 RT	142+83	15.0-16.5	A-2-4(0)	19	NP	36.1	39.0	15.9	9.1	100	82	32	-	-

EB2-C

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	17 LT	142+01	0.0-1.5	A-4(1)	30	5	21.6	26.1	32.1	20.2	99	84	59	-	-
SS-2	17 LT	142+01	3.2-4.7	A-6(5)	29	12	21.0	21.4	27.3	30.3	99	85	62	-	-
SS-3	17 LT	142+01	8.2-9.7	A-4(3)	27	9	22.6	21.8	27.3	28.3	100	85	61	-	-

EB2-D


SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-168	20 RT	142+50	0.0-1.5	A-4(2)	28	9	28.1	23.0	24.8	24.0	95	76	51	-	-
SS-169	20 RT	142+50	3.2-4.7	A-4(2)	29	9	29.9	22.0	24.0	24.0	95	74	50	-	-

ROCK TEST RESULTS									
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	H/D RATIO	UNIT WT lbs/ft3	Ultimate lbf	Ultimate ksi	Ultimate (corrected) ksi	Sec. Mod. @ 40% Mpsi
RS-1	51 LT	138+40	14.8-15.4	SAMPLE DAMAGED					
RS-2	51 LT	138+40	19.7-20.3	2.21	182.5	66900	24.6	24.9	6.37
RS-3	56 RT	139+54	19.6-20.3	2.15	184.1	62700	23.1	23.3	8.59
RS-4	56 RT	139+54	28.7-29.3	2.19	168.8	60900	22.4	22.6	7.43
RS-5	55 LT	138+90	22.9-23.5	2.19	184.4	65200	24.0	24.2	8.06
RS-6	55 LT	138+90	29.9-30.5	2.15	182.5	43200	15.9	16.0	6.07
RS-7	32 RT	139+90	15.7-16.3	2.24	166.7	35300	13.0	13.2	4.30
RS-8	32 RT	139+90	22.9-23.6	2.21	178.2	90200	33.2	33.6	7.22
RS-9	48 LT	140+44	12.9-13.4	2.21	178.2	55400	20.4	20.6	6.60
RS-10	48 LT	140+44	16.5-17.0	2.16	182.7	48200	18.3	18.5	6.70

CORE PHOTOGRAPHS


B1-A

BOXES 1 & 2: 14.1 - 35.6 FEET



B1-B

BOXES 1 & 2: 19.6 - 32.3 FEET



CORE PHOTOGRAPHS

B2-A

BOXES 1 & 2: 21.6 - 40.6 FEET



B2-B


BOXES 1 & 2: 18.6 - 32.6 FEET



CORE PHOTOGRAPHS


B2-C

BOXES 1 & 2: 14.3 - 30.5 FEET



B2-D


BOXES 1 & 2: 13.5 - 34.6 FEET



CORE PHOTOGRAPHS


B3-A

BOXES 1 & 2: 11.5 - 26.5 FEET




B3-B

BOXES 1, 2 & 3: 18.4 - 41.0 FEET



Site Photograph

Structures No. 3 & 4 on -L- (SR 4121, Greensboro/High Point Rd.) Over Deep River



Looking North

PROJECT: 34802.1.1 ID: U-2412A

CONTENTS

SHEET	DESCRIPTION
1	TITLE SHEET
2	LEGEND
3	SITE PLAN
4	PROFILE
5-8	CROSS SECTIONS
9-18	BORE LOGS & CORE REPORTS
19	SOIL TEST RESULTS
20	SCOUR REPORT
21, 22	CORE PHOTOGRAPHS
23	SITE PHOTOGRAPH

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

PROJ. REFERENCE NO. 34802.1.1 (U-2412A) F.A. PROJ. STP-4121(1)
COUNTY GUILFORD
PROJECT DESCRIPTION GREENSBORO/HIGH POINT RD. FROM
PROPOSED US 311 BYPASS TO WEST OF SR 1480

SITE DESCRIPTION STRUCTURES NO. 5 & 6 ON -L- (SR 4121,
GREENSBORO/HIGH POINT RD.) OVER BULL RUN CREEK
AT STATION 155+03

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	34802.1.1 (U-2412A)	1	19

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING, AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 250-4088. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA ARE PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE, THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

PERSONNEL

N.D. MOHS

T.T. WALKER


MACTEC

INVESTIGATED BY N.D. MOHS

CHECKED BY C.D. CZAJKA

SUBMITTED BY N.T. ROBERSON

DATE MAY 2009



Digitally signed by:

Neil T. Roberson

4081D9A8C6C649C...

1/31/2018


DRAWN BY: N.D. MOHS


NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.


NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.


SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS


REVISÉ 02/23/06












GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Mohs, N. D.								
SITE DESCRIPTION Structures No. 5 & 6 on -L- (SR 4121, Greensboro/High Point Rd.) Over Bull Run Creek										GROUND WTR (ft)							
BORING NO. EB1-A			STATION 154+22			OFFSET 55 ft LT			ALIGNMENT -L-		0 HR. 12.0						
COLLAR ELEV. 721.3 ft			TOTAL DEPTH 28.6 ft			NORTHING 815,712			EASTING 1,725,799		24 HR. 8.0						
DRILL RIG/HAMMER EFF./DATE CME-55						DRILL METHOD H.S. Augers				HAMMER TYPE Automatic							
DRILLER Contract Driller			START DATE 03/24/09			COMP. DATE 03/24/09			SURFACE WATER DEPTH N/A								
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100							
725																	
720																	
715	717.8	3.5		4	5	7						SS-4	M		721.3	GROUND SURFACE	0.0
710	712.8	8.5		3	6	9						SS-5	M		714.5	RESIDUAL Brown, Silty Clay	6.8
705	707.8	13.5		11	11	15							M		709.5	Gray, Sandy Silt	11.8
700	702.8	18.5		14	28	48							M			Tan, Coarse Sand	
695	697.8	23.5		18	34	26							M		695.3		
	692.8	28.5	60/0.1												692.8	WEATHERED ROCK (Diorite)	26.0
															692.7	CRYSTALLINE ROCK (Diorite)	28.5
																Boring Terminated with Standard Penetration Test Refusal at Elevation 692.7 ft in Crystalline Rock (Diorite)	

WBS 34802.1.1		TIP U-2412A		COUNTY Guilford		GEOLOGIST Mohs, N. D.								
SITE DESCRIPTION Structures No. 5 & 6 on -L- (SR 4121, Greensboro/High Point Rd.) Over Bull Run Creek							GROUND WTR (ft)							
BORING NO. EB1-B		STATION 153+32		OFFSET 68 ft RT		ALIGNMENT -L-		0 HR.	5.0					
COLLAR ELEV. 714.4 ft		TOTAL DEPTH 12.9 ft		NORTHING 815,574		EASTING 1,725,734		24 HR.	4.8					
DRILL RIG/HAMMER EFF./DATE CME-55				DRILL METHOD H.S. Augers			HAMMER TYPE Automatic							
DRILLER Contract Driller		START DATE 03/24/09		COMP. DATE 03/24/09		SURFACE WATER DEPTH N/A								
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
715														
	711.6	2.8	WOH	1	1								714.4 GROUND SURFACE 0.0	
710											SS-3	Mo	ARTIFICIAL FILL Brown, Sandy Silt	
	706.6	7.8		6	16	24								709.4 RESIDUAL Brown, Coarse Sand 5.0
705												Sat.	705.1 WEATHERED ROCK (Diorite) 9.3	
	701.6	12.8		60/0.1									702.1 12.3	
													701.5 CRYSTALLINE ROCK (Diorite) 12.9	
													Boring Terminated with Standard Penetration Test Refusal at Elevation 701.5 ft in Crystalline Rock (Diorite)	

NC DOT BORE DOUBLE U2412A GEO BH.GPJ NC DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT BORE LOG

[illegible]

GEOTECHNICAL BORING REPORT

BORE LOG

[illegible]

NC DOT BORE DOUBLE U2412A GEO BH.GPJ NC DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT

CORE LOG

WBS 34802.1.1		TIP U-2412A		COUNTY Guilford		GEOLOGIST Mohs, N. D.							
SITE DESCRIPTION Structures No. 5 & 6 on -L- (SR 4121, Greensboro/High Point Rd.) Over Bull Run Creek								GROUND WTR (ft)					
BORING NO. B1-A		STATION 154+59		OFFSET 47 ft LT		ALIGNMENT -L-		0 HR.	N/A				
COLLAR ELEV. 718.1 ft		TOTAL DEPTH 32.7 ft		NORTHING 815,711		EASTING 1,725,837		24 HR.	4.6				
DRILL RIG/HAMMER EFF./DATE CME-55				DRILL METHOD SPT Core Boring		HAMMER TYPE Automatic							
DRILLER Contract Driller		START DATE 03/27/09		COMP. DATE 03/27/09		SURFACE WATER DEPTH N/A							
CORE SIZE NQ		TOTAL RUN 23.6 ft											
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)	
					REC. (ft) %	RQD (ft) %		REC. (ft) %	RQD (ft) %				
709											Begin Coring @ 9.1 ft		
	709.0	9.1	3.6	N=60/0.0 2:47/1.0 3:30/1.0 4:11/1.0 1:00/0.6	(3.6) 100%	(1.8) 50%		(18.6) 79%	(7.2) 31%		709.0	9.1	
705	705.4	12.7	5.0	2:46/1.0 2:21/1.0 3:36/1.0 3:11/1.0 2:52/1.0	(5.0) 100%	(2.7) 54%	RS-3				Green,Fresh to Slightly Weathered on Fracture Surfaces, Hard, Very Close to Close Fracture Spacing, Massive, Aphanitic, Diabase REC=79% RQD=31% RMR=72		
700	700.4	17.7	5.0	2:36/1.0 3:14/1.0 3:02/1.0 2:31/1.0 2:04/1.0	(4.0) 80%	(2.7) 54%							
695	695.4	22.7	5.0	2:38/1.0 2:00/1.0 2:33/1.0 2:50/1.0 1:30/1.0	(4.0) 80%	(0.5) 10%							
690	690.4	27.7	5.0	2:15/1.0 2:27/1.0 2:03/1.0 1:54/1.0 2:16/1.0	(2.0) 40%	(0.5) 10%							
	685.4	32.7										685.4	32.7
													Boring Terminated at Elevation 685.4 ft in Crystalline Rock (Diabase)

NCDOT CORE DOUBLE U2412A GEO BH.GPJ NC DOT.GDT 1/30/18

NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

NC DOT CORE DOUBLE U2412A GEO BH.GPJ NC DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Mohs, N. D.							
SITE DESCRIPTION Structures No. 5 & 6 on -L- (SR 4121, Greensboro/High Point Rd.) Over Bull Run Creek									GROUND WTR (ft)							
BORING NO. B1-C			STATION 154+28			OFFSET 23 ft RT			ALIGNMENT -L-			0 HR. 5.0				
COLLAR ELEV. 717.3 ft			TOTAL DEPTH 13.3 ft			NORTHING 815,636			EASTING 1,725,820			24 HR. N/A				
DRILL RIG/HAMMER EFF./DATE CME-55						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic							
DRILLER Contract Driller			START DATE 03/24/09			COMP. DATE 03/24/09			SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	▼ MOI	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
720																
715	717.3	0.0									SS-6	M		717.3	GROUND SURFACE	0.0
	714.1	3.2	WOH	WOH	1									712.3	ALLUVIAL Brown, Silty Sand	
710	714.1	3.2	1	2	1							Mz V		712.3	WEATHERED ROCK (Diorite)	5.0
	709.1	8.2														
705	709.1	8.2	100/0.4											704.3		13.0
	704.1	13.2												704.0	CRYSTALLINE ROCK (Diorite)	13.3
			60/0.1											Boring Terminated with Standard Penetration Test Refusal at Elevation 704.0 ft in Crystalline Rock (Diorite)		

NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

WBS		34802.1.1		TIP		U-2412A		COUNTY		Guilford		GEOLOGIST		Mohs, N. D.																																													
SITE DESCRIPTION												Structures No. 5 & 6 on -L- (SR 4121, Greensboro/High Point Rd.) Over Bull Run Creek				GROUND WTR (ft)																																											
BORING NO.				B2-A				STATION				155+73				OFFSET				47 ft LT				ALIGNMENT				-L-				0 HR.		N/A																									
COLLAR ELEV.				716.4 ft				TOTAL DEPTH				23.3 ft				NORTHING				815,731				EASTING				1,725,950				24 HR.		2.3																									
DRILL RIG/HAMMER EFF./DATE										CME-55										DRILL METHOD										SPT Core Boring										HAMMER TYPE										Automatic									
DRILLER						Contract Driller						START DATE						03/31/09						COMP. DATE						03/31/09						SURFACE WATER DEPTH												N/A											
ELEV (ft)		DRIVE ELEV (ft)		DEPTH (ft)		BLOW COUNT			BLOWS PER FOOT					SAMP. NO.		MOI		LOG		SOIL AND ROCK DESCRIPTION																																							
						0.5ft 0.5ft 0.5ft			0 25 50 75 100											ELEV. (ft) DEPTH (ft)																																							
720																																																											
715		716.4		0.0		WOH WOH WOH								S-8		M		M		716.4 GROUND SURFACE 0.0																																							
		712.7		3.7		1 16 27										M		M		712.2 ALLUVIAL Brown, Sand 4.2																																							
710		711.1		5.3		6 7 10										Sat.		M		710.2 RESIDUAL Brown, Coarse Sand, Gravel, and Boulders 4.2																																							
705		707.7		8.7		5 14 23								SS-9		Sat.		M		707.7 CRYSTALLINE ROCK Gray, Fresh, Very Hard, Moderately Close Fracture Spacing, Massive to Weakly Foliated, Phaneritic, Diorite REC=96% RQD=81% RMR=72 13.3																																							
700														RS-1				M		700.1 Boring Terminated at Elevation 693.1 ft in Crystalline Rock (Diorite) 23.3																																							
695																		M																																									

NCDOT CORE DOUBLE U2412A GEO BH.GPJ NC DOT.GDT 1/30/18

WBS		34802.1.1		TIP		U-2412A		COUNTY		Guilford		GEOLOGIST		Mohs, N. D.																																													
SITE DESCRIPTION												Structures No. 5 & 6 on -L- (SR 4121, Greensboro/High Point Rd.) Over Bull Run Creek				GROUND WTR (ft)																																											
BORING NO.				B2-A				STATION				155+73				OFFSET				47 ft LT				ALIGNMENT				-L-				0 HR.		N/A																									
COLLAR ELEV.				716.4 ft				TOTAL DEPTH				23.3 ft				NORTHING				815,731				EASTING				1,725,950				24 HR.		2.3																									
DRILL RIG/HAMMER EFF./DATE										CME-55										DRILL METHOD										SPT Core Boring										HAMMER TYPE										Automatic									
DRILLER						Contract Driller						START DATE						03/31/09						COMP. DATE						03/31/09						SURFACE WATER DEPTH						N/A																	
CORE SIZE						NQ						TOTAL RUN						10.0 ft																																									
ELEV (ft)		RUN ELEV (ft)		DEPTH (ft)		RUN (ft)		DRILL RATE (Min/ft)		RUN REC (ft) %		RUN RQD (ft) %		SAMP. NO.		STRATA REC (ft) %		STRATA RQD (ft) %		LOG		DESCRIPTION AND REMARKS																																					
703.1																						ELEV. (ft) DEPTH (ft)																																					
703.1		703.1		13.3		5.0		2:05/1.0 4:07/1.0 4:06/1.0 4:03/1.0 6:03/1.0		(4.6) 92% (4.0) 80%						(9.6) 96% (8.1) 81%						Begin Coring @ 13.3 ft																																					
700														RS-1								CRYSTALLINE ROCK																																					
		698.1		18.3		5.0		6:13/1.0 6:22/1.0 7:45/1.0 13:12/1.0 17:00/1.0		(5.0) 100% (4.1) 82%												Gray, Fresh, Very Hard, Moderately Close Fracture Spacing, Massive to Weakly Foliated, Phaneritic, Diorite																																					
695																						REC=96% RQD=81% RMR=72																																					
		693.1		23.3																		693.1																																					
																						Boring Terminated at Elevation 693.1 ft in Crystalline Rock (Diorite)																																					

NCDOT CORE DOUBLE U2412A GEO BH.GPJ NC DOT.GDT 1/30/18

WBS 34802.1.1				TIP U-2412A				COUNTY Guilford				GEOLOGIST Mohs, N. D.				
SITE DESCRIPTION Structures No. 5 & 6 on -L- (SR 4121, Greensboro/High Point Rd.) Over Bull Run Creek												GROUND WTR (ft)				
BORING NO. B2-B				STATION 155+30				OFFSET 47 ft RT				ALIGNMENT -L-				
COLLAR ELEV. 716.2 ft				TOTAL DEPTH 18.2 ft				NORTHING 815,631				EASTING 1,725,924				
DRILL RIG/HAMMER EFF./DATE CME-55								DRILL METHOD SPT Core Boring				HAMMER TYPE Automatic				
DRILLER Contract Driller				START DATE 03/31/09				COMP. DATE 03/31/09				SURFACE WATER DEPTH N/A				
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)	
720																
715	716.2	0.0	2	2	5						SS-10	M		716.2	GROUND SURFACE	0.0
710	712.8	3.4	60/0.0								RS-2			712.8	RESIDUAL Brown, Sandy Silt and Gravel	3.4
705															CRYSTALLINE ROCK Green, Fresh, Very Hard, Moderately Close to Wide Fracture Spacing, Massive, Aphanitic, Diabase REC=90% RQD=89% RMR=72	
700														703.0	Gray, Fresh, Very Hard, Wide Fracture Spacing, Massive, Phaneritic, Diorite REC=90% RQD=89% RMR=72	13.2
														698.0	Boring Terminated at Elevation 698.0 ft in Crystalline Rock (Diorite)	18.2

WBS 34802.1.1		TIP U-2412A		COUNTY Guilford		GEOLOGIST Mohs, N. D.								
SITE DESCRIPTION Structures No. 5 & 6 on -L- (SR 4121, Greensboro/High Point Rd.) Over Bull Run Creek						GROUND WTR (ft)								
BORING NO. B2-B		STATION 155+30		OFFSET 47 ft RT		ALIGNMENT -L-								
COLLAR ELEV. 716.2 ft		TOTAL DEPTH 18.2 ft		NORTHING 815,631		EASTING 1,725,924								
DRILL RIG/HAMMER EFF./DATE CME-55				DRILL METHOD SPT Core Boring		HAMMER TYPE Automatic								
DRILLER Contract Driller		START DATE 03/31/09		COMP. DATE 03/31/09		SURFACE WATER DEPTH N/A								
CORE SIZE NQ		TOTAL RUN 14.8 ft												
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN REC. (ft) % RQD (ft) %		SAMP. NO.	STRATA REC. (ft) % RQD (ft) %		L O G	DESCRIPTION AND REMARKS			
712.8											Begin Coring @ 3.4 ft			
710	712.8	3.4	4.8	N=60/0.0 4:54/1.0 3:58/1.0 3:17/1.0 2:56/1.0 2:16/0.8	(4.0) 83%	(3.9) 81%	RS-2	(8.8) 90%	(8.7) 89%		712.8	CRYSTALLINE ROCK	3.4	
		708.0	8.2										Green, Fresh, Very Hard, Moderately Close to Wide Fracture Spacing, Massive, Aphanitic, Diabase REC=90% RQD=89% RMR=72	
705			5.0	2:41/1.0 2:36/1.0 2:51/1.0 2:32/1.0 2:30/1.0	(4.8) 96%	(4.8) 96%						703.0		13.2
		703.0	13.2					(5.0) 100%	(5.0) 100%				Gray, Fresh, Very Hard, Wide Fracture Spacing, Massive, Phaneritic, Diorite REC=90% RQD=89% RMR=72	
700			5.0	2:51/1.0 2:53/1.0 3:20/1.0 3:10/1.0 3:10/1.0	(5.0) 100%	(5.0) 100%					698.0		18.2	
	698.0	18.2									Boring Terminated at Elevation 698.0 ft in Crystalline Rock (Diorite)			

NCDOT BORE DOUBLE U2412A GEO BH.GPJ NC DOT.GDT 1/30/18

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Mohs, N. D.				
SITE DESCRIPTION Structures No. 5 & 6 on -L- (SR 4121, Greensboro/High Point Rd.) Over Bull Run Creek									GROUND WTR (ft)				
BORING NO. B2-D			STATION 155+46			OFFSET 23 ft RT			ALIGNMENT -L-			0 HR. N/A	
COLLAR ELEV. 716.3 ft			TOTAL DEPTH 4.9 ft			NORTHING 815,658			EASTING 1,725,935			24 HR. 2.0	
DRILL RIG/HAMMER EFF./DATE CME-55						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic				
DRILLER Contract Driller			START DATE 04/01/09			COMP. DATE 04/01/09			SURFACE WATER DEPTH N/A				
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			
720													
	716.3	0.0	3	0	1								716.3 GROUND SURFACE 0.0
715	713.3	3.0	WOH			6	11						712.6 3.7
	711.4	4.9	60/0.0			60/0.0							711.4 4.9
Brown, Sandy Silt and Gravel													
Boring Terminated with Standard Penetration Test Refusal at Elevation 711.4 ft on Crystalline Rock (Diabase)													

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1				TIP U-2412A				COUNTY Guilford				GEOLOGIST Milkovits, J. I.					
SITE DESCRIPTION Structures No. 5 & 6 on -L- (SR 4121, Greensboro/High Point Rd.) Over Bull Run Creek												GROUND WTR (ft)					
BORING NO. EB2-A				STATION 156+90				OFFSET 55 ft LT				ALIGNMENT -L-				0 HR. Dry	
COLLAR ELEV. 752.3 ft				TOTAL DEPTH 18.4 ft				NORTHING 815,759				EASTING 1,726,064				24 HR. Dry	
DRILL RIG/HAMMER EFF./DATE CME-55								DRILL METHOD H.S. Augers				HAMMER TYPE Automatic					
DRILLER Contract Driller				START DATE 09/22/08				COMP. DATE 09/22/08				SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)		
755																	
	752.3	0.0												752.3	0.0	GROUND SURFACE	
750			1	4	8						SS-154	M		RESIDUAL Tan-Brown, Silty Sand			
	748.8	3.5	16	30	46						SS-155	M					
745														745.3	7.0	WEATHERED ROCK (Diorite)	
	743.8	8.5	41	59/0.4													
740																	
	738.8	13.5	100/0.4														
735																	
	734.0	18.3	60/0.1											734.0 733.9	18.3 18.4	CRYSTALLINE ROCK (Diorite) Boring Terminated with Standard Penetration Test Refusal at Elevation 733.9 ft in Crystalline Rock (Diorite)	

WBS 34802.1.1				TIP U-2412A		COUNTY Guilford		GEOLOGIST Mohs, N. D.							
SITE DESCRIPTION Structures No. 5 & 6 on -L- (SR 4121, Greensboro/High Point Rd.) Over Bull Run Creek										GROUND WTR (ft)					
BORING NO. EB2-B			STATION 156+35			OFFSET 55 ft RT		ALIGNMENT -L-		0 HR.	Dry				
COLLAR ELEV. 749.1 ft			TOTAL DEPTH 4.6 ft			NORTHING 815,641		EASTING 1,726,028		24 HR.	Dry				
DRILL RIG/HAMMER EFF./DATE CME-55						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic						
DRILLER Contract Driller			START DATE 04/01/09			COMP. DATE 04/01/09		SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
750															
														749.1	GROUND SURFACE 0.0
															RESIDUAL Brown, Sandy Silt
745	745.8	3.3									S-11			745.3	3.8
	744.6	4.5	2	100/0.4										744.6	4.5
			60/0.1											744.5	4.6
															WEATHERED ROCK (Diorite)
															CRYSTALLINE ROCK (Diorite)
															Boring Terminated with Standard Penetration Test Refusal at Elevation 744.5 ft in Crystalline Rock (Diorite)

NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Mohs, N. D.						
SITE DESCRIPTION Structures No. 5 & 6 on -L- (SR 4121, Greensboro/High Point Rd.) Over Bull Run Creek									GROUND WTR (ft)						
BORING NO. EB2-C			STATION 156+70			OFFSET 19 ft LT			ALIGNMENT -L-			0 HR. Dry			
COLLAR ELEV. 752.8 ft			TOTAL DEPTH 12.7 ft			NORTHING 815,720			EASTING 1,726,050			24 HR. Dry			
DRILL RIG/HAMMER EFF./DATE CME-55						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic						
DRILLER Contract Driller			START DATE 04/01/09			COMP. DATE 04/01/09			SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)
755															
	752.8	0.0												752.8	GROUND SURFACE 0.0
750													M	750.8	RESIDUAL 2.0
	749.3	3.5	13	25	45								M		Brown, Sandy Silt
											SS-12				Brown, Saprolitic, Silty Sand
745														745.8	7.0
	744.3	8.5	100/0.3												WEATHERED ROCK (Diorite)
	740.1	12.7	60/0.0											740.1	12.7
														Boring Terminated with Standard Penetration Test Refusal at Elevation 740.1 ft on Crystalline Rock (Diorite)	

WBS 34802.1.1		TIP U-2412A		COUNTY Guilford		GEOLOGIST Mohs, N. D.								
SITE DESCRIPTION Structures No. 5 & 6 on -L- (SR 4121, Greensboro/High Point Rd.) Over Bull Run Creek							GROUND WTR (ft)							
BORING NO. EB2-D		STATION 156+58		OFFSET 19 ft RT		ALIGNMENT -L-		0 HR. Dry						
COLLAR ELEV. 752.4 ft		TOTAL DEPTH 8.5 ft		NORTHING 815,680		EASTING 1,726,045		24 HR. Dry						
DRILL RIG/HAMMER EFF./DATE CME-55				DRILL METHOD H.S. Augers			HAMMER TYPE Automatic							
DRILLER Contract Driller		START DATE 04/01/09		COMP. DATE 04/01/09		SURFACE WATER DEPTH N/A								
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
755														
	752.4	0.0												752.4 GROUND SURFACE 0.0
750			WOH	1	1							M		RESIDUAL Brown, Silty Sand
	749.0	3.4										M		
			14	14	21									
745														
	744.0	8.4												744.0 8.4
			60/0.1											743.9 8.5
														CRYSTALLINE ROCK (Diorite)
														Boring Terminated with Standard Penetration Test Refusal at Elevation 743.9 ft in Crystalline Rock (Diorite)

NCDOT BORE DOUBLE U2412A_GEO_BH.GPJ NC_DOT.GDT 1/30/18

EB1-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-4	55 LT	154+22	3.5-5.0	A-7-6(15)	41	22	13.1	14.9	29.8	42.3	99	91	75	-	-
SS-5	55 LT	154+22	8.5-10.5	A-4(0)	35	NP	12.9	47.7	31.4	8.0	100	97	50	-	-

EB1-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-3	68 RT	153+32	2.8-4.3	A-4(0)	25	6	33.8	26.8	19.3	20.1	97	78	41	-	-

EB1-C

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-1	23 RT	153+65	3.2-4.7	A-4(0)	25	7	31.6	33.6	16.7	18.1	98	79	39	-	-
SS-2	23 RT	153+65	8.2-9.7	A-1-b(0)	20	NP	49.7	25.4	16.9	8.0	58	37	17	-	-

B1-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-7	47 RT	154+16	9.0-10.5	A-2-4(0)	28	NP	51.3	24.9	15.7	8.0	92	56	27	-	-

B1-C

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-6	23 RT	154+28	0.0-1.5	A-2-4(0)	24	NP	47.9	33.2	12.9	6.0	98	77	22	-	-

B2-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
S-8	47 LT	155+73	0.0-3.7	A-3(0)	29	NP	37.9	55.5	2.6	4.0	100	96	9	-	-
SS-9	47 LT	155+73	8.7-10.2	A-1-b(0)	22	2	42.2	24.6	21.0	12.1	50	35	19	-	-

B2-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-10	47 RT	155+30	0.0-1.5	A-4(0)	27	6	23.0	23.4	31.3	22.2	79	67	47	-	-

EB2-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-154	55 LT	156+90	0.0-1.5	A-2-4(0)	26	NP	47.3	25.6	15.1	12.0	92	61	29	-	-
SS-155	55 LT	156+90	3.5-5.0	A-2-4(0)	25	4	49.5	23.9	13.5	13.0	93	60	29	-	-

EB2-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
S-11	55 RT	156+35	0.0-3.8	A-4(2)	29	5	16.0	23.0	36.8	24.2	97	87	66	-	-

EB2-C

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200		
SS-12	19 LT	156+70	3.5-5.0	A-2-4(0)	23	3	40.6	28.2	19.1	12.1	95	71	34	-	-

ROCK TEST RESULTS									
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	H/D RATIO	UNIT WT lbs/ft3	Ultimate lbf	Ultimate ksi	Ultimate (corrected) ksi	Sec. Mod. @ 40% Mpsi
RS-1	47 LT	155+73	15.0-15.5	2.44	168.3	65600	23.9	24.4	8.47
RS-2	47 RT	155+30	4.4-5.2	.717	629	92400	33.7	27.7	13.13
RS-3	47 LT	154+59	15.3-16.1	.701	629	92200	33.6	27.5	11.04
RS-4	47 RT	154+16	19.5-20.1	2.41	166.4	69600	25.4	25.9	0.27

PROJECT: 34802.1.1 ID: U-2412A

CONTENTS

SHEET	DESCRIPTION
1	TITLE SHEET
2	LEGEND
3	SITE PLAN
4	PROFILE
5, 6	CROSS SECTIONS
7-10	BORE LOGS & CORE REPORT
11	SOIL TEST RESULTS
12	CORE PHOTOGRAPHS
13	SITE PHOTOGRAPH

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

PROJ. REFERENCE NO. 34802.1.1 (U-2412A) F.A. PROJ. STP-4121(1)
COUNTY GUILFORD
PROJECT DESCRIPTION GREENSBORO/HIGH POINT RD. FROM
PROPOSED US 311 BYPASS TO WEST OF SR 1480

SITE DESCRIPTION STRUCTURE NO. 7 ON -Y8- (SR 1352, OAKDALE
RD.) OVER -L- (GREENSBORO/HIGH POINT RD.) AT STATION
14 + 98

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	34802.1.1 (U-2412A)	1	13

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING, AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 250-4088. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA ARE PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE, THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

PERSONNEL
N.D. MOHS
MACTEC
INVESTIGATED BY N.D. MOHS
CHECKED BY N.T. ROBERSON
SUBMITTED BY N.T. ROBERSON
DATE APRIL 2009

DocuSigned by:
Neil Roberson
4061D9A8C6C649C...
1/23/2018

NORTH CAROLINA
LICENSED
SEAL
1912
GEOLOGIST
NEIL T. ROBERSON

DRAWN BY: N.D. MOHS


NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.



GROUNDLINE PROFILE AT CL OF -Y8- TAKEN FROM ROADWAY DESIGN PLANS AS OF 2/23/2009.
INFERRED STRATIGRAPHY IS DRAWN THROUGH THE BORINGS WITH BOTH PROJECTED ONTO THE PROFILE.


02040
FEET
VE = 2:1

PROJECT REFERENCE NO.	SHEET
34802.1.1 (U-2412A)	4
PROFILE OF BORINGS ON -Y8-	



Ⓐ WEATHERED ROCK (DIABASE)





GEOTECHNICAL BORING REPORT
BORE LOG

WBS 34802.1.1				TIP U-2412A				COUNTY Guilford				GEOLOGIST Mohs, N. D.					
SITE DESCRIPTION Structure NO. 7 on -Y8- (SR 1352, Oakdale Rd.) over -L- (Greensboro/High Point Rd.) at Sta. 14+98												GROUND WTR (ft)					
BORING NO. EB1-A				STATION 13+88				OFFSET 45 ft LT				ALIGNMENT -Y8-				0 HR. Dry	
COLLAR ELEV. 786.2 ft				TOTAL DEPTH 29.7 ft				NORTHING 815,626				EASTING 1,725,169				24 HR. Dry	
DRILL RIG/HAMMER EFF./DATE CME-55								DRILL METHOD H.S. Augers				HAMMER TYPE Automatic					
DRILLER Contract Driller				START DATE 03/23/09				COMP. DATE 03/23/09				SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)		
790																	
785																	
780	782.2	4.0		5	11	14						SS-4	M		786.2	GROUND SURFACE 0.0	
775	777.2	9.0		5	7	12						SS-5	M		778.9	7.3	
770	772.2	14.0		5	14	19							M		773.9	12.3	
765	767.2	19.0		10	14	33							M				
760	762.2	24.0		15	38	19							M		760.7	25.5	
	757.2	29.0															
	756.5	29.7	100/0.3				100/0.3								756.5	29.7	
			60/0.0				60/0.0								Boring Terminated with Standard Penetration Test Refusal at Elevation 756.5 ft On Crystalline Rock (Diorite)		

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Milkovits, J. I.					
SITE DESCRIPTION Structure NO. 7 on -Y8- (SR 1352, Oakdale Rd.) over -L- (Greensboro/High Point Rd.) at Sta. 14+98									GROUND WTR (ft)					
BORING NO. EB1-B			STATION 13+95			OFFSET 24 ft RT			ALIGNMENT -Y8-			0 HR. Dry		
COLLAR ELEV. 787.9 ft			TOTAL DEPTH 14.3 ft			NORTHING 815,603			EASTING 1,725,103			24 HR. Dry		
DRILL RIG/HAMMER EFF./DATE CME-55						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER Contract Driller			START DATE 09/23/08			COMP. DATE 09/23/08			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
790														
785	787.9	0.0	4	4	4						SS-160	24%		787.9 GROUND SURFACE 0.0
	783.7	4.2	22	26	24						SS-161	M		784.9 RESIDUAL Yellow-Tan, Silty Clay 3.0
780														
	778.7	9.2	25	75/0.3										778.7 Yellow-Tan, Silty Sand 9.2
775														
	773.7	14.2	60/0.1											773.7 WEATHERED ROCK (Diorite) 14.2
														773.6 CRYSTALLINE ROCK (Diorite) 14.3
Boring Terminated with Standard Penetration Test Refusal at Elevation 773.6 ft In Crystalline Rock (Diorite)														

NCDOT BORE DOUBLE U2412A_GEO_BH_Y8.GPJ NC_DOT.GDT 1/22/18

GEOTECHNICAL BORING REPORT

BORE LOG

WBS 34802.1.1				TIP U-2412A				COUNTY Guilford				GEOLOGIST Mohs, N. D.					
SITE DESCRIPTION Structure NO. 7 on -Y8- (SR 1352, Oakdale Rd.) over -L- (Greensboro/High Point Rd.) at Sta. 14+98												GROUND WTR (ft)					
BORING NO. B1-A				STATION 14+98				OFFSET 36 ft LT				ALIGNMENT -Y8-				0 HR. Dry	
COLLAR ELEV. 783.6 ft				TOTAL DEPTH 18.5 ft				NORTHING 815,518				EASTING 1,725,187				24 HR. Dry	
DRILL RIG/HAMMER EFF./DATE CME-55								DRILL METHOD H.S. Augers				HAMMER TYPE Automatic					
DRILLER Contract Driller				START DATE 03/23/09				COMP. DATE 03/23/09				SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)		
785																	
														783.6	GROUND SURFACE 0.0		
780	780.2	3.4	6	9	19												
														778.6	RESIDUAL Orange, Silty Clay 5.0		
775	775.2	8.4															
			100/0.2														
770	770.2	13.4															
			100/0.2														

NCDOT BORE DOUBLE U2412A_GEO_BH_Y8.GPJ NC_DOT.GDT 1/22/18

NC DOT BORE DOUBLE U2412A_GEO_BH_Y8.GPJ NC_DOT.GDT 1/22/18

WBS 34802.1.1			TIP U-2412A			COUNTY Guilford			GEOLOGIST Mohs, N. D.					
SITE DESCRIPTION Structure NO. 7 on -Y8- (SR 1352, Oakdale Rd.) over -L- (Greensboro/High Point Rd.) at Sta. 14+98									GROUND WTR (ft)					
BORING NO. EB2-B			STATION 16+00			OFFSET 38 ft RT			ALIGNMENT -Y8-			0 HR. Dry		
COLLAR ELEV. 784.7 ft			TOTAL DEPTH 38.6 ft			NORTHING 815,400			EASTING 1,725,141			24 HR. Dry		
DRILL RIG/HAMMER EFF./DATE CME-55						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER Contract Driller			START DATE 03/23/09			COMP. DATE 03/23/09			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
785														GROUND SURFACE 0.0
780	781.2	3.5	5	7	9						SS-1	M		RESIDUAL Orange and Brown, Saprolitic, Sandy Clay
775	776.2	8.5	9	11	11							M		
770	771.2	13.5	4	5	8						SS-2	M		Gray, Saprolitic, Sandy Silt 11.8
765	766.2	18.5	4	7	9							M		
760	761.2	23.5	11	19	34							M		
755	756.2	28.5	32	68/0.2										WEATHERED ROCK (Diorite) 28.5
750	751.2	33.5	100/0.4											
	746.2	38.5	60/0.1											CRYSTALLINE ROCK (Diorite) 38.5
														Boring Terminated with Standard Penetration Test Refusal at Elevation 746.1 ft in Crystalline Rock (Diorite)

EB1-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200	MOISTURE	ORGANIC
SS-4	45 LT	13+88	4.0-5.5	A-2-6(1)	38	19	48.6	19.5	13.8	18.1	82	51	29	-	-
SS-5	45 LT	13+88	9.0-10.5	A-6(5)	36	13	22.5	25.3	30.1	22.1	96	84	55	-	-

EB1-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200	MOISTURE	ORGANIC
SS-160	24 RT	13+95	0.0-1.5	A-7-6(11)	43	23	27.3	16.2	12.4	44.1	97	80	58	24	-
SS-161	24 RT	13+95	4.2-5.7	A-2-4(0)	28	7	50.7	21.3	12.9	15.0	90	56	29	-	-

B1-A

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200	MOISTURE	ORGANIC
SS-3	36 LT	14+98	3.4-4.9	A-7-6(5)	42	21	32.6	26.5	16.8	24.1	100	81	45	-	-


EB2-B

SOIL TEST RESULTS															
SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS.	L.L.	P.I.	% BY WEIGHT				% PASSING (SIEVES)			%	%
							C.SAND	F.SAND	SILT	CLAY	10	40	200	MOISTURE	ORGANIC
SS-1	38 RT	16+00	3.5-5.0	A-6(11)	38	13	1.8	24.1	47.9	26.1	100	99	82	-	-
SS-2	38 RT	16+00	13.5-15.0	A-4(5)	36	9	12.3	30.2	43.5	14.1	100	97	65	-	-

CORE PHOTOGRAPH


B1-B

BOX 1: 40.7 - 44.7 FEET



Site Photograph

Structure No. 7 on -Y8- (SR 1352, Oakdale Rd.) over-L- (Greensboro/High Point Rd.) at Sta. 14+98



Looking East

REFERENCE: U-2412A

PROJECT: 34802

CONTENTS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	LEGEND (SOIL & ROCK)
3	SITE PLAN
4-5	MSE RETAINING WALL ENVELOPES
6-8	BORE LOGS

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

COUNTY GUILFORD

PROJECT DESCRIPTION FOR BRIDGE OVER NSRR &
DEEP RIVER TRIBUTARY ON SR 4121 BETWEEN
SR 1332 AND SR 1334

SITE DESCRIPTION MSE WALL AT SITE 1, END BENT 1

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	U-2412A	1	8

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT, AT (919) 707-6850. THE SUBSURFACE PLANS AND REPORTS, FIELD BORING LOGS, ROCK CORES AND SOIL TEST DATA ARE NOT PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THE PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

- NOTES:
- THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS ACCURATE NOR IS IT CONSIDERED PART OF THE PLANS, SPECIFICATIONS OR CONTRACT FOR THE PROJECT.
 - BY HAVING REQUESTED THIS INFORMATION, THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

- PERSONNEL
- M. ELLIS, E.I.
- K. PLUMMER
- N. MCLAREN
- S. CARPENTER
- M&W DRILLING
- HPC

INVESTIGATED BY ECS SOUTHEAST, LLP

DRAWN BY M. BREWER, P.E.


CHECKED BY M. WALKO, P.E.

SUBMITTED BY ECS SOUTHEAST, LLP

DATE MAY 2018


Prepared in the Office of:

 ECS SOUTHEAST, LLP
1812 CENTER PARK DRIVE, SUITE D
CHARLOTTE, NC 28217
(704) 525-5152 [PHONE]
(704) 357-0023 [FAX]
NC REGISTERED
ENGINEERING
FIRM # F-1078



DocuSigned by:
EC2ABBE99DB48C...
5/17/2018
SIGNATURE DATE


DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED



PROJECT REFERENCE NO. SHEET NO.

U-2412A 3

SITE PLAN




STRUCTURE NO. 270 & 271 ON SR 4121 OVER NSRR AND UNNAMED TRIBUTARY TO DEEP RIVER


MSE WALL AT SITE 1: END BENT 1
END BENT 1 SKEW = 108 DEGREES

6/23/16

04-MAY-2018 15:29
1:200 OF E:\PROJECTS\12000-12999\12600\12612-A - U-2412A Structure No. 270 and No. 271 MSE Retaining Wall\U-2412A-GEO.RWAL_PFL1.5.dgn



Prepared in the Office of:
EGS SOUTHEAST, LLP
1812 CENTER PARK DRIVE, SUITE D
CHARLOTTE, NC 28217
(704) 533-5151 (PHONE)
(704) 537-0023 (FAX)
NC REGISTERED
ENGINEERING
FIRM # E-1076



PROJ. REFERENCE NO.	SHEET NO.
U-2412A	5
MSE RETAINING WALL AT END BENT 1 (LT) END BENT 1 SKEW: 108 DEGREES	

WBS 34802.1.1		TIP U-2412A		COUNTY GUILFORD		GEOLOGIST M. Ellis							
SITE DESCRIPTION Bridge No. 270 (WBL) on SR 4121 over NSRR and Unnamed Deep River Tributary							GROUND WTR (ft)						
BORING NO. EB1-A (LL)		STATION 90+15		OFFSET 55 ft LT		ALIGNMENT -L-		0 HR. Dry					
COLLAR ELEV. 785.7 ft		TOTAL DEPTH 19.7 ft		NORTHING 814,693		EASTING 1,719,564		24 HR. Dry					
DRILL RIG/HAMMER EFF./DATE HPC2473 CME-550 85% 01/10/2018				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic							
DRILLER J. Cain		START DATE 04/26/18		COMP. DATE 04/26/18		SURFACE WATER DEPTH N/A							
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			
790													
785	785.7	0.0	1	1	2								785.7 GROUND SURFACE 0.0
780	782.2	3.5	10	18	49							M	782.7 RESIDUAL Soft, Brown-Orange, Fine Sandy CLAY (A-6) 3.0
	779.7	6.0	37	63/0.4								M	779.7 Hard, Brown-Green, Fine to Coarse Sandy SILT (A-4), with trace gravel-sized quartz fragments 6.0
	777.2	8.5	33	57	43/0.3								WEATHERED ROCK Gray-Brown-Green, (METAMORPHOSED GRANITIC ROCK)
775													773.7 RESIDUAL Very Dense, Gray-Green-Brown, Silty Fine to Coarse SAND (A-2-4) 12.0
770	772.2	13.5	16	21	56							M	
	767.2	18.5											767.2 WEATHERED ROCK Gray-Green, (METAMORPHOSED GRANITIC ROCK) 18.5
	766.0	19.7	100/0.2										766.0 WEATHERED ROCK Gray-Green, (METAMORPHOSED GRANITIC ROCK) 19.7
													Boring Terminated with Standard Penetration Test Refusal at Elevation 766.0 ft On Crystalline Rock (METAMORPHOSED GRANITIC ROCK)

NCDOT BORE DOUBLE U2412A_GEO_BORELOGS.GPJ NC_DOT.GDT 5/4/18

WBS		34802.1.1		TIP		U-2412A		COUNTY		GUILFORD		GEOLOGIST		M. Ellis						
SITE DESCRIPTION												Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary				GROUND WTR (ft)				
BORING NO.		EB1-A (RL)		STATION		89+91		OFFSET		19 ft RT		ALIGNMENT		-L-		0 HR.	Dry			
COLLAR ELEV.		783.8 ft		TOTAL DEPTH		24.6 ft		NORTHING		814,623		EASTING		1,719,529		24 HR.	21.5			
DRILL RIG/HAMMER EFF./DATE								HPC2473 CME-550 85% 01/10/2018				DRILL METHOD				H.S. Augers		HAMMER TYPE	Automatic	
DRILLER				J. Cain		START DATE		04/26/18		COMP. DATE		04/26/18		SURFACE WATER DEPTH				N/A		
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI L O G	SOIL AND ROCK DESCRIPTION							
			0.5ft	0.5ft	0.5ft	0	25	50	75	100										
785																				
	783.8	0.0		WOH	1	2								783.8	GROUND SURFACE			0.0		
															RESIDUAL					
															Soft, Brown-Orange, Fine Sandy CLAY (A-6)					
780	780.3	3.5		8	13	14							W		780.8				3.0	
															Very Stiff to Hard, Brown, Fine to Coarse					
	777.8	6.0		21	28	47							M			Sandy SILT (A-4), with trace gravel-sized				
															rock fragments					
775	775.3	8.5		100/0.3									M		775.3				8.5	
															WEATHERED ROCK					
															Tan-Brown-Gray, (METAMORPHOSED					
															GRANITIC ROCK)					
770	770.3	13.5		64	36/0.1															
765	765.3	18.5		7	10	21														

NC DOT BORE DOUBLE U2412A GEO_BORELOGS.GPJ NC_DOT.GDT 5/4/18

WBS 34802.1.1		TIP U-2412A		COUNTY GUILFORD		GEOLOGIST S. Carpenter																
SITE DESCRIPTION Bridge No. 271 (EBL) on SR 4121 over NSRR and Unnamed Deep River Tributary							GROUND WTR (ft)															
BORING NO. RW-2		STATION 89+29		OFFSET 46 ft RT		ALIGNMENT -L-		0 HR. Dry														
COLLAR ELEV. 784.8 ft		TOTAL DEPTH 18.1 ft		NORTHING 814,607		EASTING 1,719,463		24 HR. Dry														
DRILL RIG/HAMMER EFF./DATE M&W1491 Diedrich D-120-029 95% 06/02/2017				DRILL METHOD H.S. Augers			HAMMER TYPE Automatic															
DRILLER B. Snow			START DATE 02/02/18		COMP. DATE 02/02/18		SURFACE WATER DEPTH N/A															
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION									
			0.5ft	0.5ft	0.5ft	0	25	50	75	100												
785	784.8	0.0	1	1	3							M	784.8	GROUND SURFACE	0.0							
	781.3	3.5	5	3	7													781.8	ARTIFICIAL FILL Soft, Red-Brown, Fine to Coarse Sandy SILT (A-4)	3.0		
780	778.8	6.0	20	29	32														778.8	RESIDUAL Stiff, Red-Brown, Clayey SILT (A-5)	6.0	
	776.3	8.5	17	34	48															770.8	Hard, Orange-Brown, Fine Sandy SILT (A-4)	14.0
775	771.3	13.5	30	55	45/0.3															766.8	WEATHERED ROCK Orange-Brown (METAMORPHOSED GRANITIC ROCK)	18.0
770	766.8	18.0	60/0.1											766.7	CRYSTALLINE ROCK (METAMORPHOSED GRANITIC ROCK)	18.1						
														Boring Terminated with Standard Penetration Test Refusal at Elevation 766.7 ft In Crystalline Rock (METAMORPHOSED GRANITIC ROCK)								
														Notes: Surficial Organics Soils from 0.0 to 0.2 ft. Weathered and Crystalline Rock Boulders / Outcrops were observed in the Railroad Cut.								