



GENERAL NOTE:
 AFTER ALL NEW CABLES ARE INSTALLED AND THE SYSTEM INTERSECTIONS ARE OPERATING, REMOVE THE EXISTING CABLES LABELED "REM". PRIOR TO REMOVING, COORDINATE THESE ACTIVITIES WITH PWC.
 PWC CONTACT: DARLENE GOODHART AT (910) 223-4526.

- | | |
|--|---|
| <ul style="list-style-type: none"> 1 INSTALL REA, PE - 22, SHIELDED, TWISTED PAIR COMMUNICATIONS CABLE 2 INSTALL REA, PE - 38, (FIGURE - 8) SHIELDED, TWISTED PAIR COMMUNICATIONS CABLE 3 INSTALL 3-CONDUCTOR, CLASS B, STRANDED UNDERGROUND POWER CABLE 4 INSTALL SMFO CABLE 5 INSTALL WEATHERPROOF CATEGORY 5e UTP - 4 PAIR 23 AWG CABLE (PoE) 6 INSTALL FIBER OPTIC DROP CABLE 7 INSTALL TRACER WIRE 8 TRENCH 9 INSTALL PVC CONDUIT 10 INSTALL RIGID, GALVANIZED STEEL CONDUIT 11 INSTALL RIGID, GALVANIZED STEEL RISER WITH WEATHERHEAD 12A INSTALL RIGID, GALVANIZED STEEL RISER WITH FIBER OPTIC CABLE SEAL 12B INSTALL CABLES/DROP CABLE THROUGH NIPPLE ON METAL POLE (SIGNAL OR JOINT USE). INSTALL HEAT SHRINK TUBING OVER NIPPLE. 13 INSTALL OUTER-DUCT POLYETHYLENE CONDUIT 14 INSTALL POLYETHYLENE CONDUIT 15 DIRECTIONAL DRILL CONDUIT 16 BORE AND JACK CONDUIT 17 INSTALL CABLE(S) IN EXISTING CONDUIT 18 INSTALL CABLE(S) IN NEW CONDUIT 19 INSTALL CABLE(S) IN EXISTING RISER 20 INSTALL CABLE(S) IN NEW RISER 21 INSTALL CABLE(S) IN EXISTING CONDUIT STUBOUTS 22 INSTALL NEW CONDUIT INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE) 23 INSTALL NEW RISER INTO EXISTING CABINET BASE (USE EXISTING CONDUIT STUB-OUTS WHEN AVAILABLE) 24 INSTALL NEW CONDUIT INTO EXISTING POLE MOUNTED CABINET 25 INSTALL NEW RISER INTO EXISTING POLE MOUNTED CABINET 26 TERMINATE COMMUNICATIONS CABLE ON EXISTING TELEMETRY INTERFACE PANEL IN TRAFFIC SIGNAL CONTROLLER CABINET 27 INSTALL NEW TELEMETRY INTERFACE PANEL IN TRAFFIC SIGNAL CONTROLLER CABINET 28 INSTALL INTERCONNECT CENTER, PATCH PANEL, JUMPERS, AND FUSION SPICE CABLE IN CABINET 29 INSTALL UNDERGROUND SPICE ENCLOSURE 30 INSTALL AERIAL SPICE ENCLOSURE 31 INSTALL POLE MOUNTED CABINET 32 INSTALL BASE MOUNTED SPICE CABINET (336) WITH EXTEND BASE 33 REMOVE EXISTING SPICE CABINET 34 INSTALL CABINET FOUNDATION 35 REMOVE EXISTING CABINET FOUNDATION 36 INSTALL CCTV CAMERA ASSEMBLY 37 INSTALL CCTV CAMERA WOOD POLE 38 INSTALL CCTV CAMERA METAL POLE AND FOUNDATION 39 INSTALL JUNCTION BOX 40 INSTALL OVERSIZED JUNCTION BOX 41 REMOVE EXISTING JUNCTION BOX 42 INSTALL WOOD POLE 43 REMOVE EXISTING WOOD POLE 44 INSTALL AERIAL GUY ASSEMBLY 45 INSTALL STANDARD GUY ASSEMBLY 46 INSTALL SIDEWALK GUY ASSEMBLY 47 INSTALL MESSENGER CABLE 48 REMOVE EXISTING COMMUNICATIONS CABLE AND MESSENGER CABLE 49 REMOVE EXISTING COMMUNICATIONS CABLE 50 INSTALL ETHERNET SWITCH 51 INSTALL CABLE STORAGE RACKS (SNOW SHOES) AND STORE 100 FEET OF CABLE 52 INSTALL DELINEATOR MARKER 53 STORE 50 FEET OF COMMUNICATIONS CABLE 54 LASH CABLE(S) TO EXISTING PWC FIBER OPTIC LINE 55 LASH CABLE(S) TO EXISTING MESSENGER CABLE 56 LASH CABLE(S) TO NEW MESSENGER CABLE 57 MODIFY EXISTING ELECTRICAL SERVICE 58 INSTALL NEW ELECTRICAL SERVICE FOR DMS/CCTV 59 INSTALL NEW BASE MOUNTED CABINET (336) 60 SEAL ALL CONDUIT ENTERING JUNCTION BOXES AND SIGNAL/CCTV/DMS CONTROL CABINETS WITH MOLDABLE DUCT SEAL | <ul style="list-style-type: none"> 61 ROUTE CABLE(S) INSIDE METAL POLE AND OUT TO SIGNAL CABINET. USE EXISTING JUNCTION BOXES AND CONDUIT SYSTEMS WHEN AVAILABLE. ENSURE FIBER CABLES DO NOT SHARE JUNCTION BOXES AND CONDUIT SYSTEMS WITH SIGNAL CABLES OR OTHER 120 VOLT CURRENT CARRYING CONDUCTORS. 62 INSTALL TEMPORARY DROP CABLE MAINTENANCE LOOP WITH CABLE BRACKET |
|--|---|

Stantec Consulting Services Inc.
 801 Jones Franklin Road
 Suite 300
 Raleigh, NC 27606
 Tel. (919) 851-6866
 Fax. (919) 851-7024
 www.stantec.com
 License No. F-0672

PHASE II FIBER TRUNK CABLE INSTALLATION

<p>Prepared for the Offices of:</p> <p>750 N. Greenfield Plaza, Garner, NC 27529</p>	<p>US 401 BUSINESS (RAEFORD ROAD) SIGNAL SYSTEM AND COMMUNICATIONS CABLE / CONDUIT ROUTING PLANS</p> <p>DIVISION 06 CUMBERLAND CO. FAYETTEVILLE</p> <p>PLAN DATE: MARCH 2018 REVIEWED BY: D. HARRIS</p> <p>PREPARED BY: J. INGRAM REVIEWED BY: B. WATSON</p>	<p>SEAL</p> <p>Lawrence E. Overton 3/29/2018</p>						
<p>SCALE NTS</p>	<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>REVISIONS</th> <th>INIT.</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	REVISIONS	INIT.	DATE				<p>DocuSigned by: </p> <p>CADD FILE NAME</p>
REVISIONS	INIT.	DATE						

3/27/2018 11:00:17 AM j:ingram